

A134 265-

D

ALL THE COPY

DTIC
ELECTE
S NOV 2 1983 D

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

88 11 01 025

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
		A134265
4. TITLE (and Subtitle) MISSISSIPPI RIVER STUDY OF ALTERNATIVES FOR REHABILITATION OF LOCK AND DAM NO. 1, Minneapolis, Minnesota. Supporting data for Appendix C, structural investigations.		5. TYPE OF REPORT & PERIOD COVERED Design memorandum
7. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER
		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS Army Engineer District, St. Paul 1135 USPO & Custom House St. Paul, MN 55101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS		12. REPORT DATE April, 1976
		13. NUMBER OF PAGES
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report)
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. ABSTRACT (of the abstract entered in Block 20, if different from Report)		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) LOCKS (WATERWAYS) INLAND WATERWAYS MISSISSIPPI RIVER STRUCTURAL ENGINEERING		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) It is recommended that both the landward lock, the riverward lock and the dam at Lock & Dam no. 1, Minneapolis, Minnesota be completely rehabilitated. Based on studies completed to the date of this report, more detailed studies are required to firmly establish cost estimates, environmental effects, and the construction scheduling necessary to insure the work can be completed in the proposed two year construction period without delaying navigation.		

DEPARTMENT OF THE ARMY
ST. PAUL DISTRICT, CORPS OF ENGINEERS
1210 U.S. Post Office & Custom House
St. Paul, Minnesota 55101

MISSISSIPPI RIVER
STUDY OF ALTERNATIVES FOR REHABILITATION OF LOCK AND DAM NO. 1
MINNEAPOLIS, MINNESOTA

SUPPORTING DATA
FOR
APPENDIX C
STRUCTURAL INVESTIGATIONS



Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	STRUCTURAL INVESTIGATIONS	PROJECT	LOCK & DAM NO. 1
		COMPUTATIONS	FILE NO.	800A
	COMPUTED	R. V. M.	CHECKED	
			DATE	4/21/75 PAGE 1 OF 1 PAGES

COMPUTATIONSTABLE OF CONTENTS:

	PAGE
SUMMARY OF STRUCTURAL INVESTIGATIONS	-
PENETRATION TESTS AT BORE HOLES	1
LATERAL EARTH PRESSURE	2
UPPER GUIDE WALL MONOLITHS:	
NOS 1 - 7 NORMAL OPERATING	4 - 6
NOS 1 - 5 CONSTRUCTION	7 - 8
NOS 8 - 13 NORMAL OPERATING	9 - 11
LAND WALL MONOLITHS:	
NOS 5 - 15 NORMAL OPERATING	12 - 16
NO. 3 NORMAL OPERATING (PRESENT)	17 - 18
NO. 3 CONSTRUCTION	19 - 21
NO. 3 NORMAL OPERATING (AFTER CONST.)	22 - 24
NO. 4 CONSTRUCTION	25 - 28
NO. 4 NORMAL OPERATING (AFTER CONST.)	29
NO. 17 NORMAL OPERATING	30 - 34
LOWER GUIDE WALL MONOLITHS:	
N.O. 1 NORMAL OPERATING	35 - 38
NOS 3 - 13 NORMAL OPERATING	39 - 48
NOS 6 - 12 CONSTRUCTION	49 - 50
INTERMEDIATE WALL MONOLITHS:	
NOS 4 - 16 NORMAL OPERATING	51 - 54
NO. 4 CONSTRUCTION (PLAN 2)	55 - 57
NO. 5 CONSTRUCTION (PLAN 2)	58 - 61
NO. 18 NORMAL OPERATING	62 - 67

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	STRUCTURAL INVESTIGATIONS	PROJECT	LOCK & DAM No. 1
		COMPUTATIONS	FILE NO.	800 A
	COMPUTED	R.N.M.	CHECKED	
			DATE	4/21/75 PAGE ii OF _____ PAGES

	PAGE
RIVER WALL MONOLITHS:	
NO. 1 CONSTRUCTION	68-69
NOS 6 - 16 NORMAL	70-95
NOS 6 - 16 CONSTRUCTION OR MAINTENANCE	86
NO. 19 NORMAL OPERATING	87-95
NO. 20 NORMAL OPERATING	96-105

RIVER WALL SLIDING STABILITY AT CLAY SEAM:	106-109
--	---------

LAND WALL MONOLITHS. IMPROVED NORMAL OPERATING:	
NOS 5 - 15 ROCK ANCHORS	109-118
NOS 5 - 15 LOWERED BACKFILL	119-123
NO. 3 LOWERED BACKFILL	124
NO. 4 LOWERED BACKFILL	125
NO. 17 LOWERED BACKFILL	126-127
NO. 17 ROCK ANCHORS	128-130
NO. 17 LOWERED BACKFILL & ROCK ANCHORS	131-132

INTERMEDIATE WALL MONOLITH IMPROVED NORMAL OPERATING:	
NO. 18 VERTICAL ROCK ANCHORS	133-134
NO. 18 INTERCONNECTION OF 17 & 19	135-141
NO. 18 INTERCONNECTION OF 17, 19 & 19.	142-146

RIVER WALL MONOLITHS. IMPROVED NORMAL OPERATING:	
NO. 19 BACKFILLED RIVERSIDE	147-150
NO. 20 INTERCONNECTION OF 20 & 21	151-153
NO. 20 BACKFILLED RIVERSIDE	154-159
NO. 20 19, 20 & 21 INTERCONNECTED	160-166
NO. 20 19, 20 & 21 INTERCONNECTED AND BACKFILL @ RIVERSIDE	167-173

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STRUCTURAL INVESTIGATION</u>	PROJECT <u>LOCK & DAM No 1</u>
	<u>COMPUTATIONS</u>	FILE NO. <u>800A</u>
	COMPUTED <u>R.N.M.</u> CHECKED _____	DATE <u>4/21/75</u> PAGE <u>iii</u> OF _____ PAGES

	<u>PAGE</u>
PILE BEARING CAPACITY	174
BUTTRESS DAM:	
LOADING CONDITIONS AND ASSUMPTIONS	175-177
RESULTS OF STABILITY ANALYSES	178-182
NORMAL OPERATING	183-186
FLOOD DISCHARGE	187-196
EARTH QUAKE	197-200
1951 FLOOD - IMPROVED STABILITY	201-203
COFFERDAMS:	204-205
QUANTITY & COST ESTIMATES:	
SHELTER	206-214
UPPER GUIDE WALL-REMEDIAL PRESSURE GRouting	215
REMOVAL OF BACKFILL BEHIND LAND WALL	216
STABILIZATION OF LAND WALL BY ROCK ANCHORS	217-219
INTERMEDIATE WALL LOWER GATE MONOLITH-SHEAL KEYS	220
BACKFILL BEHIND DOWNSTREAM RIVERWALL MONOLITHS	221-226

MONO-LITH NOS	LOADING CONDITION	ELEV. OF BACKFILL, FT	W.S. ELEV. AT LANDSIDE, FT	W.S. ELEV. AT RIVER-SIDE, FT	LOCATION OF RESULTANT ECCENTRICITY FROM C, FT	±(L/6)
1-7 (L=14.0)	NORMAL OPERATING	732.7	725.2	725.2	3.72	-1
1-6	CONSTRUCTION	732.7	719.7	(EMPTY)	4.22	-1
8-13 (L=18.0)	NORMAL OPERATING	732.7	725.2	725.2	3.40	-0

NOTES:

- SUMMATION OF HORIZONTAL FORCES ONE FOOT STRIP ACROSS EACH
- FACTOR OF SAFETY AGAINST SLIDING TO COEFFICIENT OF FRICTION $f = 0$.
- NEGATIVE SIGN INDICATES LOCATION
- ALL WATER SURFACE (W.S.) ELEVATIONS CONSTRUCTION CONDITION FOR MONO
- FOR 3-DIMENSIONAL ANALYSES @

LOCK AND DAM NO 1 SHEET 1 OF 9 SUMMARY OF STRUCTURAL INVESTIGATIONS

V. LOCATION OF RESULTANT ECCENTRICITY FROM MIDDLE $\frac{1}{3}$ e, FT $\pm(\frac{1}{6}-e)$ FT ③		FOUNDATION PRESSURE, KEF f _{MAX} f _{MIN}		F.S.O.	EH KIPS	EV KIPS	SLIDING FACTOR, EH/EV	F.S.S. ③
UPPER GUIDE WALL								
3.72	-1.39	7.46	0.00	1.43	13	37	.35	1.80
4.22	-1.89	11.34	0.00	1.57	21	47	.44	1.41
3.40	-0.40	4.13	0.00	2.06	11	35	.33	1.90

HORIZONTAL FORCES (EH) AND VERTICAL FORCES (EV) ARE FOR AN AVERAGE
ACROSS EACH MONOLITH.

AGAINST SLIDING (F.S.S.) IS BASED ON $\phi \approx 32^\circ$ CORRESPONDING
FRICTION $f = 0.625$ (FOR DAM; $\phi \approx 33^\circ$, $f = 0.649$)

LOCATES LOCATION OF RESULTANT OUTSIDE OF MIDDLE THIRD

(W.S.) ELEVATIONS FOR INTERMEDIATE WALL ARE INTERCHANGEABLE EXCEPT
TION FOR MONOLITHS 4 & 5

ANALYSES e_x IS ACROSS THE WALL AND e_y ALONG THE WALL

MONO-
LITH
NºS

LOADING CONDITION

ELEV. OF
BACKFILL,
FT

W.S. ELEV.
AT LAND-
SIDE, FT

W.S. ELEV.
AT RIVER-
SIDE, FT

LOCATION OF
ECCENTRICITY FROM
E, FT ±(L)

LAND W

3 (L=32.0')	NORMAL OPERATING (PRESENT)	732.7	704.0	687.2	9.06
3	CONSTRUCTION - ALL REHA- BILITATION PLANS. CONDUIT LOWERED, NO CONC. FILL	724.7	704.0	(EMPTY)	7.47
3	NORMAL OPERATING - AFTER HYDRAULIC IMPROVEMENTS COMPLETED	732.7	704.0	687.2	7.70
3	IMPROVED NORMAL OPERATING - BACKFILL LOWERED BY 8'	724.7	704.0	687.2	5.61
4 (L=32.0')	CONSTRUCTION - ALL REHA- BILITATION PLANS, CONDUIT LOWERED, NO CONC. FILL	722.7	704.0	(EMPTY)	7.44
4	NORMAL OPERATING - AFTER HYDRAULIC IMPROVEMENTS COMPLETED	732.7	704.0	687.2	8.04
4	IMPROVED NORMAL OPERATING - BACKFILL LOWERED BY 10'	722.7	704.0	687.2	5.38

LOCK & DAM No 1
SUMMARY OF STRUCTURAL INVESTIGATION

SHEET 2 OF

Y POSITION OF RESULTANT FOUNDATION
R- ECCENTRICITY FROM MIDDLE PRE.URE, KIP
T e, FT $\pm(\frac{1}{6}-e)$ FT MAX. MIN. H.S.O. ΣH KIPS ΣV KIPS SLIDING FACTOR, $\Sigma H/\Sigma V$ F.S.S. ②

LAND WALL

	9.06	-3.73	13.41	0.00	1.54	85	184	.46	1.36
Y)	7.47	-2.14	13.39	0.00	1.57	75	171	.44	1.49
2	7.70	-2.40	16.10	0.00	1.67	85	201	.42	1.48
	5.61	-0.28	12.60	0.00	2.05	66	196	.34	1.85
Y)	7.44	-2.11	13.40	0.0	1.79	71	172	.41	1.52
2	8.04	-2.63	16.00	0.0	1.62	85	191	.45	1.40
2	5.38	-0.05	11.58	0.00	2.06	62	184	.34	1.86

MONO-LITH NOS	LOADING CONDITION	ELEV. OF BACKFILL, FT	W.S. ELEV. AT LAND-SIDE, FT	W.S. ELEV. AT RIVER-SIDE, FT	LOCATION OF RESULTANT ECCENTRICITY FROM C, FT	LAND WA
5-15 (L=32.0')	NORMAL OPERATING	732.7	700.0	687.2	7.85	
5-15	NORMAL OPERATING	732.7	704.0	687.2	8.56	
5-15	CONSTRUCTION AND MAINTENANCE	732.7	704.0	(EMPTY)	8.50	
5-15	IMPROVED NORMAL OPERATING 1-1 $\frac{3}{8}$ " ϕ BAR TENDON PER ANCHOR SPACED 10 FT	732.7	704.0	687.2	4.86	
5-15	IMPROVED NORMAL OPERATING 2-1 $\frac{1}{4}$ " ϕ BAR TENDONS PER ANCHOR SPACED 15 FT	732.7	704.0	687.2	4.30	
5-15	IMPROVED NORMAL OPERATING 3-1 $\frac{1}{4}$ " ϕ BAR TENDONS PER ANCHOR SPACED 15 FT	732.7	704.0	687.2	2.50	
5-15	IMPROVED NORMAL OPERATING BACKFILL LOWERED BY 10'	722.7	704.0	687.2	6.59	

LOOK AND TALK N.1
SUMMARY OF STRUCTURAL INVESTIGATION

SHEET 3 OF

NO.	LOCATION OF RESULTANT ECCENTRICITY FROM MIDDLE $\frac{1}{3}$ e, FT $\pm(\frac{1}{3}-e)$ FT (3)	FOUNDATION PRESSURE, KSF f MAX f MIN	F.S.O.T	ΣH KIPS	ΣV KIPS	SLIDING FACTOR $\Sigma H/\Sigma V$	F.S.S. (2)
-----	--	--	---------	--------------------	--------------------	--	------------

LAND WALL (CONT'D)

2	7.85	-2.52	16.50	0.00	1.68	85	202	.42	1.49
2	8.56	-3.23	17.74	0.00	1.57	86	198	.43	1.44
1)	8.50	-3.20	18.84	0.00	1.50	98	212	.46	1.35
2	4.86	0.47	12.10	0.60	2.37	72	203	.36	1.76
2	4.30	1.00	12.00	1.30	2.45	70	212	.33	1.89
2	2.50	2.83	9.80	3.60	3.27	63	215	.29	2.16
2	6.59	-1.26	12.33	0.00	1.87	63	174	.36	1.74

MONO-
LITH
NOs

LOADING CONDITION

ELEV. OF
BACKFILL,
FT

W.S. ELEV.
AT LAND-
SIDE, FT

W.S. ELEV.
AT RIVER-
SIDE, FT

LOCATION OF
ECCENTRICITY
E, FT

LAND WALL (CONT)

17
(GATE)
(L=30.0')

NORMAL OPERATING

732.7

700.0

687.2

9.76

17

IMPROVED NORMAL OPERATING
BACKFILL LOWERED BY 10 FT

722.7

700.0

687.2

6.90

17

IMPROVED NORMAL OPERATING
STABILIZED BY $1\frac{3}{8}$ " ϕ ANCHORS
SPACED 10 FT.

732.7

700.0

687.2

6.00

17

IMPROVED NORMAL OPERATING
STABILIZED BY $1\frac{3}{8}$ " ϕ ANCHORS
SPACED 10 FT, BACKFILL
LOWERED BY 10 FT.

722.7

700.0

687.2

3.20

LOWER G

1
(L=18.0')

NORMAL OPERATING

VARIES
FROM 709.7
TO 732.7

687.2

687.2

7.00

3-13
(L=20.0')

NORMAL OPERATING

697.6

687.2

687.2

2.76

6-12

CONSTRUCTION

699.6
(PLUS 3' of
SURFILL)

681.0

(EMPTY)

3.22

LOCK AND DAM NO 1
SUMMARY OF STRUCTURAL INVESTIGATIONS

SHEET 4 OF

NO.	LOCATION OF RESULTANT FROM MIDDLE FT E. FT	$\pm(\frac{L}{6}-e)$ FT	FOUNDATION PRESSURE, KSF f _{MAX} f _{MIN}	F.S.O.T.	ΣH KIPS	ΣY KIPS	SLIDING FACTOR ΣH/ΣY	F.S.S.
<u>WALL (CONT'D)</u>								
2	9.76	-4.70	26.00 0.0	1.41	94	207	.46	1.38
2	6.90	-1.90	16.44 0.00	1.81	70	200	.35	1.79
2	6.00	-1.0	18.70 0.00	1.71	79	212	.37	1.67
2	3.20	+1.8	11.10 2.50	2.23	55	205	.27	2.34

LOWER GUIDE WALL

2	7.00	-4.00	33.60 0.00	1.26	45	98	.46	1.35
2	2.76	+ .63	5.39 0.55	5.75	9	59	.15	4.07
2	3.22	+0.11	6.95 0.12	3.78	216	71	.22	2.84

MONO- LITH NOS	LOADING CONDITION	W. S. ELEVATIONS, FT LANDWARD LOCK RIVERWARD LOCK		LOCATION OF RESU ECCENTRICITY ③ FT e or e _x e _y	
					IN
4-16 (L=40.0')	NORMAL OPERATING	687.2	725.2	7.26	—
4	CONSTRUCTION — REHABILITATION PLAN 2, LANDWARD LOCK REBUILT	(EMPTY)	725.2	6.10	0.20
5	CONSTRUCTION — REHABILITATION PLAN 2 RIVERWARD LOCK REBUILT	(EMPTY)	725.2	7.60	0.51
6-16	CONSTRUCTION AND MAINTENANCE	(EMPTY)	725.2	7.23	—
18 (GATE) (L=35.0')	NORMAL OPERATING	725.2	687.2	12.40	7.90
18	IMPROVED NORMAL OPERATING STABILIZED BY 12 ROCK ANCHORS OF 3-1½" Ø BAR TENDONS PER ANCHOR	725.2	687.2	7.30	5.80
18	IMPROVED NORMAL OPERATING INTERCONNECTION OF MONO- LITHS 18 & 19 BY SHEAR KEYS	725.2	687.2	8.75	3.25
18	IMPROVED NORMAL OPERATING INTERCONNECTION OF MONOLITHS 17 & 18 BY SHEAR KEYS	725.2	687.2	8.30	—

SHEET 5 OF 5

LOCK AND DAM NO. 1
MINIATURE OF ST. LOUIS INVESTIGATIONS

LOCATION OF RESULTANT RIGHT OF WAY Ex. e_y			FOUNDATION PRESSURE, KCF $\pm (\frac{L}{6} - e)$ FT. f_{MAX} f_{MIN}		F.S.D.	EH KIPS	EV KIPS	SLIDING FACTOR EH/EV	F.S.S.
INTERMEDIATE WALL									
—	—	-0.59	10.90	0.00	1.94	73	209	.35	1.80
0.20	—	0.57	9.66	0.00	1.89	76	197	.39	1.61
0.51	—	-0.9	11.30	0.00	1.90	76	188	.41	1.57
—	—	0.56	11.32	0.00	2.02	77	217	.35	1.77
7.90	—	—	74.50	0.00	1.03	130	217	.60	1.04
5.80	—	—	47.54	0.00	—	130	370	.35	1.77
3.25	—	—	20.10	0.00	1.75	84	189	.45	1.41
—	—	-246 1	13.80	0.00	1.74 2	72	193	.37	1.68

MONO-LITH NO'S	LOADING CONDITION	ELEV. OF BACKFILL FT	W.S. ELEV. AT LAND-SIDE, FT	W.S. ELEV. AT RIVER-SIDE, FT	LOCATION OF RESULTS		
					ECCENTRICITY, FT	FT	±
<u>RIVER WALL</u>							
1 (OLD RIVER WALL) (L=25.0')	CONSTRUCTION (INVESTIGATION OF OLD RIVER WALL MONOLITH)	709.0	705.0	731.7	6.42	—	—
6-16 (L=26.0')	NORMAL OPERATING ① NEW MONOLITH	690.0	725.2	707.7	9.70	—	—
6-16 (L=28.0')	NORMAL OPERATING ② OLD MONOLITH	690.0	707.7	687.2	3.80	—	—
6-16	NORMAL OPERATING COMBINED NEW ① AND OLD ② MONOLITHS	690.0	725.2	687.2	2.58	—	—
6-16	CONSTRUCTION & MAINTENANCE COMBINED NEW ① & OLD ② MONOLITHS	690.0	(EMPTY)	690.0	—	—	—
19 (L=32.0')	NORMAL OPERATING "LOCK SIDE AVERAGE" UPLIFT PRESSURE	698.0	725.2	687.2	5.84	—	—

LOCK AND DAM NO. 1
SUMMARY OF STRUCTURAL INVESTIGATIONS

SHEET 6 OF

LOCATION OF RESULTANT CENTRICITY, FT FROM MIDDLE $\frac{1}{3}$			FOUNDATION PRESSURE, KSF		PILE LOAD KIPS/PILE	F.S.O.T.	$\frac{\Sigma H}{\Sigma V}$ KIPS	SLIDING FACTOR, $\frac{\Sigma H}{\Sigma V}$	F.S.S. ②
e_x	e_y	$\pm(\frac{1}{2}-e) \text{ FT } ③$	f_{MAX}	f_{MIN}					

RIVER WALL

42	—	-2.26	9.50	0.00	—	1.40	$\frac{38}{86}$.44	1.25
70	—	-5.70	35.60	0.00	—	—	$\frac{64}{123}$.52	1.05
80	—	+0.86	7.12	0.72	—	—	$\frac{1}{109}$	—	—
58	—	+6.42	5.54	3.07	$P_{MAX} = 50$ $P_{MIN} = 42$ $P_H = 13$	—	$\frac{64}{232}$.273	2.01
—	—	—	—	—	$P_{MAX} = 98$ $P_{MIN} = 21$ $P_H = 2$	—	—	—	—
84	—	-0.51	11.86	0.00	$P_{MAX} = 130$ $P_{MIN} = -10$ $P_H = 21$	1.84	$\frac{63}{181}$.35	1.57

MONO- LITH NOS	LOADING CONDITION	ELEV. OF BACKFILL, FT	W.S. ELEV. AT LAND- SIDE, FT	W.S. ELEV. AT RIVER- SIDE, FT	LOCATION OF ECCENTRICITY, FT	e OR e _x	e _y
19	NORMAL OPERATING "LOCKSIDE MAXIMUM" UPLIFT PRESSURE	698.0	725.2	687.2	7.14	—	—
19	IMPROVED NORMAL OPERATING-BACKFILL BEHIND MONOLITH "LOCKSIDE AVERAGE" UPLIFT PRESSURE	710.0	725.2	687.2	4.70	—	—
19	IMPROVED NORMAL OPERATING - BACKFILL BEHIND MONOLITH "LOCKSIDE MAXIMUM" UPLIFT PRESSURE	710.0	725.2	687.2	5.87	—	—
20 (L-20.0)	NORMAL OPERATING "LOCKSIDE AVERAGE" UPLIFT PRESSURE	690.0	725.2	687.2	8.62	7.25	—
20	NORMAL OPERATING "LOCKSIDE MAXIMUM" UPLIFT PRESSURE	690.0	725.2	687.2	9.29	7.95	—
20	IMPROVED NORMAL OPERATING BACKFILL "LOCKSIDE AVERAGE" UPLIFT PRESSURE	710.0	725.2	687.2	7.55	6.95	—

LOGK AND DAM NO. 1 SUMMARY OF STRUCTURAL INVESTIGATIONS

SHEET 7 OF 1

LOCATION OF RESULTANT FROM MIDDLE 1/3		FOUNDATION PRESSURE, KSF		PILE LOAD KIPS/PILE	F.S.O.T.	ZH KIPS	EV	SLIDING FACTOR EH/EV	F.S.S. ②
x	E _y	±(1/6-e), FT	f _{MAX}						

RIVER WALL (CONT'D)									
—	—	-1.80	12.17	0.00	P _{MAX} = 131 P _{MIN} = -23 P _H = 21	1.55	63 162	.39	1.41
—	—	+0.63	10.61	0.68	P _{MAX} = 117 P _{MIN} = 3 P _H = 16	1.93	49 181	.27	2.04
—	—	-0.53	10.70	0.00	P _{MAX} = 117 P _{MIN} = -9 P _H = 16	1.63	49 162	.30	1.83
7.25	—	—	53.50	0.00	P _{MAX} = 290 P _{MIN} = -151 P _H = 40	—	116 202	.59	0.95
1.95	—	—	64.20	0.00	P _{MAX} = 234 P _{MIN} = -162 P _H = 48	—	116 192	.61	0.90
6.95	—	—	45.50	0.00	P _{MAX} = 283 P _{MIN} = -139 P _H = 33	—	96 210	.44	1.20

MONO- LITH NO S	LOADING CONDITION	ELEV. OF BACK FILL FT	W.S. ELEV. AT LAND- SIDE, FT.	W.S. ELEV. AT RIVER- SIDE, FT.	LOCATION OF RESULT ECCENTRICITY ⁽⁵⁾ FT	
					e OR e _x	e _y OR e _y
	IMPROVED NORMAL OPERATING					
20	BACKFILL "LOCKSIDE MAXIMUM" UPLIFT PRESSURE	710.0	725.2	687.2	8.18	7.60
20	SHEAR KEYS ⁽⁶⁾ "LOCKSIDE AVERAGE" UPLIFT PRESSURE	690.0	725.2	687.2	5.04	3.89
20	SHEAR KEYS ⁽⁶⁾ "LOCKSIDE MAXIMUM" UPLIFT PRESSURE	690.0	725.2	687.2	5.66	5.10
20	BACKFILL & SHEAR KEYS ⁽⁶⁾ "LOCKSIDE AVERAGE" UPLIFT PRESSURE	710.0	725.2	687.2	3.90	5.21
20	BACKFILL & SHEAR KEYS ⁽⁶⁾ "LOCKSIDE MAXIMUM" UPLIFT PRESSURE	710.0	725.2	687.2	4.49	6.40

RIVER WALL

⁽⁶⁾ MONOLITHS 19, 20 & 21 INTERCONNECT

LOCK AND DAM NO. 1 SUMMARY OF GEOTECHNICAL INVESTIGATIONS

SHEET 3 OF 3

LOCATION OF RESULTANT (3) CENTRICITY (5) FT FROM MIDDLE 1/3 e_x e_y $\pm(\frac{1}{6}e)$ FT			FOUNDATION PRESSURE, KSF f_{MAX} f_{MIN}		PILE LOAD KIPS/PILE	F.S.O.T.	ΣH KIPS ΣV	SLIDING FACTOR $\Sigma H/\Sigma V$	F.S.S. (2)
--	--	--	---	--	------------------------	----------	-------------------------------	--	------------

RIVER WALL (CONT'D)

3	7.60	—	5240	0.00	$P_{MAX} = 287$ $P_{MIN} = -149$ $P_H = 33$	—	96 200	.48	1.15
4	3.89	—	14.15	0.00	$P_{MAX} = 172$ $P_{MIN} = -34$ $P_H = 30$	—	79 205	.39	1.42
5	5.10	—	14.88	0.00	$P_{MAX} = 179$ $P_{MIN} = -47$ $P_H = 30$	—	79 200	.40	1.39
6	5.21	—	13.70	0.00	$P_{MAX} = 164$ $P_{MIN} = -22$ $P_H = 23$	—	66 209	.32	1.74
7	6.40	—	13.80	0.00	$P_{MAX} = 173$ $P_{MIN} = -37$ $P_H = 23$	—	66 204	.32	1.70

INTERCONNECTED WITH SHEAR KEYS

LOADING CONDITIONS

WATER SURFACE ELEV., FT			LOCATION OF RESULTANT	
UPPER POOL	TAIL - WATER	LOWER POOL	ECCENTRICITY e, FT	FROM MIDDLE $\frac{1}{3}$ $\pm(\frac{1}{6}e)(B)$

BUTTRESS

NORMAL OPERATING
10K/FT OF CREST
ICE PRESSURE

723.2 (EMPTY) (EMPTY) 4.32 + 5.81

FLOOD DISCHARGE
1965 FLOOD
DAM CAVITY FULL
OF WATER

734.7 719.0 719.0 0.96 + 9.19

FLOOD DISCHARGE
1951 FLOOD
WATER IN CAVITY @
RELIEF HOLES LEVEL

731.0 695.5 709.0 0.72 + 9.41

EARTHQUAKE

NORMAL OPERATING WITH
EARTHQUAKE BUT WITH-
OUT ICE PRESSURE

723.2 (EMPTY) (EMPTY) 2.81 + 7.32

IMPROVED NORMAL OPERATING
1951 FLOOD
ADDITIONAL SAND FILL
UP TO EL. 701.25±

731.0 695.5 709.0 0.69 9.44

⑥ INTERNAL HYDROSTATIC PRESSURE
EXCEPT NORMAL OPERATING

LOCK AND DAM NO. 1 SUMMARY OF TEST RESULTS

SHEET 9 OF 9

OF RESULTANT FROM MIDDLE $\frac{1}{3}$ $\pm(\frac{1}{6} - c) \textcircled{3}$	B E A R I N G				S L I D I N G			
	ΣH KIPS	ΣV KIPS	FOUNDATION PRESSURES		R_T KIPS	R_T KIPS	FACTOR R_T/R_H	F.S.S.
			$f_{MAX.}$ KSF	$f_{MIN.}$ KSF				

BUTTRESS DAM

+ 5.81	725	1726	2.53	1.02	530	1903	0.279	2.33
+ 9.19	536	1215	1.36	1.13	297	1366	0.217	2.98
+ 9.41	807	1335	1.47	1.27	669	1525	0.439	1.48
+ 7.32	804	1726	2.27	1.28	609	1941	0.319	2.03
9.44	807	1557	1.48	1.30	667	1542	0.439	1.50

ATIC PRESSURE (UPLIFT) DETERMINED BY FLOW NET METHOD
OPERATING CONDITIONS.

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INVESTIGATION OF STABILITY
FOR LOCK WALLS
COMPUTED M.J. CHECKED R.N.M.

PROJECT L.E.D. #1
FILE NO 800A
DATE 8.74 PAGE 1 OF 1 PAGES

BANK FILL BEHIND WALLS

NUMBER OF BLOWS FOR 12" PENETRATION

HOLE NO DEPTH IN FT.	74-22	74-14	74-B
1	6	20	
2	16	14	100
3	28	12	40
4		20	46
5	50	20	36
6		90	42
7		140	46
8			
9	4		80
10	28		90
11	88		100
12			
13			
14			16
15	12		16
16	16		14
17	26		
18			
19			10
20			20
			26
			10
25			16
			16
30			16
			20
			30
35			110
			82
			32

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT
LATERAL EARTH PRESSURES
COMPUTED R.H.M. CHECKED VT

PROJECT LOCK AND DAM No. 1
FILE NO. 800 A
DATE OCT. 1, 75 PAGE 2 OF PAGES

The land and guide wall monoliths have been considered to behave essentially as rigid structures. Therefore at-rest earth pressure coefficients have been utilized for calculating lateral forces, modified by reduction factors considering the deformation history of the monoliths and the nature of the granular backfill materials. For monoliths founded directly upon the sandstone (sand) a reduction factor of 0.95 was used. For monoliths bearing upon timber cribs a reduction factor of 0.85 was applied.

LAND WALL, MONOLITHS 1-7 UPPER GUIDE
WALL AND MONOLITHS 1-2 LOWER GUIDE WALL

These monoliths are founded directly on sandstone

$$\begin{aligned}\gamma_{\text{moist}} &= 115 \text{ pcf} \\ \gamma_{\text{saturated}} &= 130 \text{ pcf} \\ \gamma_{\text{submerged}} &= 68 \text{ pcf}\end{aligned}$$

$$\phi = 38^\circ$$

$$\begin{aligned}K_0 &= 1 - \sin \phi = 0.384 \\ K &= 0.95 K_0 = 0.365\end{aligned}$$

$$K \gamma_{\text{moist}} = 0.365 \times 115 = 42 \text{ psf}$$

$$K \gamma_{\text{subm.}} = 0.365 \times 68 = 25 \text{ psf}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT
LATERAL EARTH PRESSURES
COMPUTED R. N. M. CHECKED VT

PROJECT LOCK AND DAM No. 1
FILE NO. 800 A
DATE Oct. 1, 75 PAGE 2A OF PAGES

MONOLITHS 8-13 UPPER GUIDE WALL AND
MONOLITHS 3-13 LOWER GUIDE WALL

These monoliths are bearing upon timber cribs

$$\begin{aligned}\gamma_{\text{moist}} &= 115 \text{ pcf} \\ \gamma_{\text{saturated}} &= 125 \text{ pcf} \\ \gamma_{\text{submerged}} &= 63 \text{ pcf}\end{aligned}$$

$$\phi = 35^\circ$$

$$\begin{aligned}K_o &= 1 - \sin \phi = 0.426 \\ K &= 0.85 K_o = 0.362\end{aligned}$$

$$K \gamma_{\text{moist}} = 0.362 \times 115 = 42 \text{ psf}$$

$$K \gamma_{\text{subm.}} = 0.362 \times 63 = 23 \text{ psf}$$

EQUIVALENT FLUID PRESSURES USED IN THE ANALYSES


Because of small variations in calculated values the following equivalent fluid weights were used for calculating earth pressures acting on the land and guide wall monoliths

$$K \gamma_{\text{moist}} = 42 \text{ psf}$$

$$K \gamma_{\text{submerged}} = 26 \text{ psf}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY OF UPPER</u>	PROJECT <u>LED #1</u>
	<u>LAND GUIDE WALL MONO #1-7</u>	FILE NO. <u>800A</u>
COMPUTED <u>M.J.</u>	CHECKED <u>R.N.M.</u>	DATE <u>8.74</u> PAGE <u>3</u> OF <u> </u> PAGES

4/2/77

UPPER (LAND) GUIDE WALL MONOLITHS #1-7

$$\Sigma V = 36.7 \text{ k} \quad \Sigma H = 12.76 \text{ k} \quad M_A = 120.3 \text{ k} \quad \alpha = \frac{120.3}{36.7} = 3.28'$$

$$1. \quad C = 3.72 \quad R = 38.9' \text{ OUTSIDE MIDDLE } E \text{ BY } 1.39'$$

$$2. \quad \frac{\Sigma H}{\Sigma V} = \frac{12.76}{36.7} = 0.348 \checkmark$$

$$3. \quad f_{SOIL} = 7.46 \text{ ksf (max.)}$$

$$4. \quad FSS = \frac{36.7 \times 0.625}{12.76} = 1.80 \checkmark$$

$$5. \quad F_{TOT} = \frac{36.7}{248.6} = 1.48 \checkmark$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY OF UPPER</u>	PROJECT <u>LSD #1</u>
	<u>LAND GUIDE WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M. J.</u> CHECKED <u>R. N. M.</u>	DATE <u>8.74</u> PAGE <u>4</u> OF <u> </u> PAGES

4/2/74

UPPER LAND GUIDE WALL - MONOLITHS #1-#7WATER LEVEL CEL 725.2

	LOADS IN KIPS	VERT ↓	VERT ↑	HORIZ.	HORIZ	ARM	MOM _A	MOM _A ^{ik}
C ₁	8.0 × 5.0 × .15	6.0				2.5		15.0
C ₂	5.0 × 8.0 × .15	6.0				4.0		24.0
C ₃	11.0 × 5.0 × .15	8.3				5.5		45.6
C ₄	14.0 × 9.6 × .15 ✓	20.2 ✓				7.0 ✓		141.1 ✓
E ₁	.11 × 9.0 × 8.0	7.9				9.5		75.2
E ₂	.13 × 6.0 × 5.0	3.9				11.0		43.0
E ₃	.13 × 3.0 × 5.0	2.0				12.5		25.0
W ₁	20.1 × .0625 × 14	✓	17.6 ✓			7.0	123.1	
Σ		54.3	17.6				123.1	368.9 ✓ ^{ik}
H _{E1}	.042 × 7.5 ² /2			1.18		22.60	26.7	
H _{E2}	.042 × 7.5 × 20.1			6.33		10.05	63.8	
H _{E3}	.026 × 20.1 ² /2			5.25		6.70	35.2 ✓	
				36.7 ✓	12.76 ✓		248.3 ✓ ^{ik}	
							Σ M = 120.3 ✓ ^{ik}	

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY OF UPPER</u>	PROJECT <u>LED #1</u>
	<u>LAND GUIDE WALL</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>P.N.M.</u>	DATE <u>8.74</u> PAGE <u>5</u> OF <u>5</u> PAGES

4/2/75


LIPPER LAND GUIDE WALL - MONOLITHS #1-#7 (UNTED)

$$H_{E1} = .042 \times 7.5^2 / 2 = 1.18^{\checkmark} k \cdot 22.60^{\checkmark}$$

$$H_{E2} = .042 \times 7.5 \times 20.1 = 6.33^{\checkmark} \times 10.05^{\checkmark}$$

$$H_{E3} = .026 \times 20.1^2 / 2 = 5.25^{\checkmark} \times 6.70^{\checkmark}$$

$$\Sigma H = 12.76 k$$



$$M_{E1} = 26.7^{\checkmark} k$$

$$M_{E2} = 63.6^{\checkmark}$$

$$M_{E3} = \frac{35.2^{\checkmark}}{125.5^{\checkmark} k \cdot 2^{\checkmark}}$$

$$\Sigma M = 368.9^{\checkmark} - 125.5^{\checkmark} - 123.1^{\checkmark} = 120.3^{\checkmark} k$$

$$a = \frac{120.3}{36.7} = 3.28^{\checkmark}$$

$$f_{\text{sail}} = \frac{2}{3} \left(\frac{36.7}{3.28} \right) = 7.46$$

$$e = 7.0 - 3.28 = 3.72^{\checkmark}$$

HARZA
ENGINEERING
COMPANY
CHICAGO


SUBJECT UPPER GUIDE WALL
STABILITY, CONSTRUCTION CONDITION
COMPUTED R.N.M. CHECKED JJ

PROJECT LOCK & DAM N.1
FILE NO. 800A
DATE 2/75 PAGE 5a OF PAGES

(16) STABILITY OF UPPER GUIDEWALL MONOLITHS 1-5 DURING CONSTRUCTION PERIOD.

Riverward side empty (Inside cofferdam enclosure)

Landward side W.S. EL. 719.7 (Ref. pgs 3, 4 & 5)



1) "R" outside middle $\frac{1}{3}$ by 1.89 ft

2) $\frac{\Sigma H}{\Sigma V} = 0.44$

3) $f_{soil} = 11.34 \text{ KSF}$

4) $FSS = 1.41$

5) $FSOT = 1.57$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>UPPER GUIDE WALL</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	<u>MONOLITHS 3, 4 & 5 (CONSTRUCTION)</u>	FILE NO. <u>800 A</u>
COMPUTED <u>R.N.M.</u>	CHECKED <u>✓</u>	DATE <u>2/75</u> PAGE <u>56</u> OF <u> </u> PAGES

CONSTRUCTION CONDITION (cont'd)

FORCES		H → ⊕	V ↓ ⊕	ARM	M _A	M _A
C1			+ 6.0			15.0
C2			+ 6.0			24.0
C3			+ 8.3			45.6
C4			+ 20.2			141.1
E1			+ 7.9			75.2
E2	0.11 x 6 x 5.0		+ 3.3	11.0		36.3
E3			+ 2.0			25.0
U	14.6 x .0625 x 14 x 1/2		- 6.4	9.3	59.5	
HE1	0.042(13) ² x 1/2	+ 3.5		18.9	66.2	
HE2	0.042(13) x 14.6	+ 8.0		7.3	58.4	
HE3	0.026(14.8) ² x 1/2	+ 2.8		4.9	13.7	
HW	0.0625(14.8) ² x 1/2	+ 6.7		4.9	32.8	
		Σ H = 21.0	Σ V = 47.3		Σ M _A = 230.6	362.2

$$\bar{x} = \frac{131.6}{47.3} = 2.78 \quad e = 7 - \bar{x} = 4.22' \quad \frac{e}{6} = 2.33$$

(1) Resultant outside middle $\frac{1}{3}$, 1.89 ft

$$(2) f_{\text{soil}} = \frac{2}{3} \frac{\Sigma V}{x} = \frac{2}{3} \times \frac{47.3}{2.78} = 11.34 \text{ KSF}$$

$$(3) \frac{\Sigma H}{\Sigma V} = \frac{21.0}{47.3} = 0.44$$

$$(4) FSS = \frac{1.41}{1}$$


$$(5) FST = \frac{362.2}{230.6} = 1.57$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILITY OF CLIPPER LAND
GUIDE WALL
COMPUTED M. J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. B00A
DATE 8.74 PAGE 6 OF PAGES

CLIPPER LAND GUIDE WALL MONOLITHS #8-13



$$\Sigma V = 34.70^k \quad \Sigma H = 11.40^k$$

$$M_A = 194.0^k \quad e = \frac{194.0}{34.70} = 5.60' \quad c = 3.4'$$

$$1. R = 37.8^k \text{ OUTSIDE MIDDLE } \frac{1}{3} \text{ BY } 0.4'$$

$$2. \frac{\Sigma H}{\Sigma V} = .33 (< .417^k)$$

$$3. FSS = \frac{34.7 \times .625}{11.40} = 1.90$$

$$4. f_{SOIL} = 4.13 \text{ ksf}$$

$$5. FDOT = 2.06$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY OF UPPER</u>	PROJECT <u>L.F.D #1</u>
	<u>LAND GUIDE WALLS</u>	FILE NO <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>8.74</u> PAGE <u>7</u> OF <u> </u> PAGES

UPPER LAND GUIDE WALL - MONOLITHS # B-13

	LOADS IN KIPS	VERT ↓	VERT ↑	HORIZ. →	HORIZ. ←	ARM	MOM _A ↓	MOM _A ↑
C ₁	8.0 x 5.0 x .15	6.0				2.5		15.0
C ₂	8.0 x 3.0 x .15	3.6				4.0		14.6
C ₃	18.0 x 4.0 x .15	10.8				9.0		97.2
C ₄	18.0 x 11.0 x ^{.037} (10-.063)	7.4				9.0		66.6
E ₁	13.0 x 8.0 x .11	11.5				11.5		132.3
E ₂	3.0 x 10.0 x .13	2.9				13.0		50.8
W ₁	7.5 x .0625 x 18.0		8.5			9.0	76.5	
H _{E1}	.315 x 3.75			1.2		21.0	25.3	
H _{E2}	.315 x 18.5			5.8		9.29	53.6	
H _{E3}	.48 x 18.5/2			4.4		6.17	27.2	
		43.2	8.5	11.4			182.6	376.5

$$\Sigma V = 43.2 - 8.5 = 34.7 \text{ k}$$

$$\Sigma M = 376.5 - 182.6 = 194.0 \text{ 'k}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILITY OF UPPER
GUIDE WALLS
COMPUTED M.T. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 900A
DATE 8.74 PAGE 8 OF 8 PAGES

UPPER LAND GUIDE WALL - MONOLITHS #8-13

$$\Sigma V = 34.70 \text{ k}$$

$$\Sigma H = 11.40 \text{ k}$$

$$\Sigma M = 194.0 \text{ k'}$$

$$a = \frac{194.0}{34.70} = 5.60$$

$$e = 9.0 - 5.6 = 3.4$$

$$M_e = 34.70 \times 3.4 = 118.0 \text{ k'}$$

1. RESULTANT OUTSIDE MIDDLE THIRD BY 0.4'

$$2. \frac{\Sigma H}{\Sigma V} = \frac{11.40}{34.70} = .33$$

$$3. FSS = \frac{34.70 \times .625}{11.40} = 1.90$$

$$4. f_{\text{soil}} = \frac{2}{3} \times 34.70 / 5.6 = 4.13 \text{ k.s.f.}$$

$$5. FSOT = \frac{376.5}{182.6} = 2.06$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL 5-15
EXISTING - NORMAL
COMPUTED R.N.M. CHECKED JJ


PROJECT L 4 D #1
FILE NO. 800 A
DATE 1/75 PAGE 10 OF PAGES

W.6. EL 704' (LANDWARD)

LANDWALL MONOLITHS ⁵ -15
NORMAL OPERATING, EXISTING CONDITION

Added hor. force — friction from w.b. of submerged slab, $P_R = 2 \times 56 \times .088 \times .55 = 5^k \leftarrow$

Compute difference in earth & hydrostatic pressures:



$$EH = 17.3 + 37.3 + 12.3 + 29.6 - 6.1 = 90.4^k \rightarrow$$

$$EM_A = 700 + 574 + 127 + 305 - 29 + 810 = 2487^k \rightarrow$$

$$EH = 22.4 + 36.7 + 9.3 + 22.4 - 6.8 = 84.7^k \rightarrow$$

$$EM_A = 844 + 492 + 83 + 199 - 29 + 725 = 2314^k \rightarrow$$

$$\Delta H = 90.4 - 84.7 = 5.7^k \rightarrow$$

$$\Delta V = 4.5 - 4.1 = 0.4^k \uparrow$$

$$\Delta M_A = 2487 - 2314 = 173^k \rightarrow$$

Cont'd on Pg 10 & 2

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL 5⁵M-15
EXISTING - NORMAL
COMPUTED R. N. M. CHECKED JL

PROJECT L & D #1
FILE NO. 800A
DATE 1/1/75 PAGE 1000 OF 1000 PAGES

W. S. EL. 704'

LANDWALL MONOLITHS 5⁵M-15
NORMAL OPERATING, EXISTING CONDITION (CONT'D)

From page 11, $\begin{matrix} E_H' = 85^k \rightarrow \\ E_V' = 202^k \downarrow \\ E_{M_A}' = 1647^k \end{matrix} \left. \vphantom{\begin{matrix} E_H' \\ E_V' \\ E_{M_A}' \end{matrix}} \right\} \begin{matrix} \text{For W.S. EL 700'} \\ \text{Without } P_r \end{matrix}$

$$E_H = 85 + .7 = 85.7^k$$

$$E_V = 202 + (-4) = 198^k$$

$$E_{M_A} = -1647 + 173 = -1474^k$$

$$(1) a = \frac{1474}{198} = 7.44' \quad e = \frac{L}{2} - a = 8.56 - 5.33 \dots 4'$$

Location of Resultant 3.23' Outside middle 3rd.

$$(2) \frac{E_H}{E_V} = \frac{85.7}{198} = 0.43$$

$$(3) FSS = \frac{198 \times 0.625}{85.7} = 1.44$$

$$(4) f_{soil} = \frac{2}{3} \times \frac{198}{7.44} = 17.74 \text{ KSF}$$

$$(5) F_{TOT} = \frac{4051}{2404 + 173} = 1.57$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDFILL MONOLITHS</u>	PROJECT <u>LED #1</u>
	COMPUTED <u>M. J.</u>	FILE NO. <u>800A</u>
	CHECKED <u>R. N. M.</u>	DATE <u>11.74</u> PAGE <u>11</u> OF <u>11</u> PAGES

W.S. EL. 700' (LANDWARD)

LANDFILL MONOLITHS #5-15 - EXISTING CONDITION

$$E_4 = 24.0 \times 7.5 \times 1.3 = 23.40 \text{ k} \quad (\text{PER CASE FOR LOWER 10' BACKFILL BY 10.0'})$$

$$\Sigma V = 202.0 \text{ k} \quad (222.8 - 44.6 + 23.4)$$

$$\Sigma H = 85.0$$

$$\Sigma M_A = 3583.5 - 808.0 + 2340 \times 20.0 - 1596 = 4051 - 2404$$

$$\Sigma M_A = 1647.0 \text{ k}$$

$$Q = \frac{1647.0}{202.0} = 8.15'$$

$$C = 16.0 - 8.15 = 7.85'$$

$$1). \text{ RESULTANT } R = 218.0 \text{ k OUTSIDE MIDDLE } \frac{1}{3} \text{ BY } 2.52'$$

$$2). \frac{\Sigma H}{\Sigma V} = \frac{85.0}{202.0} = 0.422$$

$$3). f_{\text{SOIL}} = \frac{2}{3} \times 202.0 / 8.15 = 16.50 \text{ ksf}$$

$$4). F_{SS} = \frac{202.0 \times 62.5}{850} = 1.49$$

$$5). F_{SOT} = \frac{4051}{2404} = 1.68$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL 5-15
EXISTING - MAINTENANCE
COMPUTED R.N.H. CHECKED J1

PROJECT LOCK & DAM #1
FILE NO. 800 A
DATE 3/75 PAGE 12 OF PAGES

W.S. EL 704 (LANDWARD)

LANDWALL MONOLITHS 5-15

MAINTENANCE LOADING - LOCK EMPTY
- EXISTING BACKFILL @ EL 732.7
- (REFER TO NORMAL LOADING)
- FRICTION BETWEEN SLAB & ROCK

REFERENCE PAGES 10 & 10a

$$\Sigma H = 91 + 6.8 = \underline{97.8} \text{ kips} \rightarrow$$

$$\Sigma V = 198 + 14 = \underline{212.0} \text{ kips} \downarrow$$

$$\Sigma M_A = -1473 + (-150) + 33 \left. \vphantom{\Sigma M_A} \right\} = -\underline{1590} \text{ 'k'}$$

$$(1) a = \frac{1590}{212} = 7.5' \quad \frac{L}{2} - a = e = \underline{8.5'}$$

"R" OUTSIDE M $\frac{1}{3}$, 3.2 ft.

$$(2) \frac{\Sigma H}{\Sigma V} = \frac{97.8}{212} = \underline{0.46}$$

$$(3) FSS = \underline{1.35}$$

$$(4) f_{\text{soil}} = \frac{2}{3} \times \frac{212}{7.5} = \underline{18.84} \text{ KSF}$$

$$(5) F_{\text{TOT}} = \frac{4051}{2578 + 150 - 33} = \underline{1.5}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL STABILITY-
EXISTING CONDITION


COMPUTED R. H. M. CHECKED J. L.

PROJECT LOCK & DAM NO. 1

FILE NO 800 A

DATE 2/75 PAGE 10 OF 10 PAGES

MONOLITH NO. 3, NORMAL LOADING CASE (PRESENT)



(1) Resultant 3.73 ft. outside middle $\frac{1}{3}$

(2) $f_{\text{soil}} = 13.41 \text{ KSF}$

(3) $\frac{EH}{EV} = 0.461$

(4) $F_{SS} = 1.36$

(5) $F.S.O.T. = 1.54$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL STABILITY-
EXISTING CONDITION
COMPUTED R. H. M. CHECKED J. J.

PROJECT LOCK & DAM NO. 1
FILE NO. 800 A
DATE 2/75 PAGE 10b OF PAGES

MONOLITH NO. 3, NORMAL LOADING CASE (CONT'D)

	H → E	V ↓	ARM	M _{y-r}
⑪ (28.7 1/2) 0.42 (24.3)	1420	⊕	40.4	+16981
⑫ 28.7 x 0.42 x 30.8 x 24.3	902		15.4	+13893
⑬ 14 x 14 x 24 (-0.15)		-706	2	+1412
⑭ 11.5 x 11 x 9 (-0.15)		-170	2	-340
⑮ TO ⑫ "FR. TEMP. CONST."		+5641	(0.93)	+5237
⑯ 6Y 28.7 x 24.3 x 0.11		+460	13'	-5980
⑰ & ⑱ FROM TEMP. CONST.		+261		-3463
⑲ and ⑳ FR. TEMP. CONST.	+1019			+10496
㉑ 2 x 56 x 0.088 x 24.3 x 55	-132			
㉒ 1.92 x 30 x 1/2 x 24.3		-700	6'	+4200
㉓ 0.88 x 30 x 1/2 x 24.3		-320	4	-1280
㉔ 14 ² x 1/2 x 0.0625 x 24.3	-150		4.67	-700

$$\Sigma H = +2059$$

$$\Sigma M_{y-r} = +40456$$

$$\Sigma V = 4466^k$$

$$e = \frac{40456}{4466} = 9.06 > \frac{L}{6}, \quad \frac{5.33}{9.06}, \quad \bar{X} = 6.94$$

(1) RESULTANT IS 3.73 OUTSIDE MIDDLE 3rd

$$(2) f = \frac{2}{3} \frac{\Sigma V}{A} = \frac{2}{3} \frac{4466}{6.94 \times 32} = 13.41 \text{ KSF}$$

$$(3) \frac{\Sigma H}{\Sigma V} = \frac{2059}{4466} = 0.461$$

$$(4) FSS = \frac{625}{451} = 1.36$$

$$(5) F.S.O.T. = 1.54$$

$$40456 - 43590 = 3134$$

$$\frac{3134}{5486} = 0.57$$

$$\frac{16.00}{16.00}$$

$$\text{RESULT } M = 5486 \times 16.57 = 90903$$

$$\text{OVERT. } M_A = 48590 - 2920 + 320 \times \frac{25}{2}$$

$$+ 200 \times \frac{1}{2} \times 32 = 59017^k \downarrow$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LAND WALL STABILITY -
TEMPORARY CONSTRUCTION
COMPUTED R.N.M. CHECKED JJ


PROJECT LOCK & DAM # 1
FILE NO 800 A
DATE 2/75 PAGE 106 OF 106 PAGES

LANDWALL MONOLITH NO. 3
REHABILITATION - ALL PLANS

RESULTS:

- 1) "R" outside mid $\frac{1}{2}$ by 1.58
- 2) $f_{soil} = 12.5$ KSF
- 3) $\frac{EH}{EV} = 0.436$
- 4) $FSS = 1.43$
- 5) $FSOT = 2.10$

* SEE RIVERWALL
MONOLITH #4 REHABILITATION
PLAN 2 ANALYSIS.



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILITY -</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	<u>TEMPORARY CONSTRUCTION</u>	FILE NO <u>800 A</u>
	COMPUTED <u>R. N. M.</u> CHECKED <u>J</u>	DATE <u>2/75</u> PAGE <u>10d</u> OF <u> </u> PAGES

LANDWALL MONOLITH NO. 3REHABILITATION - ALL PLANS (con'd)

		H → ⊕	V ↓ ⊕	ARM	M _y ⊕
① To	See intermediate wall		-1386	2.0	-2772
⑦	monolith No. 1, Rehabilitation Plan 2 Analysis				
⑧	59.5 x 24 x 24.3 x 0.15		5205	2.0	+10410
⑨	19.5 x 3 x 24.3 x 0.15		213	11.5	-2450
⑩	14.5 x 3 x 24.3 x 0.15		159	14.5	-2306
⑪	8 x 3 x 24.3 x .088		51	12.8	612
⑫	28.3 x 24.3 x .088		13	15.0	+195
⑬	16.3 x 3 x 24.3 x .13		154	14.5	-2233
⑭	11.3 x 3 x 24.3 x .13		107	11.5	-1230
15	18.7 x 6 x 24.3 x .11		300	13.0	-3900
⑮	3.0 x 6.0 x 24.3 x 0.11		48	13.0	-625
			(4864)	1.14	(5523)
⑮a	2 x .042 x 50 x 24.3	+102	1	25	+2552
⑯	30.8 x $\frac{1}{2}$ x .0624 x 24.3	+719		10.3	+7406
⑰	18.7 x $\frac{1}{2}$ x .042 x 24.3	+178		37.0	+6586
⑱	18.7 x .042 x 30.8 x 24.3	+588		15.4	+9055
⑲	30.8 x $\frac{1}{2}$ x .026 x 24.3	+300		10.3	+3110
H ₅	.042 x 3 x 49.5 x 24.3	+152		24.8	+3770
P ₁	2 x 56 x 0.15 x 24.3	-224		-	-
	x .55				
20	1.92 x 30 x $\frac{1}{2}$ x 24.3		-700	6.0	+4200
		+1815 ^R			31156
		+1743	+4164		+28504

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL STABILITY -
TEMPORARY CONSTRUCTION
COMPUTED R. N. M. CHECKED JL

PROJECT LOCK & DAM NO. 1
FILE NO 800 A
DATE 2/75 PAGE 10e OF PAGES

LANDWALL MONOLITH NO. 3
REHABILITATION - ALL PLANS (CONT'D)

$$EH = \frac{1815}{\cancel{1718}}^k \quad EV = 4164^k \quad EM_y = \frac{31136}{\cancel{28584}}^k$$

$$(1) e_x = \frac{\frac{31136}{\cancel{28584}}}{4064} = \frac{7.47'}{\cancel{6.86'}}$$

$$\frac{L}{6} = \frac{5.33}{2.14}$$

Resultant, $\frac{1.5}{\cancel{1.5}}$ outside middle $\frac{1}{3}$

$$(2) \bar{x} = \frac{L}{2} - e = \frac{8.53'}{\cancel{2.14'}}$$

$$f_{soil} = \frac{2}{3} \times \frac{4164}{24.3 \times \cancel{9.14}} = \frac{13.31}{\cancel{12.5}} \text{ KSF}$$

$$(3) \frac{EH}{EV} = \frac{\frac{1815}{\cancel{1718}}}{4164} = \frac{8.53}{\cancel{0.436}}$$

$$(4) FSS = \underline{1.43}$$

$$(5) (M_A \text{ (Resisting)}) = 4864 (1.14 + 16) = 83369^k$$

$$(M_A \text{ (Overturning)}) = \cancel{24384} + 1018 \times 16 + 2552 = \frac{39784^k}{\cancel{42336}^k}$$

$$FSOT = \frac{83369}{\cancel{39784}} = \frac{1.97}{\cancel{2.10}}$$

42336

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT **LANDWALL STABILITY -
EXISTING CONDITION**

COMPUTED R. N. M. CHECKED JJ


PROJECT **LOCK & DAM No. 1**

FILE NO. **800A**

DATE **3/75** PAGE **10K** OF **10** PAGES

**MONOLITH No. 3
NORMAL LOADING
(WITHOUT STABILIZATION)**

CONDUIT IS LOWERED AND 2 GATE SHAFTS ARE FILLED
WITH CONCRETE



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL STABILITY -
EXISTING CONDITION
COMPUTED R. N. M. CHECKED JL

PROJECT LOCK & DAM #1
FILE NO 800 A
DATE 3/75 PAGE 102 OF 102 PAGES

MONOLITH NO. 3
NORMAL LOADING (CONT'D)

This page is referred to: a) Pg 10a, for Hydrostatic and earth pressures
(Analyzed per foot strip of wall) b) Pg 35c, for completed 8'x10' conduit geometry.
c) Pg 10c, for Dead load

Forces	H \rightarrow	V \downarrow	ARM	M _A
Net horizontal	90.4 ^k			
Uplift		-29 ^k	22.0	2468 ^k
Water in lower conduit: 10' x 6' x 8' x .0625' x 24.3		-13 ^k	12.0	
10' x 8' Conduit space: Approx. length = 37' 80 x 37 x (-0.15) = 444 ^k Equiv. per foot = $\frac{444}{24.3}$		+2 ^k	14.0	-28 ^k
Dead load:		-19 ^k	14.0'	+266 ^k
(8) to (14) = $\frac{5641 + 261}{24.3}$		+243 ^k	15.7'	-3815 ^k
(15) 28.7 x 6 x .11		+19 ^k	29.0'	-551 ^k
P _R	-5.4 ^k			
Σ 's	85 ^k	201 ^k		
* $\frac{1774}{5902} = 0.3'$ from d Arm = 16.3 = 15.7				M _{Re} = 4128 ^k) M _{ov} = 2468) $\Sigma M_A = -1660k)$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILITY-</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	<u>EXISTING CONDITION</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>JL</u>	DATE <u>3/75</u> PAGE <u>10</u> OF <u>10</u> PAGES

MONOLIT NO 3NORMAL LOADING (CONT'D)

$$\begin{aligned}
 E_H &= \frac{85}{201} \text{ K} \rightarrow & L &= 32' & \frac{L}{6} &= 5.33' \\
 E_V &= \frac{201}{1660} \text{ K} \downarrow & B &= 1' \\
 E_{MA} &= \frac{1660}{\text{K}} \text{)}
 \end{aligned}$$

$$e = \frac{E_{MA}}{E_V} = \frac{8.30'}{2} = 4.15'; \quad e - \frac{L}{3} - a = \frac{7.70}{3}$$



- (1) Resultant is outside the middle ~~1/3~~ by 2.40 feet
- (2) $f_{soil} = \frac{2}{3} \frac{E_V}{a} = \frac{2}{3} \frac{201}{8.3} = \underline{16.10 \text{ KSF}}$
- (3) $\frac{E_H}{E_V} = \frac{85}{201} = \underline{0.423}$
- (4) $SSF = \frac{0.625}{E_H/E_V} = \underline{1.48}$
- (5) $F.S.O.T. = \frac{M_{Ra}}{M_{ov}} = \frac{4128}{2468} = \underline{1.67}$

LANDWALL MONOLITH NO. 4
REHABILITATION - ALL PLANS

Assumptions: Conc. removed for
new tunnel while
existing tunnel is
still unplugged.
Lock empty.

Results :

- 1) "R" outside middle 3, e.H'
- 2) $f = \underline{134}$ Ksf
- 3) $\frac{EH}{EV} = 0.41$
- 4) F.S.S. = 1.52
- 5) F.S.O.T. = 1.79



FOR USE ON U.S. GOVERNMENT WORK ONLY


HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILITY -</u>	PROJECT <u>LOCK & DAM #1</u>
	<u>TEMPORARY CONSTRUCTION</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>J1</u>	DATE <u>2/75</u> PAGE <u>108</u> OF <u>108</u> PAGES

LANDWALL MONOLITH NO. 4
REHABILITATION - ALL PLANS
(CONT'D)

	Concrete and soil	H	V	Y	X	Mx ft	CMY
①	11x9x35x(-0.15)		-528	0	+2.0	—	-1040
②	11x9x30(-0.15)		-446	0	+2.0	—	-892
③	10x5x40(-0.15)		-800	+5.5	+2.0	+1650	-600
			(1266)			(1650)	(2532)
④	18x6.15x59.5x0.15		+988	+12.0	-1.0	-11856	-988
⑤	18x18x $\frac{1}{2}$ x59.5(0.15)		+1446	+2.85	+2.0	-4121	+2892
⑥	6x30x59.5(0.15)		+1607	0	+11.0	0	+17677
⑦	3x13.5x49.5x0.15		+164	-11.3	+6.5	+1853	+1066
⑧	3x10.35x44.5x0.15		+207	-10.	+3.5	+1925	+725
⑨	9x16.35x39.5x0.15		+872	-7.5	-2.5	+6540	-2180
⑩	3x22.35x24.5x0.15		+246	-4.0	-8.5	+984	-2091
⑪	3x30x19.5x0.15		+263	0	-11.5	—	-3025
⑫	3x30x14.5x0.15		+196	0	-14.5	—	-2842
⑬	2x3x30x(0.089)		+16	0	+15.0	—	+240
⑭	8x3x30(0.089)		+64	0	-12.0	—	-768
			(2069)			(2495)	(10106)
E1	3x5x10.35x0.11		+17	-10.0	+3.5	+167	+60
E2	9x10x16.35x0.11		+152	-7.5	-2.5	+1215	-405
E3	3x25x22.35x0.11		+184	-4.0	-8.5	+736	-1564
E4	6x30x18.7x0.11		+370	0	-13.0	—	-810
E5	6x18.8x30x0.13		+328	0	-13.0	—	-199
			(1056)			(2118)	(10918)
S1	3.0x6.0x30x.11		+59	0	-13.	—	-767
S2	3.0x18x18x $\frac{1}{2}$ x.11		+53	-3.15	-4.	+167	-212
S3	3x6x24x.11		+46	-12.05	-1.0	+556	-46
			(150)			(723)	(1025)
			+6017			-184	-3769

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILITY -</u>	PROJECT <u>LOCK & DAM #1</u>
	<u>TEMPORARY CONSTRUCTION</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>✓</u>	DATE <u>2/75</u> PAGE <u>10k</u> OF <u> </u> PAGES

LANDWALL MONOLITH NO. 4
REHABILITATION - ALL PLANS (CONTD)



Soil pressure, Hydrostatic Uplift and Surge	H	V ↓ ⊕	ARM	M _x	M _y
Carried fr. preceeding pg.		#6017		-184	-3769
① 719 x $\frac{30}{24.3}$	+888		10.3	—	+9146
② 178 x $\frac{30}{24.3}$	+220		37.0	—	+8140
③ 588 x $\frac{30}{24.3}$	+726		15.4	—	+11180
④ 300 x $\frac{30}{24.3}$	+370		10.3	—	+3811
⑤ 700 x $\frac{30}{24.3}$		-864	6.0	—	+5184
⑥ 152 x $\frac{30}{24.3}$	+188		24.8	—	+4662
⑦ Reaction in 2' slab (See page —)	-277	—	—	—	—

ΣH

2115

ΣM_x = -184

$$e_x = \frac{38354}{5153} = 7.44'$$

$$5153 - 5.33 = 4/6$$

$$\Sigma V = 5153$$

$$\Sigma M_y = +38354$$

R = 2.11' Outside the middle third

$$e_y = \frac{-184}{5153} = +0.04"$$

$$f_{\text{soil}} = \frac{2.5 \times 5153}{30 \times 32} = 13.4 \text{ KSF}$$

$$\left. \begin{aligned} \frac{e_x}{32} &= 0.23 \\ \frac{e_y}{30} &= 0.401 \end{aligned} \right\} K=2.5$$

$$\frac{\Sigma H}{\Sigma V} = \frac{2115}{5153} = 0.41$$

$$SSF = 1.52$$

$$\Sigma M_R = \left(\frac{3761}{6017} + 1 \right) 5573 = 100047$$

$$\Sigma M_{\text{prev}} = 32277 + 864 \times 22 + 4662 = 55947$$

$$FSOT = 1.78$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	PROJECT
	LANDWALL STABILITY -	LOCK & DAM NO. 1
	TEMPORARY CONSTRUCTION	FILE NO. 800 A
COMPUTED	CHECKED	DATE
R.N.M.	JL	2/75 PAGE 10 OF 10 PAGES

LANDWALL MONOLITH NO. 4 - REHABILITATION, ALL PLANS (CONT'D)

FRICTION RESISTANCE FROM WEIGHT OF LANDLOCK SLAB

It is assumed that the 2' thick slab in landward lock is capable of supporting 2 transverse loads, P_r , equal to the force of friction between slab and foundation derived from its own weight.

$$P_r = 2 \times 56 \times 0.15 \times 0.625 = 10.5^k \text{ per foot}$$

P_r is resisted by uniformly distributed frictional force and becomes zero at end of 56' slab. Actually, buckling is not possible because any moment developed from eccentricity between P_r & friction is overcome by wt. of slab.

SSF FOR GROUND WATER BEHIND WALL @ EL 700.


$$\begin{array}{r} 2185 \\ -9 \\ \hline -121 \end{array} \quad \begin{array}{r} 5153 \\ + 91 \\ \hline 5244^k \end{array}$$

$\Sigma H = 1985^k$

$\frac{\Sigma H}{\Sigma V} = 0.38$

SSF = 1.64

Factor of safety against sliding if W.S. is lowered by 4'



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL STABILITY-
EXISTING CONDITION
COMPUTED R.N.M. CHECKED JL

PROJECT LOCK & DAM #1
FILE NO. 800A
DATE 3/75 PAGE 10 OF 12 PAGES

MONOLITH No 4
NORMAL LOADING
(WITHOUT STABILIZATION)

CONDUIT IS LOWERED
2 NEW GATE SHAFTS
FULL OR UNIFORM CONCRETE SECTION (24' TOP WIDTH)

This case is referred to monolith 3, Lowered conduits existing, normal loading condition on pages 10K to 10M.

The same outside geometry and loading prevails except that now, conduit is shorter and that, 2 gate shafts are added. Another assumption is that, the monolith is filled with concrete to the shape of monolith 3

Wt. of conduit space removed for monolith 3 (4)

$$\text{plus water} = +19 - 2 = +17^k \downarrow$$

Wt. of conduit space for monolith 4

$$\text{Void} = -8 \times 4 \times 1 \times .15 \text{ ----- } -12^k$$

$$\text{water} = +8 \times 10 \times 1 \times .0625 \text{ ----- } +3.0$$

Service gate shaft :

$$\frac{7 \times 9 \times 40 \times (-0.15)}{30} \text{ (See 35f) } \text{ ----- } -12.6^k$$

Maintenance gate shaft

$$\frac{3 \times 9 \times 40 \times (-0.15)}{30} \text{ ----- } -5.4^k$$

$$\Sigma H = 85^k \rightarrow$$

$$\Delta V = -10.0 \uparrow$$

$$\Sigma V = 201 - 10 = 191^k \downarrow$$

$$\times 14$$

$$\Sigma M_A = -1660 + 140 = -1520^k \curvearrowright$$

$$\Delta M_A = 140^k \curvearrowright$$

$$a = \frac{1520}{191.0} = 7.96 \quad e = 16 \frac{7.96}{7.96} = 8.04'$$

(1) Resultant outside middle $\frac{1}{3}$ by 2.63

$$(2) \frac{2}{3} \Sigma V = \frac{16.0^k \times 14}{7.96} \quad (3) \frac{\Sigma H}{\Sigma V} = 0.445$$

$$(4) SSF = 1.40 \quad (5) FSOT = \frac{(4128 - 140)}{2468} = 1.62$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY & LAND WALL
COMPUTED M.J. CHECKED RNM

PROJECT LED #1
FILE NO 800A
DATE 11.74 PAGE 14 OF PAGES

LANDWALL GATE MONOLITH #17 (CONT'D)

	LOADS IN KIPS	V ↓	V ↑	H ←	H →	ARM	MA _y	MA _x
①	30 × 27.5 × 28.6 × .15	8050				15.0		120,750
②	5 × 2 × 28.6 × .087	25				15.0		375
③	32.7 × 6 × 28.6 × .035		196			27.0	5300	
④	5 × 3 × 28.6 × .020		9			28.5	257	
⑤	80 × 28.6 × .6 × .088		120			12.0	1440	
	80 × 28.6 × .4 × .150		137			12.0	1650	
⑥	13 × 3 × 28.6 × .15		168			15.0	2530	
⑦	45.5 × 15.5 × 4 × .15		423			2.0	846	
⑧	11.5 × 15.5 × 4 × .087		62			2.0	124	
⑨	7.3 × 6.0 × 28.6 × .020		25			27.0	675	
		Σ 8075	1140				12.821	121.125 k
			Σ V = 6935 k					Σ M = 108.304 k

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>OF STABILITY CLAND WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>11.74</u> PAGE <u>15</u> OF <u> </u> PAGES

LANDWALL GATE MONOLITH #17 (CONT'D)

	LOADS IN kips	V ↓	V ↑	H ←	H →	ARM	M _A ↓ ft-k	M _A ↑ ft-k
W ₁	30.0 × 28.6 × 1.06		912			15.0	13700	
W ₂	30.0 × 28.6 × .80 × 1/2		344			20.0	6880	
	GATE CLOSED, LOW WATER IN LOCK	230				12.5	2880	
							<u>Σ 23460</u>	
H ₁	1.37 × 16.35 × 28.6				643	40.7	26200	
H ₂	1.37 × 29.8 × 28.6				1170	14.9	17500	
H ₃	.39 × 29.8 × 28.6				338	9.9	3350	53460
H ₄	.40 × 12.8 × 28.6				145	21.27	3100	
H ₅	.80 × 17.0 × 28.6				389	8.5	3310	
		Σ 230	1256		2685		76920	

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>OF STABILITY CLAND WALL</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>M.I.</u> CHECKED <u>R.N.M.</u>	DATE <u>11.74</u> PAGE <u>16</u> OF <u>16</u> PAGES

LANDWALL GATE MONOLITH #17 (CONT'D)

	LOAD IN KIPS	V ↓	V ↑	H ←	H →	ARM	M _{xx}
⑦	GATE	230.0				5.36	-1230
			423			6.55	+2780
		230	423				1550

SUMMARY OF LOADS

$$\Sigma V = 8075 - 1140 + 230 - 1256 = 5910 \text{ k}$$

$$\Sigma H_x = 2685 \text{ k} \quad R = 6500 \text{ k}$$

$$\Sigma M_A = 121.125 - 12521 - 76.920 = 31.384 \text{ k}$$

$$\Sigma M_{xx} = 1550 \text{ k}$$

$$e_x = \frac{31.384}{5910} = 5.30 \quad e = 15.0 - 5.30 = 9.70$$

$$e_y = \frac{1550}{5910} = 0.26'$$

$$A = 28.6 \times 30.0 = 858 \text{ FT}^2$$

MAXIMUM SOIL PRESSURE

$$f = \frac{2}{3} \frac{5910}{28.6 \times 5.30} = 26.00 \text{ ksf}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY CLAND WALL
COMPUTED M.T. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800A
DATE 11.74 PAGE 17 OF PAGES

LANDWALL GATE MONOLITH #17 (CONT'D)

$$\Sigma V = 5910^k \quad \Sigma H = 2685^k$$

$$\Sigma M_{yy} = 5910 \times 9.70 = 57200^k$$

1. SOIL PRESSURE $f = 26.00 \text{ KSF}$

2. $R = 6500.0^k$ OUTSIDE MIDDLE $\frac{1}{2}$ BY $2.20'$ 4.70

3. $\frac{\Sigma H}{\Sigma V} = \frac{2685}{5910} = .455$

4. $FSS = \frac{5910 \times .625}{2685} = 1.38$

5. $FSOT = \frac{108304}{76920} = 1.41$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>OF STABILITY C LAND WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>11.7.4</u> PAGE <u>19</u> OF <u> </u> PAGES

LOWER LAND GUIDE WALL MONOLITH #1 (CONT'D)

	LOADS IN KIPS	V ↓	V ↑	H ←	H →	ARM	M _A ↑	M _A ↓
C ₁	23.0 × 30.7 × 2.5 × .15	266				2.5	667	
C ₂	7.0 × 5 × 33 × .15	173				2.5	435	
C ₃	7.5 × 5 × 33 × .15	185				3.75	697	
C ₄	9.0 × 33 × .088	26				15.0	390	
C ₅	23.5 × 18.0 × 33 × .15	2090				9.0	18,800	
C ₆	80.0 × 33 × 6 × .088		✓ 139			8.0		✓ 1113
	80.0 × 33 × 4 × .150		✓ 158			8.0		✓ 1263
C ₇	3 × 96 × .088		✓ 25			2.0		✓ 50
C ₁₁	10.4 × 3 × 23.5 × .15	110				20.0	2200	
E ₈	13.0 × 30.7 × 11.5 × .115	530				11.5	6100	
E ₉	13 × 7 × 33 × .115	345				11.5	3970	
E ₁₀	10.5 × 5 × 33 × .115	200				12.75	2550	
E ₁₁	10.4 × 3 × 35 × .115	126				20.0	2520	
W ₁	.81 × 18 × 33.0		✓ 482			9.0		✓ 4350
W ₁₁	.81 × 3 × 10.4		25			20.0		✓ 500
	Σ	4051	829			Σ	38329	7276

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>OF STABILITY CLAND WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.T.</u> CHECKED <u>R.M.M.</u>	DATE <u>11.7.4</u> PAGE <u>20</u> OF <u> </u> PAGES

LOWER LAND GUIDE WALL MONOLITH #1 (CONT'D)

$H_{E1} = 4 \times .97 \times \frac{30.7}{2} \times \frac{23.0}{3} \times \frac{1}{4} = 114.0$	43.17	4.950 ^{1k}
$H_{E2} = .97 \times 22.5 \times 30.7 \times \frac{1}{2} = 335.0$	24.25	8.120
$H_{E3} = .95 \times \frac{1}{2} \times 22.5 \times 33.0 = 352.0$	20.50	7.220
$H_{E4} \left\{ \begin{array}{l} .95 \times 13.0 \times 33.0 \\ .97 \times 13.0 \times 33.0 \times 0.5 \end{array} \right. = 408.0$	6.50	2.660
$H_{E5} = .34 \times 13.0 \times 33.0 \times \frac{1}{2} = 73.0$	4.33	3.16
<u>1490.0^k</u>		<u>24.616^{1k}</u>

RESULTANT $H = 1490.0k$

$$\frac{24.616}{1490.0} = 16.50$$

$$\Sigma V = 4051 - 829 = 3222^k$$

$$\Sigma M_A = 38329 - 7276 - 24616 = -6437^k$$

$$\frac{6437}{3222} = 2.0'$$

1. $R = 3560k$ OUTSIDE MIDDLE $\frac{1}{3}$

$$2. \frac{\Sigma H}{\Sigma V} = \frac{1490}{3222} = 0.463$$

$$3. FSS = \frac{3222 \times .625}{1490.0} = 1.35$$

$$4. FSOT = \frac{31.053}{24616} = 1.26$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u> <u>OF STABILITY CLAND WALL</u>	PROJECT <u>LED #1</u>
	COMPUTED <u>M.J.</u> CHECKED _____	FILE NO. <u>800A</u>
		DATE <u>11/74</u> PAGE <u>21</u> OF _____ PAGES

LOWER LAND GUIDE WALL MONOLITH #1 (CONT'D)

SOIL PRESSURE VALUE

$$V = 3222^k \quad M_R = 6437^k \quad \alpha = 2.0' \quad c = 7.0'$$

$$f = \frac{2}{3} \times \frac{3222}{33 \times 2} = 33.6 \text{ ksf}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LOWER GUIDE WALL
BACKFILL TO TOP OF WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800A
DATE 8.74 PAGE 23 OF PAGES

LOWER LAND GUIDE WALL (CONTD)

LOADS IN KIPS	VERT. ↓	VERT. ↑	HORIZ. →	HORIZ. ←	ARM	MOM _A	MOM _A
C ₁	5.3				2.5	13.2	
C ₂	5.6				3.8	21.3	
C ₃	7.5				5.0	37.5	
C ₄	5.6				6.25	35.0	
C ₅	12.0				10.00	120.0	
E ₁	11.6				12.50	146.0	
E ₂	6.9				13.75	95.0	
E ₃	5.5				15.00	82.5	
E ₄	2.5				16.25	40.7	
W ₁ 1.63 × 0.63 × 20		2.1			10.00		21.0
Σ	62.5	2.1				591.2	21.0
H _w .73 × 11.63/2			4.3	4.3			
H _{E1} 1.23 × 22.37/2				13.7	19.1		262.0
H _{E2} 1.23 × 11.63				14.4	5.3		83.6
H _{E3} .40 × 11.63/2				2.3	3.0		9.0
ΣH				30.4			354.6

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LOWER GUIDE WALL
BACKFILL TO TOP OF WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT L.E.D. #1
FILE NO 800A
DATE 8.74 PAGE 24 OF 24 PAGES

LOWER LAND GUIDE WALL, (CONT'D)

CHECK STABILITY INCLUDING ROCK FILLED CRIB

$$10.0 \times 20.0 \times (10.063) = 7.3 \text{ k}$$

$$M_A = 7.30 \times 10.0 = 73.0 \text{ k} \quad \Sigma V = 62.5 - 2.1 + 7.3 = 67.7 \text{ k}$$

$$\Sigma H_A = 591.2 - 21.0 - 354.6 + 73.0 = 288.6 \text{ k}$$

$$a = \frac{288.6}{67.7} = 4.26'$$

1. RESULTANT OUTSIDE MIDDLE $\frac{1}{2}$ BY 74'

$$2. \frac{\Sigma H}{\Sigma V} = \frac{30.4}{67.7} = 0.45 \text{ (SEE BELOW)}$$

MAXIMUM SOIL PRESSURE

$$3. f_{\text{soil}} = \frac{2 \times 67.70}{3 \times 4.26} = 10.6 \text{ ksf}$$

$$\text{IF } \frac{\Sigma V \times 0.625}{\Sigma H} = 1.5, \frac{\Sigma V}{\Sigma H} = 2.73 \text{ OR } \frac{\Sigma H}{\Sigma V} = .417 \text{ MAX}$$

$$F.S. = \frac{67.7 \times 0.625}{30.4} = 1.39$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LOWER GUIDE WALL
BACKFILL TO TOP OF WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT L.E.D. #1
FILE NO. 800A
DATE 8.74 PAGE 25 OF PAGES

LOWER LAND GLIDE WALL (CONT'D)

CHECK STABILITY C TOP OF CRIB

$$\Sigma V = 36.0 + 26.5 - 2.1 = 60.4^k$$

$$\Sigma H = 1.23 \times 22.37/2 + 1.23 \times 1.63 + 1.67 \times 0.034/2$$

$$\Sigma H = 13.70 + 2.06 + .05 = 15.81^k$$

$$\Sigma M = 591.2 - 21.0 - 13.7 \times 9.1 - 2.06 \times 1.815 - .05 \times 1.54$$

$$\Sigma M = 591.2 - 148.0 = 443.2^k$$

$$a = \frac{443.2}{60.4} = 7.34$$

1. $e = 2.66'$ WITHIN MIDDLE $\frac{1}{3}$

$$2. \frac{\Sigma H}{\Sigma V} = \frac{15.81}{60.4} = .263 < .367 \text{ OK}$$

$$3. \int B \cdot W R G = \frac{60.4}{20.0} \pm \frac{60.4 \times 2.66}{66.7} = 3.02 \pm 2.40 \begin{cases} \text{MAX } 5.42 \text{ KSF} \\ \text{MIN } 0.62 \text{ KSF} \end{cases}$$

$$S = \frac{20.0^2}{6} = 66.7$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LOWER GUIDEWALL
BACKFILL TO TOP OF WALL
COMPUTED M.T. CHECKED R.N.M.

PROJECT L.F.D. #1
FILE NO. 800A
DATE 8.74 PAGE 26 OF PAGES

LOWER LAND GUIDEWALL (CONT'D)

CHECK STABILITY ASSUMING CRIBS FILLED IN WITH CONCRETE

$$\text{CRIB WT } 10 \times 20 \times (.15 \times .063) = 17.4 \text{ k/ft}$$

$$M_A' = 17.4 \times 10 = 174.0 \text{ k' } \quad 174.73 = 101 \text{ k'}$$

$$\Sigma M_A = 288.6 + 101 = 389.6 \text{ k'}$$

$$\Sigma V = 67.7 + (17.4 \times 7.3) = 77.8 \text{ k}$$


$$a = \frac{389.6}{77.8} = 5.0'$$

1. RESULTANT AT MIDDLE $\frac{1}{2}$ (BY 0.0')

$$2. \frac{\Sigma H}{\Sigma V} = \frac{30.4}{77.8} = .391 \text{ [4.917 (MIN.) FOR } f_{fric} = .625 \text{ AND F.S. = 1.5]}$$

$$3. f_{soil} = \frac{2}{3} \frac{77.8}{5.0} = 10.4 \text{ ksf}$$

LOWER LAND GUIDE WALLS - CRIBS FILLED WITH GROUT
(BACKFILL REMOVED)



$K = 0.50$ (SOIL PRESSURE AT REST CONDITION)

$$\Sigma V = 59.3 \text{ k}$$

$$\Sigma H = 12.1 \text{ k}$$

$$\Sigma H_A = 409.4 \text{ k} \quad \alpha = \frac{409.4}{59.3} = 6.9' \quad e = 3.10' < \frac{240}{6} = 333$$

$R = 61.2^k$ INSIDE MIDDLE $\frac{1}{3}$

$$\frac{\Sigma H}{\Sigma V} = 0.205 < 4/7 / F_r = 0.625 F_{SS} = 1.5'$$

$$FSS = \frac{5934.625}{13.1} = 3.06$$

$$f_{swr} = \text{MAX } 5.73 \text{ ksf, MIN } .21 \text{ ksf}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LOWER GUIDE WALL</u>	PROJECT <u>LED #1</u>
	<u>BACKFILL REMOVED TO EL 697.6</u>	FILE NO. <u>800A</u>
COMPUTED <u>M.J.</u>	CHECKED <u>R.N.M.</u>	DATE <u>8.74</u> PAGE <u>28</u> OF <u> </u> PAGES

LOWER LAND GUIDE WALL WITH BACKFILL REMOVED TO EL 697.6
(CONCRETE FILLED CRIB)

	LOADS IN KIPS	VERT. ↓	VERT. ↑	HORIZ. ↓	HORIZ. ↑	ARM	MA ↓	MA ↑
C ₁		5.3					13.2	
C ₂		5.6					21.3	
C ₃		7.5					37.5	
C ₄		5.6					35.0	
C ₅		12.0					120.0	
C ₆	10.0 x 20.0 x .087	17.4				10.	174.0	
E ₃		5.5					82.5	
E ₄		2.5					40.7	
W ₁			2.1			10.		21.0
Σ		61.4	2.1				524.2	21.0
H _{E3}	10.4 x .58 / 2				3.0	15.1		45.3
H _{E4}	11.63 x .58				6.8	5.8		39.5
H _{E5}	11.63 x .20				2.3	3.9		9.0
Σ		61.4	2.1		12.1		524.2	114.8

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LOWER GUIDE WALL
BACKFILL REMOVED TO EL 697.6
COMPUTED M.T. CHECKED R.N.M.

PROJECT L. & D. #1
FILE NO. 800A
DATE 8.74 PAGE 29 OF PAGES

LOWER LAND GUIDE WALL WITH BACKFILL REMOVED (CONT'D)

$$\Sigma V = 61.4 - 2.1 = 59.3^k$$

$$\Sigma H = 12.1^k$$

$$\Sigma M_A = 524.2 - 114.8 = 409.4^k$$

$$a = \frac{409.4}{59.3} = 6.9$$

1). $e = 10.0 - 6.9 = 3.1$ RESULTANT WITHIN MIDDLE 3

$$M = 59.3 \times 3.1 = 183.8^k$$

2). $\frac{\Sigma H}{\Sigma V} = \frac{12.1}{59.3} = 0.205$

3). $f_{soil} = \frac{59.3}{20.0} \pm \frac{183.8}{66.7} = 2.97 \pm 2.76 \begin{cases} \text{MAX} & 5.73 \text{ KSF} \\ \text{MIN} & 0.21 \text{ KSF} \end{cases}$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITION
DESTABILITY
COMPUTED M.T. CHECKED R.N.M.

PROJECT LEO #1
FILE NO. 800A
DATE 11-74 PAGE 30 OF PAGES

LOWER LAND GUIDE WALLS - BACKFILL REMOVED (CON.'M)
(SOIL PRESS. 42PSF & 26PSF)

$$H_{E1} = .042 \times 10.37^2 / 2 = 2.25^k \quad \times 15.10 \quad \begin{matrix} M_A^{\curvearrowright} \\ 34.00^k \end{matrix}$$

$$H_{E2} = .435 \times 11.63 = 5.07^k \quad \times 5.80 \quad 29.40$$

$$H_{E3} = .304 \times 11.63 / 2 = 1.77^k \quad \times 3.90 \quad \underline{6.92}$$

$$\Sigma H = 9.09^k \quad 70.32^k$$

$$\Sigma M_A = 524.2 - 21.0 - 70.3 = 432.9^k \cdot 2$$

$$\Sigma V = 61.4 - 2.1 = 59.3^k$$

$$\Sigma H = 9.1^k$$

$$a = \frac{432.9}{59.3} = 7.3'$$

$$e = 2.7' < 3.33' \quad (\text{USED})$$

1) $R = 59.3^k$ INSIDE MIDDLE $\frac{1}{3}$ BY 0.63'

2) $\frac{\Sigma H}{\Sigma V} = \frac{9.10}{59.3} = .154$

3) $f_{\text{SOIL}} = \frac{59.3}{20.0} \pm \frac{59.3 \times 2.7}{66.70} \quad S = \frac{20.0^2}{6} = 66.70 \text{ FT}^2$

$$f_{\text{SOIL}} = 2.97 \pm 2.42$$

$$f_{\text{MAX}} = 5.39 \text{ KSF} \quad f_{\text{MIN}} = .55 \text{ KSF}$$

4) $FSS = \frac{59.3 \times 62.5}{9.10} = 4.07$

5) $FSOT = 5.75$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITION
DESTABILITY


COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1

FILE NO. 800A

DATE 11.74 PAGE 31 OF PAGES

LOWER LAND GUIDE WALLS - BACKFILL REMOVED



1). $R = 59.3^k$ INSIDE MIDDLE $\frac{1}{3}$ BY 0.63

2). $\frac{\Sigma H}{\Sigma V} = \frac{9.10}{59.3} = .153$

3). $f_{SOIL} = \begin{matrix} \text{MAX} & 5.89 \text{ ksf} \\ \text{MIN} & 0.55 \text{ ksf} \end{matrix}$

4). $FSS = \frac{59.3 \times .625}{9.10} = 4.07$

5). $FSOT = 5.75$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LOWER GUIDE WALL</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	<u>STABILITY, CONSTRUCTION, CONDITION</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>JL</u>	DATE <u>2/75</u> PAGE <u>31 a</u> OF <u> </u> PAGES

16/b. STABILITY OF LOWER GUIDE WALL MONOLITHS 6-12 DURING CONSTRUCTION PERIOD (Backfill removed) Ref. page 27

According to water level readings in borehole No. 74-84 and downstream of the lock chamber the difference in hydraulic grade line was about 7' on Sept. 10, 1974. Using the same difference, assume that the hydraulic grade line behind the lower guide wall monoliths is approximately, $674 + 7 = 681'$ when the construction area is dewatered. Assume 3' of surcharge


(1) "R" inside middle $\frac{1}{3}$ by 0.11'

(2) $\frac{EH}{EV} = 0.22$

(3) $FSS = 2.84$

(4) $f_{ss1} = 6.95$ KSF max
0.12 KSF min

(5) $FSOT = 3.78$



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LOWER GUIDE WALL</u>	PROJECT <u>LOCK & DAM #1</u>
	STABILITY, CONSTRUCTION CONDITION	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u>	CHECKED <u>JH</u>
	DATE <u>2/75</u> PAGE <u>316</u> OF <u> </u> PAGES	

CONSTRUCTION CONDITION

		H → ⊕	V ⊕ ↓	ARM	⊕ → MA	⊙ MA
①-⑤	See page 28		+36.0			227
③			+55	15.0		83
④			+2.5	16.25		41
⑥	10 x 20 x 0.15		30.0	10		300
①	0.0625 x 5.4 x 20 x $\frac{1}{2}$		-3.4	13.3	45	
HS	5 x 0.042 x 22	+4.6		11.0	51	
HE1	0.042 x (16.6) x $\frac{1}{2}$	+5.8		10.9	63	
HE2	0.042 (16.6) x 5.4	+3.8		2.7	10	
HE3	0.026 (5.4) x $\frac{1}{2}$	+0.4		1.8	1	
HW	0.0625 (5.4) x $\frac{1}{2}$	+0.9		1.8	2	
		$\Sigma H =$ <u>15.5^K</u>	$\Sigma V =$ <u>70.6^K</u>		172 ^K $\Sigma M_A =$ <u>479^K</u>	651 ^K

$$1) \bar{X} = \frac{479}{70.6} = 6.78' \quad e = 3.22'$$

Resultant inside middle $\frac{1}{3}$, 0.11 ft

$$2) \frac{\Sigma H}{\Sigma V} = \frac{15.5}{70.6} = 0.22 \quad (3) FSS = 2.84$$

$$4) f_{soil} = \frac{70.6}{20} \left(1 \pm \frac{6 \times 3.22}{20} \right) = 6.95 \text{ KSF max.} \\ - 0.12 \text{ KSF min.}$$


$$5) F_{TOT} = \frac{651}{172} = 3.78$$

**HARZA
ENGINEERING
COMPANY
CHICAGO**

SUBJECT STABILITY CONDITIONS
AT INTERMEDIATE WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 32 OF PAGES

INTERMEDIATE WALL MONOLITHS #4-16



NORMAL OPERATING CONDITION

- 1). RESULTANT OUTS. $\frac{1}{2}$ BY 0.59
- 2). $\frac{FH}{2V} = \frac{2031}{5844} = .348$
- 3). $f_{sol} = 10.90 \text{ ksf}$
- 4). $FSS = 1.80$
- 5). $FSOT = 1.94$

CONSTRUCTION CONDITION
(ONE LOCK EMPTY)

- 1). RESISTANT OUTS. $\frac{1}{3}$ BY 0.56
- 2). $\frac{SH}{SV} = .354$
- 3). $f_{SON} = 11.32 \text{ KSE}$
- 4). $FSS = 1.77$
- 5). $FSOT = 2.02$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILITY CONDITIONS
AT INTERMEDIATE WALL
COMPUTED M.J. CHECKED R.N.W.

PROJECT LED #1
FILE NO 800A
DATE 11.74 PAGE 33 OF PAGES

INTERMEDIATE WALL MONOLITHS #4-16

		$V \downarrow_k$	$V \uparrow_k$	$H \rightarrow_k$	$H \leftarrow_k$	ARM	M_e^2	M_e^1
C1	^{4.2} 35.0 x 57.0 x 28 x .15	8380				0.		
C2	^{1.2} (10 x 23 + 170) x 28 x .035 _{5 x 17 + 5 x 11 + 6 x 5 = 11}		392			0.		
C3	$\pi \times 4.8^2 \times 28 \times .088$		178			0.		
C4	$\pi \times 4.8^2 \times 28 \times .088$		178			0.		
C5	2 x 2.5 x 4.0 x 28 x .088	49				0.		
C6	5.5 x 3.0 x 28 x .088	41				16.0		660
		Σ 8470	748					
HW1	3.10 x 29.75 x 28				2148	16.5		35500
HW2	.73 x 11.5 $\frac{1}{2}$ x 28			117	384	450		
W1	3.10 x 17.5 x 28		1520			5.83		8860
W2	.73 x 17.5 x 28		358			5.83	2090	
				Σ 117	Σ 2148		Σ 2540	45020

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILITY CONDITIONS
AT INTERMEDIATE WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 34 OF PAGES

INTERMEDIATE WALL MONOLITHS #4-16 (CONT'D)

NORMAL OPERATING CONDITION (W. L @ 725.2' f 687.2')

$$\sum V = 8470 - 748 - 1520 - 358 = 5844 \text{ k}$$

$$\sum H = 2148 - 117 = 2031 \text{ k}$$

$$\sum M_E = 45020 - 2540 = 42480 \text{ k'$$

$$e = \frac{42480}{5844} = 7.26' \quad \frac{400}{6} = 6.67' \quad \alpha = 12.74'$$

1). RESULTANT OUTSIDE MIDDLE $\frac{1}{3}$ BY 0.59'

$$2). \frac{\sum H}{\sum V} = \frac{2031}{5844} = .348$$

$$3). f_{sok} = \frac{2}{3} \times \frac{5844}{2.9 \times 12.74} = 1090 \text{ ksf}$$

$$4). F_{SS} = \frac{5844 \times 6.25}{2031} = 1.80$$

$$5). F_{SOT} = \frac{7722 \times 20}{79550} = 1.94$$

$$8470 - 748 = 7722 \text{ k}$$

$$M_A = 35500 + .73 \times 35.0 \times 28.0 \times 20 + \frac{2.37}{2} \times 35.0 \times 28 \times 25.84 - 450 = 35500 + 14300 + 30200 - 450 = 79550$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	STABILITY CONDITIONS	PROJECT	LED #1
		AT INTERMEDIATE WALL	FILE NO.	800A
	COMPUTED	M.J.	CHECKED	R.N.M.
			DATE	11.74 PAGE 35 OF 35 PAGES

INTERMEDIATE WALL MONOLITHS #4-16

REHABILITATION CONDITION - ONE LOCK EMPTY (CONSTRUCTION)

2268

$$\Sigma V = 8470 - 748 - 1520 - 126 = 6076^k$$

$$\Sigma H = 2148^k$$

$$C_3 = \pi \times 4.8^2 \times 28 \times .15 = 304^k$$

$$\frac{304}{178} = 1.71$$

$$\Sigma M_L = 45,020 - 126 \times 8.7 = 43,920^k$$

$$e = \frac{43,920}{6076} = 7.23'$$

$$a = 12.77$$

1). RESULTANT OUTSIDE MIDDLE $\frac{1}{3}$ BY .56'

$$2). \frac{\Sigma H}{\Sigma V} = \frac{2148}{6076} = .354$$

$$3). f_{soil} = \frac{3 \times 6076}{28 \times 12.77} = 11.32 \text{ ksf}$$

$$4). F_{SS} = \frac{6076 \times .625}{2148} = 1.77$$

$$5). F_{OT} = \frac{7722 \times 20}{76450} = 2.02$$

$$M_A = 35,500 + \frac{310}{2} \times 350 \times 28.0 \times 25.84 + 126 \times 12.3 =$$

$$= 35,500 + 39,400 + 1,550 = 76,450^k$$


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
STABILITY - TEMPORARY CONSTRUCTION
COMPUTED R.N.M. CHECKED JH

PROJECT LOCK & DAM #1
FILE NO. 800 A
DATE 2/75 PAGE 35a OF PAGES

REHABILITATION PLAN 2 - MONOLITH NO. 4
INTERMEDIATE WALL, LANDWARD LOCK REBUILT
RIVERLOCK — NO CHANGE

- 1) Resultant inside middle $\frac{1}{3}$ by .57
- 2) Factor of sliding = .39
- 3) Sliding safety factor = 1.61
- 4) Bearing pressure = 9.66 ksf
- 5) F.S.O.T. = 1.89



$$\begin{aligned}\Sigma H_x &= \text{---} \text{---} \text{---} 1858 \text{ K} \leftarrow \\ \Sigma V &= \text{---} \text{---} \text{---} 4789 \text{ K} \downarrow \\ \Sigma M_x &= \text{---} \text{---} \text{---} + 923 \text{ K} \\ \Sigma M_y &= \text{---} \text{---} \text{---} - 29343 \text{ K}\end{aligned}$$

$$\begin{aligned}\frac{\Sigma H_x}{\Sigma V} &= \frac{1858}{4789} = .39 \quad SSF = 1.61 \\ e_x &= \frac{\Sigma M_y}{\Sigma V} = \frac{29343}{4789} = 6.1 \quad \frac{e_x}{40} = 0.15 \\ e_y &= \frac{\Sigma M_x}{\Sigma V} = \frac{923}{4789} = .2 \quad \frac{e_y}{24.3} = 0.01 \\ f_s &= \frac{1.96 \times 4789}{972} = 9.66 \text{ ksf} \\ F.S.O.T. &= \frac{6102 (17.5 + 1.47)}{133 \times 23.33 + 30657} = 1.89\end{aligned}$$

$8862 - 816 + 936 = 8982$
 $7272 - 1386 + 51 + 93 + 122 = 6102$
 $\frac{8982}{6102} = 1.47$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u>	PROJECT <u>LOCK & DAM #1</u>
	STABILITY-TEMPORARY CONSTRUCTION	FILE NO <u>8001</u>
	COMPUTED <u>R.W.M.</u> CHECKED <u>JJ</u>	DATE <u>2/75</u> PAGE <u>35b</u> OF <u> </u> PAGES


REHABILITATION PLAN 2 - MONOLITH NO 4 (CONT'D)

		V	Y	X	M _x	M _y
C.C. OPENINGS	① 14 x 14 x 24 (-0.15)	- 706	2.95	-7.67	+2083	+5415
	$\frac{1}{2} \times 8.0 \times 7.0 \times 9 (-0.15)$	+ 38	+6.5	-7.67	-247	-291
	② 3 x 10 x 24 (-0.15)	- 108	-8.0	-7.67	-864	+828
	③ $\frac{15.5 + 21}{2} (7.8)(9)(-0.15)$	- 192	+8.5	-7.67	+1632	+1473
	④ $\frac{21 + 17}{2} (4.35)(9)(-0.15)$	- 110	+2.2	-7.67	+242	+844
	⑤ $\frac{17 + 12}{2} (7.2)(-0.15)(9)$	- 141	-3.6	-7.67	-508	+1081
	⑥ $\frac{12 + 11}{2} (5)(9)(-0.15)$	- 78	-9.65	-7.67	-753	+598
Y	⑦ 24.3 x 11 x 9 (-0.15)	- 361	0	+7.67	0	- 2769
	3.5 x 11 x 9 (-0.15)	- 52	+10.5	-7.67	+546	+399
	2.0 x 11 x 9 (-0.15)	- 30	-6.1	-7.67	-183	+230
	3.5 x 3.0 x $\frac{1}{2}$ x 9 (-0.15)	- 7	+9.8	-7.67	+67	+54

$$V_1 = 1386^k$$

$$M_x = +923^k \quad +8862^k$$

GROSS CONC.	57 x 24.3 x 35 x 0.15 =	+7272	0	0	0	0
	3 x 8 x 24.3 x 0.088 =	+ 51	0	16	0	-816
	4 x 5 x 24.3 x 0.093 =	+ 43	0	0	0	0
	Water: 8 x 10 x 24.3 x 0.0625	+122	0	-7.67	0	+936
	11 = 49.5 x 0.0625 x 35 x 24.3 x $\frac{1}{2}$ =	-1313	0	5.84	0	-7668
$\Sigma H_x = \frac{49.5}{2} \times 0.0625 \times 24.3 = 1856^k$						-30657
$\Sigma V = 4789^k$						
					$\Sigma M_x = +923^k$	
						$\Sigma M_y = -29343^k$

HARZA
ENGINEERING
COMPANY
CHICAGOSUBJECT INTERMEDIATE WALL
STABILITY-TEMPORARY CONSTRUCTION
COMPUTED R.H.M. CHECKED _____PROJECT LOCK & DAM #1
FILE NO. 800 A
DATE 2/75 PAGE 35C OF _____ PAGESREHABILITATION PLAN 2 - MONOLITH #4 (CONT'D)


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
STABILITY - TEMPORARY CONSTRUCTION
COMPUTED R. N. M. CHECKED J

PROJECT LOCK & DAM NO. 1
FILE NO. 800 A
DATE 2/75 PAGE 35d OF PAGES

REHABILITATION PLAN 2 - MONOLITH NO. 5

INTERMEDIATE WALL LANDWARD LOCK CULVERT REBUILT *
NO CHANGE IN RIVER LOCK



- 1) Resultant outside middle $\frac{1}{3}$ by 0.9'
- 2) Factor of sliding = 0.41
- 3) Factor of safety against sliding = 1.54
- 4) Bearing pressure = 11.30 KSF
- 5) F.S.O.T. = 1.90

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u>	PROJECT <u>LOCK & DAM #1</u>
	<u>STABILITY-TEMPORARY CONSTRUCTION</u>	FILE NO. <u>800A</u>
	COMPUTED <u>R. H. M.</u> CHECKED <u>JL</u>	DATE <u>2/75</u> PAGE <u>35</u> OF <u>35</u> PAGES

REHABILITATION PLAN 2 - MONOLITH #5 (CONT'D)


CONCRETE		ARM		MOMENT	
		Y	X	M_x	M_y
①	$7 \times 13.5 \times 9 \times (-0.15) = -128$	+6.5	-7.67	+832	981
②	$\frac{15+13}{2} \times 4.8 \times 8 (-0.15) \times 2 = -161$	-12.5	0.0	-2013	0
③	$\frac{13+12}{2} \times 5.1 \times 8 (-0.15) \times 2 = -153$	-7.5	0.0	-1148	0
④	$\frac{12+11.5}{2} \times 5 \times 8 (-0.15) \times 2 = -141$	-2.5	0.0	-353	0
⑤	$10 \times 15.1 \times 8 (-0.15) \times 2 = -362$	+7.5	0.0	+2715	0
⑥	$10 \times 7 \times (9-8) (-0.15) = -11$	+6.0	-7.67	+66	+84
⑦	$8 \times 12.5 \times 9 (-0.15) = -135$	+6.5	-7.67	+878	+1035
⑧	$5.5 \times 5 \times 9 (-0.15) = -37$	+6.5	-7.67	+241	+284
⑨	$30 \times 9 \times 11 (-0.15) = -446$	0	-7.67	0	+3419
⑩	$10^2 (-0.15) \times 13 = -195$	+8.0	+7.67	+1560	-1495
⑪	$3 \times 9 \times 13 (-0.15) = -53$	-1.5	+7.67	-80	-406
	<u>-1822</u>				
⑫	$35 \times 57 \times 30 \times 0.15 = +8978$	0	0	0	0
⑬	$3 \times 3 \times 30 \times 0.088 = +64$	0	-16.0	0	-1024
⑭	$4 \times 5 \times 30 \times 0.088 = +53$	0	0	0	0
	<u>+8978</u>				
	$V_1 = + \frac{8978}{7273}$			$M_x = 2690$	
				$\Sigma M_y = 12878$	

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
STABILITY - TEMPORARY CONSTRUCTION
COMPL. ED. P.V.M. CHECKED J1

PROJECT LOCK & DAM #1
FILE NO. 800 A
DATE 2/75 PAGE 35 OF 35 PAGES

REHABILITATION PLAN 2 - MONOLITH # 5 (cont'd)



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	STABILITY-TEMPORARY CONSTRUCTION	FILE NO <u>800A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>JL</u>	DATE <u>2/1/75</u> PAGE <u>354</u> OF <u>357</u> PAGES

REHABILITATION PLAN 2 - MONOLITH NO. 5 (CONT'D)

	H	V	Y	X	M _x	M _y
<u>Water in riverward tunnel</u>		+7318 +7273	.4	0.28 .37	+2698	+2878
② 80 x 0.0625 / 0.15		+33	-125	+7.67	+413	+253
③ 77 x 0.0625 / 0.15		+32	-7.5	+7.67	+240	+245
④ 70 x 0.0625 / 0.15		+29	-2.5	+7.67	+73	+222
⑤ 181 x 0.0625 / 0.15		+75	+7.5	+7.67	-563	+575
		+164		1.1	+163	(1294)
H _x $\frac{49.5^2}{2} \times 0.0624 \times 30$	-2293			z = 16.5		-37835
U $49.5 \times 0.0624 \times 35 \times 30$		-1628 ²		+5.84		-9472

$$\Sigma H = -2293$$

$$\Sigma V = 5651$$

$$\Sigma M_x = +2861$$

$$\Sigma M_y = -43134$$

$$e_x = \frac{43134}{5651} = 7.6$$

$$\frac{e_x}{40} = 0.19$$

$$e_y = \frac{2861}{5651} = 0.51$$

$$\frac{e_y}{30} = 0.02$$

$$e > \frac{1}{6} \text{ by } 0.9$$


$$f = 2.4 \times 5651 = 11.80 \text{ KSF}$$

$$\frac{\Sigma H}{\Sigma V} = \frac{2293}{5651} = .406$$

$$SSF = 1.54$$

$$F.O.T. = \frac{7273 \times 20.25 + 164 \times 21}{37950 + 1628 \times 25.84} = \frac{151700}{74147} = 1.90$$

INTERMEDIATE WALL GATE MONOLITH #1B-EXISTING CONDITIONS




HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERM. WALL
DOWNSTR. GATE MONO. #18
COMPUTED M. J. CHECKED R. M.

PROJECT L.S.D. #1
FILE NO. 800A
DATE 9.7.4 PAGE 37 OF PAGES

INTERMEDIATE WALL MONOLITH #18 (CONT'D)

HYDROSTATIC LOAD



$$\begin{array}{r} 2.10 \\ .91 \\ \hline 1.19 \end{array} \quad \begin{array}{r} 1350 \\ 0.0341 \end{array}$$


$.15 \times 9.0 = 1.35$	$\times 6.0$	8.12
$.910 \times 9.0 = 8.20$	$\times 4.5$	37.00
$1.03 \times 17.0 = 17.50$	$\times 17.5$	307.00
$1.79 \times 9.0 = 16.10$	$\times 30.5$	492.00
$.15 \times 9.0 = 1.35$	$\times 32.0$	43.30
$.29 \times 17.0 = 4.92$	$\times 20.3$	100.00
		<u>987.42</u>
$49.42 \times 28.0 = 1380.0$		
		<u>987.4</u>
		<u>49.42</u>
		$= 20.0'$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
DOWNSTREAM GATE MONO. #18
COMPUTED M. J. CHECKED RNM

PROJECT LED #1
FILE NO. 800 A
DATE 9.74 PAGE 38 OF PAGES

INTERMEDIATE WALL MONOLITH #18 (UNITED)



$$\sin 10 = .1736$$

$$\cos 10 = .9848$$

$$PL = (45.2 \times 23.7 + 26.4 \times 5.5) \times 32.75 = 2350 \text{ k}$$

$$V = 2350 \times .9848 = 2312 \text{ k} = Y1$$

$$2350 \times 16.37 + 11.2 H^2 = 2312 \times 30.8$$

$$38500 - 68200 = -11.2 H$$

$$H = X1 = 2650 \text{ k}$$

$$45.2 \times 23.7 = 1070.0$$

$$\frac{26.4 \times 5.5}{71.6} = \frac{145.0}{1215.0 \text{ k}}$$

$$Q = \frac{1215.0}{71.60} = 17.0 \text{ (ABOVE EL 676.10)}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u>	PROJECT <u>LED #1</u>
	<u>DOWNSTREAM GATE MONO. #18</u>	FILE NO <u>B30A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>B.N.M.</u>	DATE <u>9.74</u> PAGE <u>39</u> OF <u> </u> PAGES

INTERMEDIATE WALL DOWNSTREAM GATE MONO. #18

		VERT ↓ K.	VERT ↑ K.	HORIZ. → K.	HORIZ. ← K.	ARM	±M _{xx}	M _{yy}
MONOLITH		6.634					+87.100	116.980 ²
GATES L.L.		240					+ 4.920	-3.360
R.L.		230					+ 4.635	10.425
WATER INLANDWARD ELEVAT		357					+ 5.651	2.560
HYDROSTATIC, "↑"		-1380				1400 1500	-19.400	-20.800
GATE THRUST X↑				2650				54.300
" " Y↓				2210		20.5	-45.800	
HYDROSTATIC →				1.000				20.500
		6.081					37.606	181.105

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u> <u>DOWNSTREAM GATE MONO. #18</u> COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	PROJECT <u>LED #1</u> FILE NO. <u>800A</u> DATE <u>9.78</u> PAGE <u>40</u> OF <u> </u> PAGES
--	--	---

INTERMEDIATE WALL MONOLITH #18 (CONT'D)

HYDROSTATIC LOAD ON LAND LOCK SIDE

$$2.37 \times 38.0/2 + 2.37 \times 11.1 = 71.6$$

$$71.6 \times 14.0 = 1000 \text{ k} @ 17.0' \text{ ABOVE SILL EL } 676.1$$

$$M_{yy} = 1000 \times (17.0 + (676.1 - 672.6) \times 3.5) = 20,500 \text{ k'}$$

SOIL PRESSURE AND LOCATION OF RESULTANT

$$\Sigma V = 603 \text{ k}$$

$$\Sigma M_{xx} = 37,606 \text{ k'}$$


$$\alpha_{yy} = 6.10'$$

$$\Sigma M_{yy} = 181,105 \text{ k'}$$

$$\alpha_{xx} = 29.90'$$

$$e_{yy} = 14.0 - 6.10 = 7.90' \quad \text{OUTSIDE MIDDLE BY } 0.90'$$

$$e_{xx} = 29.9 - 17.5 = 12.4' \quad \text{OUTSIDE MIDDLE BY } 3.65'$$



$$A = 29.5 \times 45.0 = 980.0 \text{ FT}^2$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u>	PROJECT <u>L.F.D #1</u>
	<u>DOWNSTREAM GATE MONO #1B</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M. J.</u> CHECKED <u>B.N.M.</u>	DATE <u>9.74</u> PAGE <u>41</u> OF <u> </u> PAGES

INTERMEDIATE WALL MONOLITH #1B (CONT'D)

SOIL PRESSURE AT EDGE

$$\frac{C_{x1}}{d} = \frac{12.40}{35.0} = .356$$

$$\frac{C_{y1}}{b} = \frac{7.90}{28.0} = .282$$

$$C \approx 12.0$$

$$f = 12 \cdot \frac{6081.0}{980} = 74.5 \text{ ksf}$$

$$FSOT = \frac{6081 \times 17.5}{2650 \times 20.5 + 1000 \times 20.5 + 1380 \times 20.0} = \frac{106.000}{102.600} = 1.03$$

$$\Sigma H = 2650 + 1000 = 3650 \text{ k}$$

$$\Sigma V = 6081 \text{ k}$$

$$FSS = \frac{6081 \times .625}{3650} = 1.04^*$$


* ACTUAL SLIDING WILL BE RESISTED BY SILL SLAB

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILITY OF RIVER WALL
MONOLITH #1 DURING CONSTRUCTION
COMPUTED M.T. CHECKED R.N.M.

PROJECT L&D #1
FILE NO 800A
DATE 1.75 PAGE 41 OF 42 PAGES

STABILITY OF MONOLITH #1 DURING CONSTRUCTION



$$(25 \times 36 - 3.5 \times 18) \times 1.5 = 125k$$

$$- 13.3 \times 0.0625 \times 25$$


$$= - 21$$

$$\Sigma Y = 104k$$

$$900 \times 1.5 = 135 \times 12.5 = 1688$$

$$63 \times 1.5 = -10 \times 23.5 = -235$$

$$125k \downarrow M_R = 1453$$



$$1.42 \times 25 / 2 = 17.8k$$

$$17.8k$$

$$H_{W1} = 1.67 \times 26.7 \times \frac{1}{2} = 22.6k$$

$$+ 18.20 = 408.1k$$

$$H_{W2} = 1.67 \times 9.3 = 15.6$$

$$+ 4.05 = 73$$

$$479.1k$$

$$\Sigma H = 37.8k$$

$$\Sigma M_L = 479 \times 17.9 \times 4.17 = 554.0$$

$$21 \times 12.5 = 263$$

$$17.8 \times 16.75 = 298$$

$$M_O = 1040 \downarrow$$

OVER

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RIVER WALL MONOLITH</u>	PROJECT <u>LEO #1</u>
	<u>#1, STABILITY DURING CONSTRUCTION</u>	FILE NO <u>80017</u>
COMPUTED <u>M.T.</u>	CHECKED <u>R.N.M.</u>	DATE <u>1.25</u> PAGE <u>41</u> OF <u>6</u> PAGES

STABILITY OF MONOLITH #1 DURING CONSTRUCTION (CONT'D)

$$\Sigma V = 125.0 - 21.0 - 17.8 = 86.2 \text{ k}$$

$$\Sigma M_L = 554.0 \text{ k} \quad \Sigma H = 37.8 \text{ k}$$

$$e = \frac{554}{86.2} = 6.42' \quad a = 6.08' \quad \left(\frac{b}{6} - e\right) = 4.16 - 6.42 = -2.26'$$

1). $R = 95.0$ OUTSIDE MIDDLE $\frac{2}{3}$ BY $\frac{2.26}{3}$

2). $\frac{\Sigma H}{\Sigma V} = \frac{37.8}{86.2} = .439$

3). $f_{\text{req}} = \frac{2 \times 86.2}{3 \times 6.08} = 9.50 \text{ ksf}$

4). $F_{SS} = \frac{86.2 \times .55}{37.8} = 1.25 *$


$$M_A = 470 + 17.8 \times 16.67 = 776 \text{ k} + 21 \times 12.5' = 1040$$

5). $F_{SUT} = \frac{1040 + 12.5}{776} = 1.67 = \frac{1453}{1040} = 1.40$

* A. ~~THE~~ SLIDING WILL BE IMPROVED, IF EXISTING PART OF MONOLITH 1A UNDER CONSTRUCTION WOULD BE COUNTED.

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS OF</u>	PROJECT <u>LED #1</u>
	<u>STABILITY OF TYPICAL RIVER WALL</u>	FILE NO <u>800A</u>
	COMPUTED <u>M.J.</u> <u>R.N.M.</u> CHECKED	DATE <u>11.74</u> PAGE <u>42</u> OF <u>42</u> PAGES

TYPICAL RIVER WALL MONOLITHS 6-16



FOR FOUNDATION / PRESSURES SEE 50 g
 FOR PILE LOADS SEE p: 50 a and p 50 b

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>OF STABILITY</u>	FILE NO <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>11.74</u> PAGE <u>43</u> OF <u> </u> PAGES

TYPICAL RIVER WALL MONOLITH

	LOADS IN KIPS	V ↓	V ↑	H ←	H →	ARM	MA ₂	MA ₅
C ₁	6.0 × 10 × .15	9.0				5.0	45.0	
C ₂	5.0 × 9.0 × .15	6.8				6.5	44.2	
C ₃	5.0 × 12.0 × .15	9.0				8.0	72.0	
C ₄	5.0 × 15.0 × .15	11.3				9.5	107.3	
C ₉	32.0 × 24.0 × .15	115.0				14.0	1615.0	
C ₁₀	2.0 × 4.0 × .15	1.2				1.0	1.2	
C ₁₁	17 × 4.8 ² × .15		✓ 10.8			14.0		✓ 151.5
C ₁₂	4.0 × 3.0 × .15		✓ 1.8			24.5		✓ 45.2
E ₅	10.0 × 18.0 × .115	20.8				17.0	354.0	
E ₆	5.0 × 15.0 × .115	8.6				18.5	159.0	
E ₇	5.0 × 12.0 × .115	6.9				20.0	138.0	
E ₈	5.0 × 9.0 × .115	5.2				21.5	111.5	
	Σ	193.8	12.6				2647.2	196.7 ^{1k}
		Σ V = 101.2 ^k ↓					Σ M = 2450.5 ^{1k} 2	

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY
COMPUTED M. J. CHECKED R. N. M.

PROJECT LED #1
FILE NO 800 A
DATE 11.78 PAGE 44 OF PAGES

TYPICAL RIVER WALL MONOLITH (GATED)

	LOAD IN KIPS	V ↓	V ↑	H ←	H →	ARM	M _{B 2}	M _{B 1}
C ₁₃	8.0 × 19.0 × .15	22.8				4.0	91.4	
C ₁₄	6.6 × 6.5 × .15	6.4				10.2	65.3	
C ₁₅	15.0 × 29.25 × .15	66.0				7.5	496.0	
C ₁₆	12.0 × 11.0 × .15	19.8				19.0	377.0	
C ₁₇	12.5 × 7.25 × .15	13.6				21.75	290.0	
	Σ	128.6 k					1319.7 k	
H _{w2}	3.10 × 49.5/2				77.0	16.5	M _{B 2} 1270.0	

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY

COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 45 OF 45 PAGES

TYPICAL RIVER WALL MONOLITH (CONT'D)

MONOLITH (I) (SMT #5)


$$\Sigma V = 181.2 \text{ k} \quad (\text{WITHOUT UPLIFT})$$

$$\Sigma M_A = 2450.5$$

LOCATION OF RESULTANT (VERT.)

$$\frac{2450.5}{181.2} = 13.50' \quad (\text{DISTANCE FROM "A"})$$

HYDR. UPLIFT




MONOLITH (II) (SMT #5)

$$\Sigma V = 128.6 \text{ k} \quad (\text{WITHOUT UPLIFT})$$

$$\Sigma M_B = 1319.7 \text{ k}$$

LOCATION OF RESULTANT $\frac{1319.7}{128.6} = 10.3' \quad (\text{DIST. FROM "B"})$

HYDROST. UPLIFT




HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY

COMPUTED M.J. CHECKED P.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 46 OF 46 PAGES

TYPICAL RIVER WALL MONOLITH (CONT'D)



$$W.S. EL. e''B'' = 675.7 + \frac{1}{.0625} \left[\frac{(3.10 - .18)}{52} 28 + .18 \right] = 703.7'$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY
COMPUTED M.T. CHECKED R.N.M.


PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 47 OF PAGES

TYPICAL RIVER WALL MONOLITH (CONT'D)

MONOLITH (I) FOUNDATION PROPERTIES

PILES @ 3.0' SPACING 7 ROWS @ 3' = 21.0'

FOR 30' WIDE MONOLITH X 24' DEEP



$$I_{yy} = 20 \times 10.5^2 + 20 \times 7.5^2 + 20 \times 4.5^2 + 20 \times 1.5^2 = 3793$$

$$S_{yy} = \frac{3793}{10.5} = 362 \quad \text{FOR 1'-0" WIDTH } S = 12.0$$

MONOLITH (II) FOUNDATION PROPERTIES

FOR 30' WIDE X 28.0' DEEP MONO.

$$I_{yy} = 20 \times 12.0^2 + 20 \times 9.0^2 + 20 \times 6.0^2 + 20 \times 3.0^2 = 5400$$

$$S_{yy} = \frac{5400}{12} = 450 \quad \text{FOR 1'-0" WIDTH } S = 15.0$$

MONO'S (I) & (II) COMBINED

$$I_{yy} = 20 \times 3.0^2 + 20 \times 6.0^2 + 20 \times 9.0^2 + 20 \times 12.0^2 + 20 \times 15.0^2 + 20 \times 18.0^2 \\ + 20 \times 21.0^2 + 20 \times 24.0^2 = 36670$$

$$S_{yy} = \frac{36670}{24} = 1550 \quad \text{FOR 1'-0" WIDTH } S = 51.7$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY

COMPUTED M.P. CHECKED E.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 48 OF 48 PAGES

TYPICAL RIVER WALL MONOLITH (CONT'D)

MONOLITH (I) FOUNDATION LOADING

$$181.2 \times 11.5 = 2084$$

$$- 16.2 \times 8.0 = - 130$$

$$- 42.0 \times 12.0 = - 504$$

$$\frac{127.6k}{123.0} \quad \frac{1450}{123.0}$$

$$x_1 = \frac{1450.0}{123.0} = 11.80' \text{ (13.7' FROM "A")}$$

$$M_{\frac{1}{2}} = 77.0 \times 16.5 - 123.0 \times 0.2 - 12.9 \times 4.0 = 1194.4 \text{ k}$$

$$e = \frac{1194.4}{123.0} = 9.70' \quad a = 2.30' \quad \frac{1}{2} - e = -5.7'$$

AREA LOADING,

$$\frac{EH}{2V} = \frac{64.1}{123} = .52$$

$$FSS = 1.05$$

$$A = 24.0 \text{ ft}^2$$

$$\text{SOIL PRESSURE } f = \frac{2}{3} \times \frac{127.6}{2.30} = \frac{35.6}{2.30} = 15.5 \text{ ksf}$$

PILE LOADING,

$$P = \frac{123.0}{80/30} \pm \frac{1194.4}{12} = 46.0 \pm 99.0$$

$$P_{\text{MAX}} = 145.0 \text{ k}$$

$$P_{\text{MIN}} = -53.0 \text{ k}$$

FOR COMBINED PILE LOADING, SEE SH? # 1

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>OF STABILITY</u>	FILE NO <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>P.V.M.</u>	DATE <u>11.74</u> PAGE <u>19</u> OF <u> </u> PAGES

TYPICAL RIVER WALL MONOLITH (CONT'D)
MONOLITH (II), FOUNDATION LOADING

$$\begin{aligned}
 128.6 \times 10.30 &= 1325.0 \text{ k} \\
 - 14.3 \times 9.33 &= -134.0 \\
 - \frac{5.1 \times 14.00}{109.2} &= - \frac{71.3}{1120.0 \text{ k}^2 (\text{MB})}
 \end{aligned}$$

$$X_2 = \frac{1120.0}{109.2} = 10.25' \quad 14.0 - 10.25 = 3.75'$$

$$M_2 = 109.2 \times 3.75 + .175 \times \frac{2.8^2}{2} + .144 \times \frac{5.55^2}{2} = 415.0 \text{ k}$$

$$e = \frac{415.0}{109.2} = 3.80' \quad S = \frac{10 \times 28.0^2}{6} = 130.0' \quad \frac{L}{6} - e = -.86'$$

AREA LOADING

$$f = \frac{109.2}{28} \pm \frac{415.0}{130.0} = 3.92 \pm 3.20$$

$$f_{\text{MAX}} = 7.12 \text{ ksf} \quad f_{\text{MIN}} = 0.72 \text{ ksf}$$

PILE LOADING

$$P = \frac{109.20}{80/30} \pm \frac{415}{15.0} = 41.2 \pm 27.7$$

$$P_{\text{MAX}} = 68.9 \text{ k}$$

$$P_{\text{MIN}} = 13.5 \text{ k}$$

FOR COMBINED PILE LOADING, SEE SHT # 19

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY
COMPUTED M.T. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 50 OF 50 PAGES

TYPICAL RIVER WALL MONOLITH (CONT'D)

COMBINED PILE LOADING FOR MONO'S (I) & (II)

$$M_{EI} = 415.0 \text{ k}$$

$$77.0 \times 16.5 = 1270$$

$$\frac{-12.9 \times 4.0}{64.1 \text{ k}} = -51.6$$

$$1218.4$$

$$y = \frac{1218.4}{64.1} = 19.1'$$

MOMENT C EL 684.45

$$64.1 \times (19.0 - 8.75) - 415.0 = 243.3 \text{ k}$$

$$EH = 64.1$$

PILE LOADING

$$P = \frac{127.6}{8/3} - \frac{243.0}{51.7} = 48.0 - 4.7$$

$$P_{MAX} = 43.30 \text{ k/PILE}$$

$$P = \frac{107.1}{9/3} + 4.7$$

$$P_{MIN} = 35.7 + 4.7 = 40.4 \text{ k/PILE}$$

FOR PILE LOADS WHERE STEEL SHEET PILING
IS NOT CONSIDERED, SEE P. 50a


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT TYPICAL RIVERWALL-
EXISTING - NORMAL CONDITION
COMPUTED R. N. M. CHECKED ✓

PROJECT LOCK & DAM
FILE NO. 800 A
DATE 3/75 PAGE 50^a OF 50 PAGES

TYPICAL RIVERWALL MONOLITH
EXISTING CONDITION
NORMAL LOADING

ANALYSIS @ ELEVATION
675.7'



- 1) MAX BEARING ON PILES = 50^K (PILE #16)
- 2) HORIZONTAL PILE LOAD = 13^K


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT TYPICAL RIVERWALL -
EXISTING - NORMAL LOADING
COMPUTED E.H.M. CHECKED JL

PROJECT L & DAM #1
FILE NO 800 A
DATE 3/75 PAGE 50 b OF PAGES

TYPICAL RIVERWALL
EXISTING CONDITION
NORMAL LOADING

PILE FOUNDATION PROPERTIES**



$$I = 2(24)^2 + 2(21)^2 + 2(18)^2 + 15^2 + 2(12)^2 + 2(9)^2 + 2(6)^2 + 3^2 + 2^2$$

Y-Y


$$I_{Y-Y} = 3442'4$$

$$S = \frac{3442}{24} = 143'3 \text{ PER 3 FEET LONGITUDINAL}$$

Number of piles = 16

HORIZONTAL LOAD PER PILE

$$P_H = \frac{230 - 20}{16} = 13^K \text{ (APPROX)}$$



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT TYPICAL RIVERWALL, -
EXISTING, - NORMAL LOADING
COMPUTED E.N.M. CHECKED VI

PROJECT L & D #1
FILE NO 800 A
DATE 3/75 PAGE 50C OF PAGES

TYP. RIVERWALL MONOLITH, EXISTING CONDITION, NORMAL LOADING
GRAVITY LOAD, $V \frac{1}{2} M_{Y-Y}$

REFERENCE Pg 42

TAKEN AT ELEVATION 684.45'

	GRAVITY LOAD	H	$V \downarrow$ \oplus	ARM A	ARM Y-Y	M_A	M_{Y-Y}
①	6 x 10 x .15		9.0	5.0		45.0	
②	5 x 9 x .15		6.8	6.5		44.2	
③	5 x 12 x .15		9.0	8.0		72.0	
④	5 x 15 x .15		11.3	9.5		107.3	
⑤	10 x 18 x .115		20.8	17.0		354.0	
⑥	5 x 15 x .115		8.4	18.5		159.0	
⑦	5 x 12 x .115		6.9	20.0		138.0	
⑧	5 x 9 x .115		5.2	21.5		111.5	
⑨	32 x 24 x .15		115.2	14.0		1613	
⑩	24 x 8.75 x (-.063)		-11.3	13.0		-169	
⑪	$\pi(4.8)^2 \times (-15)$		-10.8	14.0		-151	
⑫	4 x 3 x (-15)		-1.8	24.5		-44	
⑬			22.8	30.0		684	
⑭			6.4	36.2		398	
⑮			66.0	33.5		2211	
⑯			19.8	45.0		891	
⑰			13.6	47.3		643	
		TOTAL =	295.8	(23.47)		6941	1340
	ARM Y-Y = ARM A - 28'		24.0	-4.53'		-1186'	
			x 3 ft. strip of wall			x 3	
			887.4			-4020.4	
	CONC. BELOW EL 684.5:		91.3	x 14'			
	$\Delta V = 24 \times 8.45 \times 3 \times .15$		978.3	ΔM_{Y-Y}		-1278	
			ΣV GRAVITY = 978.4			ΣM_{Y-Y} GRAVITY = 5298.4	

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT TYPICAL RIVER WALL
EXISTING - NORMAL LOADING
COMPUTED R.N.M. CHECKED JJ

PROJECT L&D #1
FILE NO. 800 A
DATE 3/75 PAGE 50d OF PAGES

TYPICAL RIVER WALL MONOLITHS
EXISTING, NORMAL LOADING CONDITION

MAX. LOAD ON PILES @ EL. 675.7

LATERAL PRESSURES:

$$M_{\text{GRAVITY}} = 5298'$$

$$\frac{(725.2 - 675.7)^2}{2} \times 0.0625 \times 3 = +230' \text{K} \quad \times 16.5 = 3795' \text{K} \downarrow$$

$$\frac{(687.2 - 675.7)^2}{2} \times 0.0625 \times 3 = -12' \text{K} \quad \times 3.8 = -46' \text{K}$$

$$\frac{(690 - 675.7)^2}{2} \times 0.026 \times 3 = -8' \text{K} \quad \times 4.8 = -38' \text{K}$$

$$\Sigma H = 210' \text{K} \quad M_{\Sigma H} = 3711' \text{K} \downarrow$$

UPLIFT:

$$\frac{3.10 \times 52}{2} \times 3 = +242' \text{K} \quad \times 8.7 = +2105' \text{K} \downarrow$$

$$\frac{0.72 \times 52}{2} \times 3 = +56' \text{K} \quad \times 8.7 = -487' \text{K}$$

$$0.53 \times 28 \times 3 = -45' \text{K} \quad \times 12 = +540' \text{K} \downarrow$$

$$U = 253' \text{K} \downarrow \quad M_U = 2158' \text{K} \downarrow$$

PILE LOAD:

$$\Sigma V = 978 - 253 = 725' \text{K} \quad \Sigma M_{\phi} = +571' \text{K} \downarrow$$

$$\frac{725}{16} - \frac{571}{143} = 41.3 \text{ SAY } 42' \text{K} \quad - \text{P VERT ON PILE \# 1}$$

$$\frac{725}{16} + \frac{571}{143} = 49.3 \text{ SAY } 50' \text{K} \quad - \text{P VERT. ON PILE \# 16}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	TYPICAL RIVERWALL	PROJECT	L & V #1
	EXTENSION	NATURAL SLOPING	FILE NO.	800A
	COMPUTED	JL	CHECKED	R.N.M.
	DATE		4/75	PAGE 50f OF PAGES

FOUNDATION PRESSURES - VERTICAL LOAD TRANSFER
BETWEEN I & II

Combine (I) & (II) Loads (Ref. p 42-50)
per linear foot

(I) ΣV	181.2	2451	
(II) ΣV	128.6	4603	$(\frac{1219}{128.6} + 26.0) 128.6$
(I) Uplift	-16.2	-162	$(\frac{24.0}{2} + 2.0) 16.2$
(I)	-42.0	-588	$(\frac{28.0}{2} + 2.0) 42$
(II)	-5.0	-200	$(\frac{28.0}{2} + 26.0) 5$
(II)	-14.3	-565	$(\frac{28.0}{2} + 26.0) 14.3$
$\Sigma V_{reqd} =$	232.3	5659	$\frac{5659}{232.3} = 24.36$

H	77.0	1271	
E	.4	4	
I'	1.0	2	
I''	12.0	52	
$\Sigma H =$	63.5	1212	

$$\bar{X} = \frac{5659 + 1212}{232.3} = 29.58'$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT TYPICAL RIVER WALL
EXISTING - NORMAL LOADING
COMPUTED JI CHECKED _____

PROJECT L 410 H 1
FILE NO. 800A
DATE 1/75 PAGE 504 OF _____ PAGES

$$e = \frac{54.4}{2} - 29.58' = -2.58' \quad \left(\frac{L}{6} - e\right) = 642'$$

$$p = \frac{232.3}{54.0} \left(1 \pm \frac{6 \times 2.58}{54.0}\right) = \begin{cases} \underline{5.54} \text{ ksf max} \\ \underline{3.07} \text{ ksf min} \end{cases}$$


$$\Sigma H = 63.5$$

$$\Sigma V = 232.3$$

$$\frac{\Sigma H}{\Sigma V} = .273$$

$$F.S.S. = 2.01$$

PROJECT LED #1
FILE NO B00A
DATE 11-74 PAGE 51 OF PAGE



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>TYPICAL RIVERWALL -</u>	PROJECT <u>L & D #1</u>
	<u>LOCK EMPTY</u>	FILE NO. <u>800A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>J</u>	DATE <u>3/17/75</u> PAGE <u>50</u> OF <u>50</u> PAGES

RIVERWALL TYP. MONOLITH
CONSTRUCTION/MAINTENANCE


Analysis taken at el. 675.7'

G.S. & W.S. El. 690'

Ref. page 50 c

Maximum bearing
load on extreme
"lockside" pile.

Assume complete
transfer of vert.
load between
original and
new riverwall.



$$\begin{aligned}
 \Delta V &= 24 \times 8.45 \times 3 \times 15 = 91.3^k & \times (-14) &= -1278^k \\
 \Sigma V_1 &= 887.0^k & \times (-4.53) &= -4020^k \\
 U_1 &= -14.8^k & \times (-10) &= +148^k \\
 U_2 &= -11.3^k & \times (+19) &= -215^k \\
 \Sigma V &= \underline{952.2^k} \downarrow \\
 \Sigma H &= \underline{27.2^k} \leftarrow & \times \frac{14.3}{3} &= -130^k \\
 \Sigma M_E &= -5495^k \uparrow
 \end{aligned}$$

Force per pile, $P = \frac{\Sigma V}{n} \pm \frac{\Sigma M_E}{S}$

$$= \frac{952.2}{16} + \frac{5495}{143} = \underline{98^k} \text{ Pile \#1}$$

$$P = 59.5 - \frac{5495}{143} = \underline{21^k} \text{ Pile \#16}$$


$$P_H = \frac{27.2}{16} = \underline{2^k}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITION OF
STABILITY @ RIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LOCK & DAM #1
FILE NO. 800A
DATE 8.1974 PAGE 52 OF 52 PAGES

RIVER WALL MONOLITH #19



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITION OF</u>	PROJECT <u>LED #1</u>
	<u>STABILITY OF RIVER WALL</u>	FILE NO <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>P.N.M.</u>	DATE <u>8.74</u> PAGE <u>53</u> OF <u> </u> PAGES

RIVER WALL MONOLITH #19 (CONT'D)

	LOADS IN KI/RS	VERT. ↓	VERT. ↑	HORIZ. →	HORIZ. ←	ARM	MOMENT	MOMENT
C1	57.0 x 20.0 x 28 x .15	4790				18.0		86200
C2	53.0 x 4.0 x 28 x .15	890				5.33		4740
C3	8.0 x 4.0 x 28 x .15	134				4.0		538
C4	5.0 x 4.0 x 28.0 x .087	49				25.5		1250
C5	6.5 x 4.0 x 19.5 x .087	43				30.0		1290
C6	47. x 4 x 19.5 x .0625	230				30.0		6900
C6	61 x 4.0 x 8.5 x .15	312				30.0		9360
		Σ 6448						Σ 110.280
C7	80.0 x 28 x .088		200			200	4.000	
HW1	3.10 x 24.8 x 28			2150		16.53	35600	
HW2	.730 x 5.8 x 28				1180	3.88		460
HE1	.328 x 3.9 x 28				69.0	17.0		1170
HE2	.328 x 11.6 x 28				147.0	5.8		855
HE3	.151 x 11.6 x 28				49.0	3.88		190
		Σ 6448	200.0	2150	383		39,600	112,860
W1	AVERAGE PRESS. CLUX SIDE		11890 ^k	(SEE NEXT SHT)				Σ M = 73260 ^k
W2	MAX PRESS. (LOW SIDE)		17170 ^k	(" " ")				

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITION OF STABILITY OF RIVER WALL</u> COMPUTED <u>M.T.</u> CHECKED <u>R.N.M.</u>	PROJECT <u>LED #1</u> FILE NO. <u>800A</u> DATE <u>8.1974</u> PAGE <u>54</u> OF <u> </u> PAGES
--	--	---


RIVER WALL MONOLITH #19 (CONT'D)

HYDROSTATIC PRESSURE C BOTTOM

1). LOCKSIDE AVERAGE

$$\frac{3.10 + .73}{2} = 1.92 \text{ ksf}$$


$$\left. \begin{array}{l} 32 \times 28 \times .73 = 655 \text{ k} \\ 32 \times 14 \times 1.19 = 534 \text{ k} \end{array} \right\} 1189 \text{ k}$$



$$M_A = 655 \times 16 + 534 \times 21.33 = 10450 + 11390 = 21840 \text{ 'k}$$

$$\Sigma M_A = 66360 - 21840 = 44520 \text{ 'k}$$

2). LOCKSIDE MAXIMUM



$$655 + 1.185 \times 32 \times 28 = 1717 \text{ k}$$

$$M_A = 10450 + 1.185 \times 32 \times 28 \times 21.33 = 10450 + 22700$$

$$M_A = 33.150 \text{ 'k}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
DESTABILITY AT RIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 10.74 PAGE 55 OF PAGES

RIVER WALL MONOLITH #19 (CONTD)

PILE LOADING FOR AVERAGE HYDROSTATIC LOAD ↑

(LOCKSIDE AVERAGE LOAD ↑)

(AVERAGE UPLIFT)

$$V = 6248 - 1189 = 5059 \text{ k}$$

$$M_A = 73260 - 21040 = 51420 \text{ k}$$

$$e = \frac{51420}{5059} = 10.16 \text{ ' } \quad e = \frac{32.0}{2} - 10.16 = 5.84 \text{ '}$$

$$M_e = 5059 \times 5.84 = 29500 \text{ k}$$

SHEET PILE LOADING

$$P_{SP} = \frac{5059}{3 \times 99} \pm \frac{29500}{3 \times 600} = 17.03 \pm 16.4 \text{ /FT } \left\{ \begin{array}{l} 33.4 \\ 0.6 \end{array} \right.$$

FOR 15" SHT PILES, $P_{MAX} = 41.8 \text{ k}$ $P_{MIN} = 0.8 \text{ k}$

MAX LOAD ON TIMBER PILES

$$I_{xx} = 8690$$

$$S = \frac{8690}{12.0} = 725$$

$$P = \frac{5059}{99} \pm \frac{29500}{725} = 51.10 \pm 40.7$$

$$P_{MAX} = 91.8 \text{ k} \quad P_{MIN} = 10.4 \text{ k}$$

$$H = 2150 - 383 = 1767 \text{ k OR } 17.8 \text{ EA. PILE}$$

FOR PILE LOADS
(WITHOUT STEEL
SHT PILING) SEE
PAGE 56 a

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY AT RIVER WALL
COMPUTED M. J. CHECKED R. N. M.

PROJECT LED #1
FILE NO 800A
DATE 10.74 PAGE 56 OF PAGES

RIVER WALL MONOLITH #19 (LOCKSIDE AVERAGE), (CONT'D)

CHECK AREA LOADING, ASSUMING AREA BETWEEN SHEET PILES

$$A = 29.0 \times 28.0 = 812 \text{ FT}^2$$

$$Q = 10.16' \quad Q = 5.84'$$

$$5.84 - 5.33 = 0.51'$$


1). RESULTANT OUTSIDE MIDDLE $\frac{1}{3}$ BY 7.00'

$$2). f_{\text{SWL}} = \frac{2}{3} \frac{5059}{28 \times 8.66} = \frac{11.86}{10.16} = 73.90 \text{ KSF}$$

$$3). \frac{\Sigma H}{\Sigma V} = \frac{1767}{5059} = 0.350$$

$$4). FSS = \frac{5059 \times 0.55}{1767} = 1.57$$

$$5). FSOT = \frac{112860}{61440} = 1.84$$



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RIVER WALL STABILITY-
PILE LOAD
COMPUTED P.N.M. CHECKED J1

PROJECT L&D #1
FILE NO 800 A
DATE 3/75 PAGE 56a OF PAGES

RIVER WALL MONOLITH NO. 19


EXISTING, NORMAL LOADING CONDITION

PILE LOADING, ASSUMING THAT THE TIMBER PILES
SUPPORT ALL THE LOAD

(BEARING CAPACITY OF STEEL
SHEET PILING NOT CONSIDERED)

ASSUME ϕ PILES
COINCIDES WITH
 ϕ BASE

TIMBER PILES @ 3' O.C.
SPCG. EACH WAY



"LOCK SIDE AVERAGE"

$$2(12) = 288$$

$$2(9) = 162$$

$$2(6) = 72$$

$$2(3) = 18$$

$$= 540 \text{ ft}^4$$

$$= 45 \text{ ft}^3$$

$$\Sigma V = 5059 \times \frac{3}{28} = 540 \text{ k} \quad \text{Ref. Page 55} \quad \checkmark$$

$$\Sigma M_{\phi} = 29,500 \times \frac{3}{28} = 3160 \text{ k} \quad \text{PER 3' STRIP OF WALL}$$

$$\Sigma H = 1767 \times \frac{3}{28} = 189 \text{ k} \rightarrow$$

MAXIMUM LOAD ON TIMBER PILES:

$$P = \frac{542}{9} + \frac{3160}{45} = 60 + 70 = 130 \text{ k (MAX) / PILE}$$

$$\text{MINIMUM LOAD ON TIMBER PILES} = 60 - 70 = -10 \text{ k (MIN) / PILE}$$

$$\text{HORIZONTAL LOAD PER PILE} = \frac{189}{9} = 21 \text{ k / PILE}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY CRIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 10.74 PAGE 57 OF PAGES

RIVERWALL MONOLITH #19 (CONT'D)

MAXIMUM LOADING ON PILES (LOCKSIDE MAXIMUM)

$$\Sigma V = 6248 - 1717 = 4531 \text{ k}$$

$$M_A = 73260 - 33,150 = 40,110 \text{ k}$$

$$e = \frac{40110}{4531} = 8.85' \quad e = \frac{32.0}{2} - 8.85 = 7.14'$$

$$M_d = 7.14 \times 4531 = 32350 \text{ k}$$

$I_{xx} = 18 \times 14.5^2$	712	3820
18×12.0^2	144	2600
18×9.0^2	81	1460
18×6.0^2	24	648
18×3.0^2	9	162
		<u>8690</u>

$$I_{xx} = 8690 \text{ FT}^4$$

$$S_{xx} = \frac{8690}{14.50} = 6000 \text{ FT}^3$$

PAGE 57 G FOR
PILE LOADS (W/O
STEEL SH. PILING)

MAX LOADS ON SHEET PILING

$$P = \frac{4531}{99} \pm \frac{32350}{600} = 45.60 \pm 54.00 \left[\begin{array}{l} 99.60 \text{ k} \\ -8.40 \text{ k TENS.} \end{array} \right]$$

FOR 15" SH. PILES $P_{max} = 41.6 \text{ k/PILE}$ $P_{min} = 3.5 \text{ k/PILE (TENS.)}$

MAX LOAD ON TIMBER PILES

ASSD MP 101 A = 10.31M' $f_{max} = 25,000 \text{ psi}$
MIN. P = 25.4 k

$$I_{xx} = 8690 \text{ FT}^4 \quad S_{xx} = \frac{8690}{12} = 725 \text{ FT}^3$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RIVER WALL STABILITY-</u>	PROJECT <u>L & D #1</u>
	<u>PILE LOAD</u>	FILE NO. <u>800A</u>
	COMPUTED <u>RNM</u> CHECKED <u>JJ</u>	DATE <u>3/75</u> PAGE <u>57</u> OF <u>57</u> PAGES

RIVER WALL MONOLITH NO. 19

EXISTING, NORMAL LOADING CONDITION

PILE LOADING

ASSUMPTION THAT PILES SUPPORT ALL LOAD

"LOCK SIDE MAXIMUM." - Reference pgs 56 & 55⁷

$$\Sigma V = 4531 \times \frac{3}{28} = 486 \text{ k} \quad \text{SECT. MOD., } S = 45 \text{ ft}^3$$

$$\Sigma M_e = 32,350 \times \frac{3}{28} = 3466 \text{ k}$$

$$P_{\text{MAX}} = \frac{486}{9} + \frac{3466}{45} = 54 + 77 = \underline{131} \text{ k}$$

$$P_{\text{MIN}} = \text{---} = 54 - 77 = \underline{-23} \text{ k}$$

$$P_H = 21 \text{ k}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS OF</u>	PROJECT <u>LED #1</u>
	<u>STABILITY AT RIVERWALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.S.</u>	CHECKED <u>R.N.M.</u>
	DATE <u>10.74</u> PAGE <u>58</u> OF <u> </u> PAGES	

RIVERWALL MONOLITH #19 (CONT'D)MAX LOAD ON TIMBER PILES (LOCKSIDE MAXIMUM) (CONT'D)

(SEE P. 57a)

$$P = 45.6 \pm \frac{32350}{725} = 45.6 \pm 44.6$$

$$H = 1767^k$$

$$P_{MAX} = 90.2^k \downarrow \quad P_{MIN} = +1.0^k \downarrow$$

$$H/P_{PILE} = 17.8^k$$

CHECK FOUNDATION LOADING, ASSUMING FULL AREA (BETWEEN

SHEET PILING) SUPPORTING ALL LOADS (AREA LOADING)

$$A = 29.0 \times 28 = 810 \text{ FT}^2$$

$$e = 7.14' \quad a = 7.14' - 7.14' = 7.26' \quad \frac{8.86}{16}$$

$$1). \text{ RESULTANT OUTSIDE MIDDLE } \frac{1}{6} \text{ BY } 7.14' - \frac{32}{6} = 1.80' \quad \frac{1.80}{6} = 290$$

$$2). f_{SOIL} = \frac{2 \times 4531}{3 \times 28 \times 7.26} = 12.17 \quad \frac{8.86}{12.17} = 14.6 \text{ ksf}$$

$$3). FSS = \frac{4531 \times 1.55}{1767} = 1.41$$

$$4). \frac{\Sigma H}{\Sigma V} = \frac{1767}{4531} = .39 \quad (\text{FOR } f = .55 \quad \text{IF } FSS = 1.5 \quad \frac{\Sigma H}{\Sigma V} = .367)$$

$$5). F_{TOT} = \frac{112.860}{39600 + 33150} = 1.55 \quad \frac{72750}{39600 + 33150}$$

PROJECT LED #1
FILE NO. 800A
DATE 10.74 PAGE 53 OF PAGES

The diagram illustrates a dam cross-section with the following details:

- Top Dimensions:** A crest width of 24' and a total width of 32.0'. The right elevation is EL 732.6.
- Left Side (Upstream):**
 - Gate 230:** A vertical gate structure with a height of 49.6' and a width of 12.5'. It is subjected to a water pressure of 62.5 PSF.
 - Foundation:** A rectangular foundation with a width of 7.8' and a height of 2.37'. It is subjected to a pressure of 3.10 KSF.
 - Foundation Pressure:** A triangular pressure distribution with a peak of 2.37 KSF and a base of 7.8'.
 - Foundation Settlement:** A settlement of 1.2' is indicated.
 - Foundation Load:** A load of 2180 K is shown.
 - Foundation Dimensions:** A width of 4.56' and a height of 1.0' are indicated.
- Internal Structure:**
 - Zone 1:** The upper central region of the dam.
 - Zone 2:** A central vertical zone.
 - Zone 3:** A lower central zone.
 - Zone 4:** A small rectangular zone with a width of 8' and a height of 10'.
 - Zone 5:** A vertical zone on the left side.
- Right Side (Downstream):**
 - Foundation:** A rectangular foundation with a width of 23' and a height of 9'. It is subjected to a pressure of 6.75 KSF.
 - Foundation Pressure:** A triangular pressure distribution with a peak of 6.75 KSF and a base of 23'.
 - Foundation Settlement:** A settlement of 1.16' is indicated.
 - Foundation Load:** A load of 26 PSF is shown.
 - Foundation Dimensions:** A width of 11.6' and a height of 2.8' are indicated.
 - Foundation Pressure:** A triangular pressure distribution with a peak of 42 PSF and a base of 11.6'.
 - Foundation Load:** A load of 117 KSF is shown.
- Bottom Dimensions:** A total width of 32' and a height of 28.0'.
- Coordinate System:** A coordinate system with X and Y axes is shown at the bottom right.
- Moments:** Moments are indicated as $M_{xx}(+)$ and $M_{yy}(+)$.

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS OF</u>	PROJECT <u>L. F. D. #1</u>
	<u>STABILITY OF RIVER WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.T.</u> CHECKED <u>R.N.M.</u>	DATE <u>9.74</u> PAGE <u>60</u> OF <u> </u> PAGES

RIVERWALL GATE MONOLITH #20 (CONTD)

AT SECTION

	LOADS IN KIPS	VERT. ↓	VERT. ↑	HORIZ.	HORIZ	ARM	MOM ² y	MOM ² y
C1		5746				4.0		22.984
C2		958				19.7	10.220	
C3	4 × 9 × 28 × 0.87	88				11.5		1.000
C4			196			4.0	784	
C5			260			14.0	3650	
GATE		230				28.5		6.560
		Σ 7022	456			Σ 146.54		30.544

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>EXISTING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>OF STABILITY & RIVER WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u>	CHECKED <u>R.N.M.</u>
	DATE <u>10.74</u>	PAGE <u>61</u> OF <u> </u> PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

	LOAD IN KIPS	V ↓	V ↑	ARM	MOMENT MKK-FT		
	$C_1 + C_2 + C_3$	6792		0			
C_4			196	0			
C_5			260	7.0		1820	
	GATE	230		5.56	1280		
		$\Sigma 7022$	456				
W_1	$.73 \times 32.0 \times 14.0$		327	7.0		2290	
W_2	$1.19 \times 32 \times 14.0 \times \frac{1}{2}$		267	7.0		1870	
						$\Sigma 5980$	2^{1k}
W_3			327	7.0	2290		
	* LOCKSIDE AVERAGE			Σ	3570	1^{1k}	
W_2'	$2.37 \times 32 \times 14.0 \times \frac{1}{2}$		532	7.0		3730	
	Σ	$\Sigma 7022$	$\Sigma 1642$		$\Sigma 3570$	$\Sigma 7840$	2^{1k}
	Σ	$\Sigma 7022$	$\Sigma 1642$		$\Sigma 3570$	$\Sigma 7840$	2^{1k}


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY CRIVERWALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LFO #1
FILE NO. 800 A
DATE 10.7.4 PAGE 62 OF PAGES

RIVERWALL GATE MONOLITH #20 (CONT'D)

HYDROSTATIC LOAD ON GATES



$$2.37 \times 38.0 / 2 = 45.10 \text{ k}$$



$$2.37 \times 9.1 = \frac{21.60}{66.70 \text{ k}}$$

$$45.1 \times 21.77 = 980.0$$

$$y = \frac{1078.3}{66.7} = 16.2' / \text{EL } 694.3' \quad \frac{21.6 \times 4.55}{66.7 \text{ k}} = \frac{98.3}{1078.3} \text{ k}$$

TOTAL GATE THRUST

$$66.7 \times 32.75 = 2180 \text{ k}$$



$$T = \frac{PL}{2 \sin \alpha}$$

$$S = T \cos 2 \alpha$$

$$X = T \sin 2 \alpha$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	EXISTING CONDITIONS	PROJECT	LED #1
		OF STABILITY CRIVER WALL	FILE NO.	B00A
	COMPUTED	M.J.	CHECKED	R.N.M.
			DATE	10.74 PAGE 63 OF 63 PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

$$\Sigma M_{xx} = 5980 - 3570 + 2050 \times (16.2 + 2.5) = 49820 \text{ k}^2$$

$$\Sigma M_{yy} = 30544 - 14654 - 2470 - 18.7 -$$

$$- 32 \times 28.0 \times 1.19 \times (16.0 - 10.67)$$

$$- 3.10 \times 24.8 \times 14 \times 16.55 + 460 + 190$$

$$+ .117 \times 11.6 \times 28 \times 5.8 + .117 \times 11.6 \times 28 \times 5.8$$

$$\Sigma M_{yy} = 30544 - 14654 - 46200 - 1420 - 17800 + 650$$

$$+ 221 + 110 = 31525 - 47774 = -16250 \text{ k}^2$$

$$\Sigma M_{xx} = 40.820 \text{ k}^2 \quad e_y = 7.25'$$

$$\Sigma M_{yy} = 48550 \text{ k}^2 \quad e_x = 8.62'$$

$$\Sigma V = 7022 - 456 - 2 \times 327 - 267 = 5645 \text{ k}$$

$$\Sigma H_x = 3260 \text{ k}$$

$$\Sigma H_y = 2050 \text{ k}$$

$$\Sigma H_R = 3850 \text{ k}$$

(CONT'D ON PAGE 65)

LOCKSIDE A BRAGE' UPLIFT


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY CRIVER WALL
COMPUTED M.V.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800A
DATE 10.74 PAGE 02 OF 02 PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

PILE LOADING FOR LOCKSIDE AVERAGE UPLIFT PRESSURE



$$I_{yy} = 8690$$

$$S_{yy} = 6090$$

$$\begin{aligned} I_{xx} &= 22 \times 3.0^2 = 198 \\ &22 \times 6.0^2 = 792 \\ &22 \times 9.0^2 = 1783 \\ &22 \times 12.0^2 = 3170 \\ &\hline &5943 \end{aligned}$$

$$S_{xx} = \frac{5943}{12} = 495$$

$$P = \frac{5645}{99} \pm \frac{40820}{495} \pm \frac{48.550}{600} = 57.0 \pm 82.5 \pm 81.0$$

$$\text{MAX } P = 57.0 + 82.5 + 81.0 = \underline{220.5 \text{ k}}$$

$$\text{MIN } P = -106.5 \text{ k (UPLIFT)}$$

$$\text{TOTAL } H_x = 3260 \text{ k OR } \frac{3260}{99} = 33.0 \text{ k/PILE}$$

ANOTHER COMPUTATION
FOR PILE LOADS IS
ON PAGE 64 b, WHERE
SHEET PILING IS
NOT INCLUDED

HARZA ENGINEERING COMPANY CHICAGO	EXISTING	PROJECT
	SUBJECT <u>IMPROVED CONDITIONS</u>	<u>LED #1</u>
	<u>OF STABILITY @ RIVER WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>1.75</u> PAGE <u>64C</u> OF <u> </u> PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

EXISTING CONDITIONS - AREA LOADING (EXESIDE MAXIMUM)

$$\Sigma V = \underline{5380k}$$

$$\Sigma M_{xx} = 40820 + 1870 = \underline{42690k}$$

$$\Sigma M_{yy} = 40550 + 1420 = \underline{41970k}$$

$$\Sigma H_x = \underline{3260k}$$

$$\Sigma H_y = 3851k$$

$$\Sigma H_y = \underline{2050k}$$

$$A = 912 \text{ FT}^2 \quad (29 \times 28)$$

$$e_y = \frac{42690}{5380} = \underline{7.95} \quad e_x = \frac{41970}{5380} = \underline{7.80}$$

$$e_y/b = 7.95/28.0 = .284; \quad e_x/l = 7.80/29.0 = .113$$

$$L = 9.7$$

PILE LOADS
ON PAGE 64C

$$1) \quad f_{soil} = 9.7 \cdot \frac{5380}{912} = 64.2 \text{ K/F}$$

$$2) \quad L \text{ OUTSIDE KERN}$$

$$3) \quad \frac{\Sigma H}{\Sigma V} = \frac{3260}{5380} = 0.61$$


$$4) \quad \bar{m} = \bar{s}_x = \frac{5380 \cdot 3.5}{2475} = 0.90 \quad f_{ssr} = \frac{5380 \cdot 55}{3851} = .77$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RIVERWALL STABILITY-
PILE LOAD
COMPUTED R.N.M. CHECKED JL

PROJECT L & D #1
FILE NO 800A
DATE 3/75 PAGE 46 OF 46 PAGES

RIVER WALL GATE MONOLITH NO 20
EXISTING, NORMAL LOADING CONDITION



ASSUME PILE FOUNDATION SUPPORTING ALL LOAD

"LOCK SIDE AVERAGE" $P_{22} = 64$

$$\sum V = 5645^k \quad \sum M_x = 40,820^k \cdot$$

$$\sum M_y = 48,550^k \cdot$$

$$\sum H_x = 3260^k$$

$$P_{MAX} = \frac{5645}{81} + \frac{48550 \times 12}{4860} = 69.7 + 119.9 + 100.8 = 290.4^k$$

$$P_{MIN} = 69.7 - 119.9 - 100.8 = -151^k$$

$$P_H = \frac{3260}{81} = 40^k$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RIVER WALL STABILITY
PILE LOAD
COMPUTED JT CHECKED R.W.M.

PROJECT L & D #1
FILE NO 800 A
DATE 2/75 PAGE 64C OF PAGES

RIVER WALL GATE MONOLITH #20
EXISTING, NORMAL LOADING CONDITIONS

"LOOKSIDE" MAXIMUM (REF. p. 64a)

$$\Sigma V = 5380^k$$

$$\Sigma M_{xx} = 42690^k\gamma \quad \Sigma M_{yy} = 49970^k\gamma$$

$$\Sigma H_x = 3260^k \quad \Sigma H_y = 2050^k \quad \Sigma H_R = 3851^k$$

$$P_V = \frac{5380}{81} \pm \frac{42690 \times 12.0}{4860} \pm \frac{49970 \times 12.0}{4860} =$$

$$= 66 \pm 105 \pm 123 = \begin{cases} 294^k \text{ max} \\ -162^k \text{ min} \end{cases}$$

$$P_{Hx} = \frac{3260}{81} = 40^k/\text{ft.}$$

$$P_{HR} = \frac{3851}{81} = 48^k/\text{ft.}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITIONS
OF STABILITY @ RIVER WALL
COMPUTED M.T. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800 A
DATE 10.74 PAGE 65 OF PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

CHECK SOIL PRESSURE, ASSUMING AREA LOADING
(LOOKSIDE AVERAGE)

$$A = 29 \times 28 = 812 \text{ FT}^2$$

$$e_y = \frac{40820}{5645} = 7.25'$$

$$e_x = \frac{48550}{5645} = 8.62'$$

$$\frac{e_y}{b} = \frac{7.25}{29.0} = 0.26$$

$$\frac{e_x}{b} = \frac{8.62}{29.0} = 0.30$$

$$K = 7.70$$

SUMMARY OF RESULTS

1). $f_{\text{MAX}} = 7.70 \times \frac{5645}{812} = 53.5 \text{ KSF}$

2). RESULTANT OUTSIDE KERN

3). $\frac{\Sigma H_i}{\Sigma V} = \frac{3260}{5645} = .58$

4). $FSS_{\text{L}} = \frac{5645 \times .55}{3260} = 0.95$ $FSS_{\text{R}} = \frac{5645 \times .55}{3850} = .81$

(FROM PAGE 63)

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>SLIDING STABILITY</u>	PROJECT <u>LEDA</u>
	COMPUTED <u>M.J.</u>	FILE NO. <u>800A</u>
	CHECKED <u>P.N.M.</u>	DATE <u>1.75</u> PAGE <u>66</u> OF <u> </u> PAGES

SLIDING STABILITY

TOP OF IMPERVIOUS LAYER (UNIT B) EL 660.00

H. WL EL 725.2' $.0625 \times 65.2 = 4.08 \text{ ksf}$

$$H_{w1} = .0625 \times 65.2^2 / 2 = 133.0 \text{ k}$$

$$H_{w2} = .0625 \times 70.2^2 / 2 = 154.0 \text{ k (TOP OF IMPERVIOUS LAYER)}$$

CEL 655.0

TOTAL VERTICAL LOAD

$$\Sigma V = 6443 - 200 - 1133 = 5059 \text{ k}$$

$$5059 / 28 = 180 \text{ k / FT OF WIDTH}$$

WEIGHT OF SOIL

$$\left. \begin{array}{l} 4 \times 24 \times .063 = 6.3 \\ 11.6 \times 32.0 \times .068 = 25.2 \end{array} \right\} 31.5 \text{ k (BEFORE EL 675.6 \& 660.0)}$$

$$9.5 \times 32.0 \times .115 = 35.0 \text{ (BETWEEN EL 660.0 \& 650.5')}$$

$$\Sigma V = 180.0 + 31.5 + 35.0 = 246.5 \text{ k}$$

$$\phi = 22^\circ \quad \tan \phi = .404$$

$$246.5 \times .404 = 100.0 \text{ k}$$

$$\phi = 23^\circ \quad \tan \phi = .424$$

$$246.5 \times .424 = 104.5 \text{ k}$$

$$\phi = 18^\circ \quad \tan \phi = .325 \quad .325 \times 246.5 = 80.5 \text{ k}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT SLIDING STABILITY

PROJECT LED #1

FILE NO. 800A

COMPUTED M.J. CHECKED B.M.M.

DATE 1/75 PAGE 62 OF PAGES


SLIDING STABILITY (CONT'D)

$$k_p = 1.5$$

$$1.5 \times .13 = .195 \text{ ksf/ft}$$

$$1.5 \times .068 = .102 \text{ ksf/ft}$$

$$1.5 \times .115 = .173 \text{ ksf/ft}$$



$$0.85 \times 27.2 = 23.1^k$$




$$0.5 \times .173 \times 4.8^2 = 2.0^k$$



$$22.6 \quad 38.2$$


$$.832 \times 27.2 + 1.40 \times 27.2 = 60.8^k$$



$$14.2 \quad 8.9$$

$$9.5 \times 3.63 + .93 \times 9.5 = 43.1^k$$

$$\Sigma H = 2.0 + 23.1 + 60.8 + 43.1 = 129.0^k$$



$$21.4$$

$$5.49 \times 5.0 + 2.5 \times 9.8 = 29.9^k$$

$$\Sigma H = 129 + 30 = 159^k$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT SLIDING STABILITY
OF L & D STRUCTURE

COMPUTED M. J. CHECKED R.N.M.


PROJECT LED #1

FILE NO. B00A

DATE 1.75 PAGE 68 OF PAGES

SLIDING STABILITY (CONTD)

SLIDING STABILITY C CLAY SEAM - SUMMARY



ASSUME NO COHESION IN CLAY SEAM

$$H_{w1} = 4.08 \times 65.2 / 2 = 133.0^k \quad (154^k)$$

$$H_s = 246.5 \times .404 = 100.0^k \quad (104.5^k)$$

$$H_p = 129.0^k$$


$$F_{SS} = \frac{100.0 + 129}{133.0} = 1.72 \quad \phi = 22^\circ \quad \frac{100 + 159}{154} = 1.68$$

$$F_{SS} = \frac{104.5 + 129}{133} = 1.75 \quad \phi = 23^\circ \quad \frac{104.5 + 159}{154} = 1.70$$

$$F_{SS} = \frac{90.5 + 129}{1.33} = 1.58 \quad \phi = 18^\circ \quad \frac{80.5 + 129}{154} = 1.36$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL MONOLITHS</u>	PROJECT <u>LED #1</u>
	COMPUTED <u>M. J.</u>	FILE NO <u>800A</u>
	CHECKED <u>R. N. M.</u>	DATE <u>11.74</u> PAGE <u>69</u> OF <u> </u> PAGES

LANDWALL MONOLITHS #4-15 - STABILIZING BY ANCHORS



- 1). $R = 219.0 \text{ K}$ INSIDE MIDDLE $\frac{1}{3}$ by
- 2). $\frac{\Sigma H}{\Sigma V} = \frac{71.0}{207.0} = 0.343$
- 3). $f_{SOIL} = 6.5 \pm 5.2$ [MAX 11.7 KSF
MIN 1.3 KSF]
- 4). $FSS = \frac{207 \times 6.25}{70.0} = 1.85$
- 5). $FSOT = \frac{4831}{2404} = 2.0$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDHALL MONOLITHS</u>	PROJECT <u>LED #1</u>
	COMPUTED <u>M.I.</u>	FILE NO <u>800A</u>
	CHECKED <u>P.N.M.</u>	DATE <u>11.74</u> PAGE <u>70</u> OF <u> </u> PAGES

LANDHALL MONOLITHS #⁵ 1-15 STABILIZING BY ANCHORS (CONT)

$$H_1 = 1.37 \times 32.7 / 2 = 22.40^k$$

$$H_2 = 1.37 \times 26.8 = 36.92$$

$$H_3 = .70 \times 26.8 / 2 = 9.36$$

$$H_4 = .80 \times 12.8 / 2 = 5.12$$

$$H_5 = .80 \times 14.0 = 11.20^k$$

$$\Sigma H = 85.0^k$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL MONOLITHS</u>	PROJECT <u>LED #1</u>
	COMPUTED <u>M.J.</u>	FILE NO. <u>800A</u>
	CHECKED <u>P.N.M.</u>	DATE <u>11.74</u> PAGE <u>71</u> OF <u> </u> PAGE

LANDWALL MONOLITHS #4-15 STABILIZING BY ANCHORS
(CONT'D)

MAXIMUM LOAD ON ANCHORS (ACTIVE PRESS. CONDITION)

$$22.40 \times 37.7 = 846.0$$

$$36.92 \times 13.4 = 495.0$$

$$9.36 \times 8.93 = 83.6$$

$$5.12 \times 18.27 = 93.4$$


$$\underline{11.20 \times 7.00 = 78.4}$$

$$\Sigma 85.0^k$$

$$\Sigma 1596.4^k / (MA)$$



$$H = \frac{1596.4}{55.50} = 28.7^k / \text{FT. OF WALL}$$



$$T = \frac{28.7}{3} \times 3.16 = 300^k / \quad V = 9.5^k /$$

$$\text{TOTAL } \Sigma T \text{ ON 30' MONOLITH} = 900.0^k$$

USE $\frac{1}{3}$ " RYERSON "DYWIDAG" BARS, WITH PRESTRESSING

$$.80 T_u = 187.2^k$$

CHECK STABILITY CONDITIONS USING 3 ANCHORS FOR EACH MONOLITH, SEE NEXT SH. $[3 \times 187.2 < 900.0^k]$
OK

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDFILL MONOLITHS
COMPUTED M.J. CHECKED P.N.M.

PROJECT LED #1
FILE NO 800A
DATE 11.78 PAGE 72 OF 72 PAGES

LANDFILL MONOLITHS #⁵ - STABILIZING BY ANCHORS
(CONT'D)

1 ϕ BARS; $180T_u = 187.2k$ ("RYERSON" CATALOG 40-1 PG. #5)

LOSS OF PRESTRESS ASSUMED 25 KSI (ACI, 318-71 COMMENT.)
18.6.1

USABLE TENSION $187.2 - 1.56 \times 25.0 = 148.2 k/\text{BAR}$

$$\frac{3 \times 148.2}{30} \times \frac{3.0}{3.16} = 14.0 k/\text{FT} (\approx H) \quad \begin{array}{c} T \quad 3.16 \\ \swarrow \quad \searrow \\ H \quad 3 \quad V \end{array}$$

EXISTING CONDITIONS

$$\Sigma V = 202.0k \quad \Sigma H = 85.0k \quad \Sigma M_A = 1647.0k$$

IMPROVED CONDITIONS

$$\Sigma V = 202.0 + 5.0 = 207.0k$$

$$\Sigma H = 85.0 - 14.0 = 71.0k$$

$$\Sigma M_A = 1647.0 + 14.0 \times 55.5 = 2425k$$

$$\Sigma R = 219.0k$$

$$\alpha = \frac{2425}{207} = 11.7'$$

$$e = 16.0 - 11.7 = 4.3'$$

$$M_{yy} = 4.3 \times 207 = 890.0k$$

$$1596.4 + 808 = 2404k$$

$$S_{yy} = \frac{32.0^2}{6} = 170.0 \text{ FT}^3$$

$$4051 + 14 \times 55.5 = 4831k$$

FOR RESULTS OF IMPROVED CONDITIONS SEE SAT #1

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILIZATION</u>	PROJECT <u>LOCK & DAM #1</u>
	<u>BY ROCK ANCHORS 1 1/2" x 4</u>	FILE NO <u>900 A</u>
COMPUTED <u>R.N.M.</u>	CHECKED <u>JL</u>	DATE <u>JAN '75</u> PAGE <u>72a</u> OF <u>72</u> PAGES

LANDWALLS 5-15
ANALYSIS OF UPPER LANDWALL MONOLITHS FOR ASSUMED
WATER SURFACE ON LANDWARD SIDE AT ELEVATION 704

Ref.: pages 69-72, and 75a

* P_n = Friction resistance due to weight of submerged slab = 5^k (pg 10)

	Σ Forces for W.S. @ El. 700 (From pg 72)	Change in hydrostatic and earth pressures, (P_g 75a)	Σ Forces for W.S. @ El. 704
$\Sigma H \rightarrow \leftarrow$	$+71^k - P_n^*$	6^k	$77 - 5 = 72^k$
$\Sigma V \downarrow \uparrow$	$+201^k$	-4^k	203^k
$\Sigma M_A \rightarrow \leftarrow$	-2425^k	163^k	2262^k

$$e = \frac{2262}{203} = 11.14' \quad e = 4.86' < 5.33$$

(1) Resultant, $R = 203$ inside middle $\frac{1}{3}$ by C.47'

$$(2) f_{soil} = \frac{202}{32} \left(1 + \frac{6 \times 4.86}{32} \right) = 6.34 (1 \pm 0.91)$$

$$f_{max} = \underline{12.1 \text{ KSF}}$$

$$f_{min} = \underline{0.6 \text{ KSF}}$$

$$(3) \text{Factor of sliding} = \frac{72}{203} = 0.355 \quad \frac{\Sigma H}{\Sigma V}$$

$$(4) \text{Factor of safety against sliding, } F.S. = \underline{1.76}$$


$$(5) \text{Factor of safety against overturning}$$

$$F.S.O.T. = \frac{4051}{2487 - 14.0 \times 55.5} = 2.37$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILIZATION</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	USING <u>LARGER ROCK ANCHORS</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.H.M.</u> CHECKED <u>J</u>	DATE <u>2/75</u> PAGE <u>72b</u> OF <u> </u> PAGES

LANDWALL MONOLITHS 5-15 IMPROVEMENT & STABILITY, USING LARGER ANCHORS
(ITEM 19 OF GENERAL COMMENTS RECEIVED 2/21/75)

DETERMINATION OF MAXIMUM SIZE OF ROCK ANCHORS IN
 LANDWALL, UTILIZING ONLY ACTIVE SOIL PRESSURE IN BACKFILL
 DURING PRESTRESSING.



$$T_1 = 28.5 \times \frac{3.16}{3.0} = 30 \text{ }^k \text{ PER FOOT OF WALL}$$

$$T = 30.0 \times 15 = 450 \text{ }^k \text{ MAX FOR ROCK ANCHORS SPCD 15' O.C.}$$

★ ASSUMED W.S. ELEV. DURING PRESTRESSING

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL STABILIZATION
USING LARGER ROCK ANCHORS
COMPUTED R. H. M. CHECKED ✓

PROJECT LOCK & DAM NO. 1
FILE NO. 800 A
DATE 2/75 PAGE 72C OF PAGES

LANDWALL MONUMENTS # 5-15
IMPROVEMENT OF STABILITY BY LARGER
ANCHORS (CONT'D)

MAX PRESTRESSING FORCE FOR
ACTIVE SOIL PRESSURE ONLY

ASSUME $2-1\frac{1}{4}" \phi$ BARS/ANCH. - See sketch attached.
"RYERSON"

PRESTRESSING FORCE, $0.80 f_{pu} = 150$ per rod

$$\begin{array}{r} \text{LOSSES } 1.25 \times 2 \times 25 \text{ ksi} = \frac{2}{300} \text{ K} \\ \text{DESIGN CAPACITY PER ANCHOR} = \underline{237 \text{ K}} \end{array}$$

ASSUME $3-1\frac{1}{4}" \phi$ RODS PER ANCHOR $150 \times 3 = 450 \text{ K}$

$$\text{DESIGN CAPACITY/ANCHOR} = 237 \times \frac{3}{2} = \underline{356 \text{ K}}$$

$$2-1\frac{1}{4}" \phi (\text{DOUBLE ROD}) \text{ CAPACITY} = \frac{237}{15} = 15.8 \text{ K/ft.}, < 30. \text{ *}$$

$$3-1\frac{1}{4}" \phi (\text{TRIPLE ROD}) \text{ CAPACITY} = \frac{356}{15} = 23.7 \text{ K/ft.}, < 30. \text{ *}$$

DOUBLE ROD ANCHOR:

$$15.8 \times \frac{3.0}{3.16} = \underline{15 \text{ K}} \leftarrow$$

$$15.8 \times \frac{1}{3.16} = \underline{5.0 \text{ K}} \downarrow$$

TRIPLE ROD ANCHOR:

$$23.7 \times \frac{3.0}{3.16} = \underline{22.5 \text{ K}} \leftarrow \text{PER FOOT OF WALL}$$

$$23.7 \times \frac{1}{3.16} = \underline{7.5 \text{ K}} \downarrow$$

* TENSION DUE TO MAXIMUM ACTIVE SOIL PRESSURE

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILIZATION</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	<u>USING LARGER ROCK ANCHORS</u>	FILE NO. <u>800A</u>
	COMPUTED <u>R.H.M.</u> CHECKED <u>JH</u>	DATE <u>2/75</u> PAGE <u>72d</u> OF <u> </u> PAGES

LANDWALL MONOLITHS 5-15 IMPROVEMENT OF STABILITY USING LARGER ANCHORS
STABILITY ANALYSIS (refer to page 72a)

A. 2 - 1 1/4" Ø STRAND PER ANCHOR, 2 ANCHORS PER MONOLITH

$$\Sigma H = 85 - 15 - - - = 70 \text{ K} \rightarrow$$

$$\Sigma V = 207 + 5 - - - = 212 \downarrow$$

$$\Sigma M = 1647 + 55.5 \times 15.0 = 2480' \text{ K} \rightarrow$$

$$L = 32'$$

$$\frac{L}{6} = 5.3'$$

$$\frac{L}{4} = 8.0'$$

$$(1) \bar{X} = \frac{2480}{212} = 11.7' \quad e = 4.3$$

RESULTANT INSIDE MIDDLE 1/2 1.0

$$(2) f = \frac{212}{32} (1 \pm \frac{6 \times 4.3}{32}) = \begin{cases} 12.0 \text{ KSF MAX.} \\ 1.3 \text{ KSF (MIN)} \end{cases}$$

$$(3) \frac{\Sigma H}{\Sigma V} = 0.33 \quad (4) \text{ FSS} = 1.89$$

$$(5) \text{ F.S.O.T.} = \frac{4051}{2487 - 15.0 \times 55.5} = 2.45$$

B. 3 - 1 1/4" Ø STRANDS PER ANCHOR, 2 ANCHORS PER MONOLITH

$$\Sigma H = 85 - 22.5 = 62.5 \text{ K}$$

$$\Sigma V = 207 + 7.5 = 214.5 \text{ K}$$

$$\Sigma M = 1647 + 55.5 (22.5) = 2896' \text{ K}$$

$$(1) \bar{X} = 13.5 \quad e = 16.0 - 13.5 = 2.5'$$


RESULTANT INSIDE MIDDLE 1/2 BY 2.83

$$(2) f = \frac{214.5}{32} (1 \pm \frac{6 \times 2.5}{32}) = \begin{cases} 9.80 \text{ KSF MAX.} \\ 3.60 \text{ KSF MIN.} \end{cases}$$

$$(3) \frac{\Sigma H}{\Sigma V} = 0.29 \quad (4) \text{ FSS} = 2.16$$


$$(5) \text{ F.S.O.T.} = \frac{4051}{2487 - 22.5 \times 55.5} = 3.27$$

Page 12 e





MATERIAL
 1R 1 1/2 x 7 1/2 x 8 A36
 OR Fy min = 33000, CARBON

FOR REFERENCE ONLY.

TOP PLATE FOR TWO BARS - TRUMAN DAM		DRAWN BY	CLYDE	DATE	10-
		REVISED BY		DATE	
		APPROVED BY	G che lla	DATE	10-1
CONSTRUCTION PRODUCTS COMPANY 					

This drawing has not been published, it is the sole property of the person or persons who have prepared it. It is loaned to the recipient for his confidential use only, and upon the conditions and agreements following: In consideration of the loan of this drawing, the recipient guarantees and agrees to return it upon request, and that it shall not be reproduced, copied, loaned or otherwise disposed of without the written consent of the Construction Products Company.

Page 72 F



ONLY

COUNTERSINK HOLE

MATERIAL

1 lb $1\frac{1}{2} \times 8 \times 8$ A36

OR MIN $F_y = 33000$, MIN CARBON = .15

For REFERENCE ONLY:

100 PINTS FOR THREE EARS TRUMAN DAM

**CONSTRUCTION
PRODUCTS COMPANY**

DRAWN BY	DATE
CLYDE	10-3-76

REVISED BY

DATE 10-3-76

DATE _____

APPROVED BY	DATE
C. Chaffin	10-7-74

DATE 10-7-74

This drawing has not been published. It is the sole property of Island-Ryan Construction Products Company. It is lent to the recipient for his confidential use only, and upon the conditions and agreements following. In consideration of the loan of this drawing, the recipient promises and agrees to return it upon request, and that it shall not be reproduced, copied, lent or otherwise disposed of without the written consent of Island-Ryan Construction Products Company.

FOR USE ON U.S. GOVERNMENT WORK ONLY

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY OF LAND</u>	PROJECT <u>LED #1</u>
	<u>WALL MONOLITHS</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u>	CHECKED <u>R.N.M.</u>
	DATE <u>8.74</u>	PAGE <u>74</u> OF <u> </u> PAGES

LANDWALL MONOLITHS #2-15-LOWERING BACKFILL BY 10'-0"

	LOADS IN KIPS	VERT. ↓	VERT. ↑	HORIZ. →	HORIZ. ←	ARM	MOMENT	MOMENT
C ₁	40.0 × 24 × 1/2 × .15	72.0				16.0		1150.0
C ₂	12.0 × 30.0 × .15	54.0				17.0		918.0
C ₃	8.0 × 3.0 × .088	2.1				28.0		58.8
C ₄	2.0 × 4.0 × .088	0.7				1.0		0.7
C ₅	47.5 × 6.0 × .150	42.8				5.0		214.0
C ₆	17 × 4.15 × .088		6.2			15.0	94.0	
E ₁	22.6 × 9.0 × .110	22.4				27.5		617.0
E ₂	16.0 × 22.6 × .055	20.0				18.5		370.0
E ₃	9.0 × 7.5 × .180	8.8				29.0		255.0
								<u>23583.5</u>
W ₁	.88 × 30.0		26.4			17.0	450.0	
W ₂	.40 × 30.0		12.0			22.0	264.0	
							<u>2808.0</u>	
H _{E1}	.95 × 11.3			10.7		34.4	370.0	
H _{E2}	.95 × 26.9			25.6		13.5	345.0	
H _{E3}	.35 × 26.9			9.4		9.0	84.6	
H _{w1}	.84 × 26.9			22.6		9.0	204.0	
H _{w2}	.44 × 14.1				6.2	4.7		29.2
		222.8	44.6	68.3	6.2		1812.0	3613.0

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	STABILITY OF LAND WALL MONOLITHS #4-15	PROJECT	LED #1
	COMPUTED	M.J.	FILE NO.	800A
	CHECKED	Z.M.	DATE	8.74 PAGE 75 OF PAGES

LAND WALL MONOLITHS #4-15 - LOWERING BACKFILL BY 10' 0" (CONT'D)

$$\Sigma V = 222.8 - 44.60 = 178.2^k$$

$$\Sigma M = 3613 - 1812.0 = 1801^k \cdot ft$$

$$\Sigma H = 62.1^k \quad R = 189.0^k$$

$$a = \frac{1801.0}{181.2} = 10.10$$

$$e = \frac{10.6}{3} - 10.10 = 0.57$$

1. RESULTANT OUTSIDE MIDDLE $\frac{1}{3}$ BY 0.57'

$$2. \frac{\Sigma H}{\Sigma V} = \frac{62.10}{178.2} = .343'$$

$$3. F.S.S. = \frac{178.2 \times .625}{62.1} = 1.79$$

$$4. f_{SNL} = \frac{2}{3} \times 181.2 / 10.10 = 12.0 \text{ ksf}$$


$$5. F.S.O.T. = \frac{3613.0}{1812} = 2.0$$

FOR USE ON U.S. GOVERNMENT WORK ONLY

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL STABILIZATION</u>	PROJECT <u>LOCK & DAM NO. 1</u>
	<u>BY LOWERING OF BACKFILL</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u>	CHECKED <u>JL</u>
	DATE <u>1/21/75</u>	PAGE <u>75</u> OF <u>75</u> PAGES

ANALYSIS OF UPPER LANDWALL MONOLITHS FOR ASSUMED WATER SURFACE ON LANDWARD SIDE AT ELEVATION 704

Reference: Pgs 73-75 of this computation



W.S. LANDWARD SIDE @ EL 704

W.S. LANDWARD SIDE @ EL 700

$$30 + 7.26 + 24.1 + 12.3 - 6.1 = 68^{\text{K}} \rightarrow$$

$$\times \frac{10.3}{37} \times \frac{15.4}{10.3} \times \frac{4.7}{29} = 1047^{\text{K}} \downarrow$$

$$309 + 269 + 371 + 127 + 29 = 1047^{\text{K}} \downarrow$$

$$31 + 1.4 = 45^{\text{K}} \uparrow$$

$$\times \frac{21.3}{10.7} \times \frac{150}{150} = 810^{\text{K}} \downarrow$$

$$660 + 150 = 810^{\text{K}} \downarrow$$

$$22.4 + 10.7 + 25.6 + 9.4 - 6.1 = 62^{\text{K}} \rightarrow$$

$$\times \frac{9}{34.4} \times \frac{13.4}{9} \times \frac{4.7}{29} = 969^{\text{K}} \downarrow$$

$$202 + 368 + 343 + 85 - 29 = 969^{\text{K}} \downarrow$$

$$27 + 1.4 = 41^{\text{K}} \uparrow$$

$$\times \frac{21.3}{10.7} \times \frac{150}{150} = 725^{\text{K}} \downarrow$$

$$575 + 150 = 725^{\text{K}} \downarrow$$

$$\Delta H = 68 - 62 = 6^{\text{K}} \rightarrow$$

$$\Delta V = 45 - 41 = 4^{\text{K}} \uparrow$$

$$\Delta M_A = 1047 + 810 - 969 - 725 = 163^{\text{K}} \downarrow$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL STABILIZATION
BY LOWERING OF BACKFILL
COMPUTED R.N.M. CHECKED JL

PROJECT LOCK and DAM #1
FILE NO 800 A
DATE JAN '75 PAGE 756 OF PAGES

Upper Landwall Monoliths, (cont'd)

	Σ FORCES FOR W.S. @ EL. 700	CHANGE IN HYDROSTATIC AND EARTH FORCES	Σ FORCES FOR W.S. @ EL. 704
Σ H → ⊕	+62 ^K - P _r *	+6 ^K	+68 ^K - 5 = 63 ^K
Σ V ↓ ⊕	+178 ^K	-4 ^K	+174 ^K
Σ M _A ↺ ⊕	-1801 ^K	+163 ^K	-1638 ^K

$$a = \frac{1638}{174} = 9.41' \quad e = 16 - 9.41 = 6.59$$

$$\text{Resultant } R = 174^{\text{K}}, \text{ outside middle } \frac{1}{3}, \frac{5.33}{1.26}$$

$$f_{\text{soil}} = \frac{2}{3} \times \frac{174}{9.41} = \underline{12.33 \text{ KSF}}$$

$$\text{Factor of sliding} = \frac{\Sigma H}{\Sigma V} = 0.35$$

$$\text{Factor of safety against sliding} = \frac{625}{.36} = \underline{1.74}$$

$$F.S.O.T. = \frac{3519}{1718 + 163} = 1.87$$

* Friction resistance due to weight of submerged slab.

$$P_r = 56 \times 2 \times 0.002 \times 0.55 = 6^{\text{K}}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LAND WALL - IMPROVED
CONDITION
COMPUTED R.N.M. CHECKED J.I.

PROJECT LOCK & DAM No. 1
FILE NO. 800 A
DATE 3/75 PAGE 75C OF PAGES

MONOLITH No. 3
NORMAL LOADING
IMPROVED (OR STABILIZED) CONDITION

BACKFILL IS LOWERED BY 8', GATE SHAFTS ARE FILLED.

The only differences in load between this condition and that of existing (lowered conduit, shafts filled) condition are the following decreases both in horizontal earth pressure, and weight of backfill

$$\frac{20.7}{2} (.042) = 9.0^k$$

$$20.7 (.042) (30.8) = 26.8^k$$

$$\Delta H = (17.3 - 9) + (37.3 - 26.8) \\ = 8.3 + 10.5 = 18.8^k$$

$$\Delta M_A = -(17.3) 40.4 + 9 (37.7) \\ + (-10.5 \times 15.4 - 5 \times 29) \\ = (-699 + 339) - 162 + 145 \\ = -377^k$$

$$\Delta V = 8 \times 6 \times 0.11 = 5^k \uparrow \\ \times \frac{29}{145} \rightarrow 145^k \downarrow$$


$$\Sigma H = 85 - 18.8 = 66.2^k \rightarrow$$

$$\Sigma V = 201 - 5 = 196^k \downarrow$$

$$\Sigma M_A = 1660 + 377 = 2037^k \rightarrow$$

$$a = 10.39$$

$$e = 5.61 \rightarrow 5.33$$



(1) Resultant outside middle $\frac{1}{3}$ by 0.28'

(2) $f_{soil} = \frac{2}{3} \left(\frac{195}{10.39} \right) = 12.5 \text{ KSF}$

(3) $\Sigma H / \Sigma V = 66.2 / 196 = 0.338$ (4) $\text{FSF} = 1.85$

(4) FSOT not necessary, resultant is almost at middle $\frac{1}{3}$ (-2.05)

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LAND WALL - IMPROVED
CONDITION
COMPUTED R.N.M. CHECKED J.I.

PROJECT LOCK & DAM NO. 1
FILE NO. 800 A
DATE 7/75 PAGE 75d OF PAGES

MONOLITH N# 4
NORMAL LOADING
IMPROVED (OR STABILIZED) CONDITION

BACKFILL IS LOWERED BY 10 FEET - The only differences in load between this condition and that of existing (lowered conduit, 2 gate shafts full conc. sect.) condition are the following decreases ($\Delta H, \Delta V$ & ΔM) both in horizontal earth pressure and weight of backfill.

$$18.7^2 \left(\frac{1}{2}\right) (.042) = 7.3 \text{ kips/ft. of wall}$$

$$18.7 (.042) (30.8) = 24.2$$

$$\Delta H = \frac{17.3}{10.0} \times 37.3 - \frac{7.3}{13.0} \times 24.3 = -23.0 \text{ k} \leftarrow$$


$$\Delta V = 10 \times 6 \times 11 = -6.6 \text{ k} \uparrow$$

$$-17.3 \times 40.4 + 7.3 (37.03) = -429 \text{ k}$$

$$-13.0 \times 15.4 = -200 \text{ k}$$

$$6.6 \times 29.0 = 191 \text{ k}$$

$$\Delta M_A = -438 \text{ k}$$



$$\Sigma H = 85.0 - 23.0 = 62.0 \text{ k} \rightarrow$$

$$\Sigma V = 191.0 - 6.6 = 184.4 \text{ k} \downarrow$$

$$\Sigma M_A = -1520 - 438 = -1958 \text{ k}$$

$$a = 10.62'$$

$$e = 5.38'$$

$$- \frac{5.38}{0.05} = -107.6$$

(1) Resultant outside middle $\frac{1}{3}$ by 0.05 feet

$$(2) f_{soil} = (2/3) (184.4) (1/10.6) = 11.58 \text{ KSF}$$

$$(3) (\Sigma H / \Sigma V) = 0.338 \quad (4) \text{ S.S.F.} = 1.86$$

$$(5) \frac{4128 - 146 - 191}{2968 - 679} = \frac{3797}{2289} = 1.66 = \text{F.S.O.T.}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL MONOLITHS

PROJECT LED #1

FILE NO 800A

COMPUTED M. J. CHECKED R. N. M.

DATE 12.7.74 PAGE 76 OF 76 PAGES

LANDWALL GATE MONOLITH #17 - 10' 0" BACKFILL REMOVAL

$H_1 = .95 \times 22.70/2 \times 28.6$	$= 309.0^k$	37.37	11,500
$H_2 = .95 \times 23.80 \times 28.6$	$= 810.0$	14.90	12,030
$H_3 =$	$= 339.0$	9.93	3,350
$H_4 =$	$= 145.0$	21.27	3,100
$H_5 =$	$= 389.0$	8.50	3,310
	<u>1991.0 k</u>		<u>33,290 k</u>

$$V_3' = 6.0 \times 28.6 \times 10.0 \times .115 = 197.0^k \uparrow$$

$$\Sigma V = 5910 - 197 = 5713^k \downarrow$$

$$\Sigma H_x = 1991.0^k$$

$$\Sigma M_A = 108,304 - 197.0 \times 27.0 - 33,290 - 23,460 = 46,234^k$$

$$\Sigma M_{xx} = 1550^k \quad \Sigma M_{yy} = 5289 \times 6.90 = 39,420^k$$

$$\alpha = \frac{46,234}{5713} = 8.10$$

$$e = 15.0 - 8.10 = 6.90 > 5.00 \text{ OUTSIDE MIDDLE } \frac{1}{3} \text{ BY } 1.90$$

MAX SOIL PRESSURE

$$f = \frac{2}{3} \times \frac{5713}{28.6 \times 8.10} = 16.44 \text{ ksf}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL MONOLITHS</u> COMPUTED <u>M.T.</u> CHECKED <u>R.N.M.</u>	PROJECT <u>LED #1</u> FILE NO <u>800A</u> DATE <u>12.74</u> PAGE <u>77</u> OF <u> </u> PAGES
--	---	---

LANDWALL GATE MONOLITH #17-10'0" BACKFILL REMOVAL

$\Sigma V = 5713.0^k$ $\Sigma H_x = 1991.0^k$ $\Sigma H_y = 39400^k$ (CONT'D)

1). $f_{soil} = 16.44^k/sf$

2). $R = 6050^k$ ^{outside middle $\frac{1}{3}$ by 1.9'}
~~inside middle $\frac{1}{3}$ by 2.7'~~

3). $\frac{\Sigma H}{\Sigma V} = \frac{1991}{5713} = .350$

4). $FSS = \frac{5713 + 625}{1991.0} = 1.79$

5). $F_{OT} = \frac{102964}{56750} = 1.81$


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL MONOLITHS


COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 11.74 PAGE 78 OF PAGES

LANDWALL GATE MONOLITH #17 - STABILIZING BY ANCHORS



1. $f_{soil} = 18.70 \text{ ksf}$
2. $R = 6440 \text{ INSIDE}$
3. $\frac{\Sigma H}{\Sigma V} = \frac{2260}{5031} = .37$
4. $FSS = \frac{605 \times 62.5}{2260} = 1.67$
5. $F_{SOT} = \frac{131504}{76920} = 1.71$



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL MONOLITHS

COMPUTED M.J. CHECKED P.V.M.

PROJECT LED #1

FILE NO. 800A

DATE 1274 PAGE 79 OF PAGES

LAND WALL GATE MONOLITH #17-STABILIZING BY ANCHORS
(CONT'D)

EXISTING CONDITIONS


$$\Sigma H = 2685^k$$

$$\Sigma V = 5910^k \quad \Sigma M_A = 31,384^k \quad \Sigma M_{ux} = 1550^k$$

IMPROVED CONDITIONS USING 3 ANCHORS

3 - 1 1/8" ANCHORS, SEE CALCS FOR MONO'S # 4-15

USEFUL TENSION 140.2^k/BAR



$$T = 140.2 \times 3 = 420.6^k \quad H = 425.0^k \quad V = 141.0^k$$

$$\Sigma V = 5910 + 141 = 6051^k$$

$$\Sigma H_{\text{net}} = 2685 - 425 = 2260^k$$

$$\Sigma M_A = 31,384 + 425 \times 54.50 = 31,384 + 23,200 = 54,584^k$$

$$a = \frac{54,584}{6051} = 9.00'$$

$$e = 6.00'$$

$$M_{yy} = 6051 \times 6.00 = 36,300^k$$

$$f_{sm} = \frac{2}{3} \times \frac{6051}{9.00 \times 28.6} = 18.70 \text{ ksi}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL MONOLITHS

PROJECT LED #1

FILE NO. 900A

COMPUTED M. J. CHECKED R. N. M.

DATE 12.74 PAGE 80 OF PAGES

LANDWALL GATE MONOLITH #17 - STABILIZING BY ANCHORS
(CONT'D)

IMPROVED CONDITIONS OF STABILITY BY 3 ANCHORS
(CONT'D)

$$\frac{\Sigma H}{\Sigma V} = \frac{2260}{6051} = \underline{.37}$$

$$f_{SOIL} = 18.70 \text{ ksf}$$

$$F_{SS} = \frac{6051 \times .625}{2260} = \underline{1.67}$$

$$M_A = 108,304 + 23,200 = 131,504 \text{ k}$$

$$M_A^2 = 76,920 \text{ k}$$

$$F_{SOT} = \frac{131,504}{76,920} = 1.71$$

$$R = 6440 \text{ k}$$

$$(4 - 1\frac{3}{8} \text{ ROCK ANCHORS } F_{SS} = 1.88)$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT LANDWALL MONOLITHS
COMPUTED M.J. CHECKED RNM

PROJECT LED #1
FILE NO. 300A
DATE 12.74 PAGE 81 OF PAGES

LANDWALL GATE MONOLITH #17-STABILIZING BY BACKFILL
REMOVAL (NO DEEP) AND ANCHORS (3-18" ANCHORS)

$$\Sigma V = 5713 + 141 = 5854 \text{ k}$$

$$\Sigma H = 1991 - 425 = 1566 \text{ k}$$

$$\Sigma M_A = 46,234 + 425 \times 54.50 = 69,434 \text{ k}$$

$$e = \frac{69,434}{5854} = 11.80$$

$$1) e = 3.20'$$

$$M_{yy} = 5854 \times 3.20 = 18,700 \text{ k}$$

$$S_{yy} = 6 \times 30.0^2 \times 28.6 = 4290 \text{ ft}^3$$

$$A = 28.6 \times 30.0 = 958 \text{ ft}^2$$

$$2) f_{soil} = \frac{5854}{958} \pm \frac{18700}{4290} = 6.8 \pm 4.3 \begin{cases} \text{MAX } 11.10 \text{ ksf} \\ \text{MIN } 2.50 \text{ ksf} \end{cases}$$

$$3) \frac{\Sigma H}{\Sigma V} = \frac{1566}{5854} = .269$$

$$4) F_{ss} = \frac{5854 \times .625}{1566} = 2.34$$

$$M_A = 109,304 - 5340 + 23200 = 126,164$$

$$M_A^2 = 33,290 + 23460 = 56,750 \text{ k}$$

$$5) F_{sot} = \frac{126,164}{56,750} = 2.23$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>LANDWALL</u>	PROJECT <u>LED #1</u>
		FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u>	CHECKED <u>RNM</u>
	DATE <u>12.74</u> PAGE <u>82</u> OF <u> </u> PAGES	

SUMMARYLANDWALL GATE MONO #17-STABILIZING BY 10'-0" BACKFILL REMOVAL

1. $R = 6050 \text{ k OUTS. MIDDLE } \frac{1}{3} \text{ BY } 1.90'$

2. $\frac{\Sigma H}{\Sigma V} = \frac{1991}{5713} = .35$

3. $f_{\text{SOIL}} = 16.44 \text{ ksf}$

4. $FSS = \frac{5713 \times .625}{1991} = 1.79$

5. $FSOT = \frac{102964}{56750} = 1.81$

LANDWALL GATE MONO #17-STABILIZING BY 10'-0" BACKFILL -- REMOVAL AND 3-12" ANCHORS

1. $R \text{ INSIDE MIDDLE } \frac{1}{3} \text{ BY } 1.80'$

2. $\frac{\Sigma H}{\Sigma V} = .27$

3. $f_{\text{SOIL}} = 11.10 \text{ ksf}$

4. $FSS = 2.34$

5. $FSOT = 2.23$

HARZA
ENGINEERING
COMPANY
CHICAGO


SUBJECT I-WALL STABILITY -
IMPROVED - NORMAL LOADING
COMPUTED R.N.M. CHECKED ✓

PROJECT LOCK & DAM #1
FILE NO. 800 A
DATE 3/75 PAGE 82a OF PAGES

INTERMEDIATE WALL GATE MONOLITH NO. 18
IMPROVEMENT OF STABILITY BY VERTICAL ROCK ANCHORS
NORMAL LOADING CONDITION

Approximate arrangement of
5" ϕ \pm boreholes was estimated
from drawings available with
the indication that there
is only a very
limited space for
rock anchors.

Assume 3-1/4" ϕ Bar tendons
per anchor, design capacity
= 356 k per anchor.
(Page 78 c)



Resultant of 12 Anchors:

** Figures taken from
existing-normal load-
ing condition, pg 40

$$\begin{array}{rclcl} 6 & \times & 7 & = & 42 \\ 2 & \times & 18 & = & 36 \\ 4 & \times & 14 & = & 56 \\ \hline 12 & h & & = & 134 \end{array}$$

$$h = 11.2$$

$$y = -\underline{2.8} \text{ ft}$$

$$12 \times 356 = 4272 \text{ k} \downarrow$$

From existing condition, pg 40

$$H = 3650 \text{ k} \quad V = 6081 \text{ k} \quad x = 12.4' \quad y = -7.9'$$

4267

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT I-WALL STABILITY-
IMPROVED-NORMAL LOADING
COMPUTED R.N.M. CHECKED VI

PROJECT L & D #1
FILE NO 800 A
DATE 3/75 PAGE 82b OF PAGES

I-WALL GATE MONOLITH 18
IMPROVEMENT OF STABILITY BY VERTICAL ANCHORS
NORMAL LOADING CONDITION (Cont'd)

Location of Resultant:

$$\begin{array}{rcl} \begin{array}{l} 4272 \\ \cancel{1320} \end{array} \times 2.8 & = & \begin{array}{l} 11962 \\ \cancel{12480} \end{array} \\ \underline{6081} \times 7.9 & = & \underline{48040} \\ EV = \frac{(\cancel{12480})^K}{10353} e_y = \underline{5.8'} & & \frac{60002}{(\cancel{58136})^K} = EM_x \end{array}$$

$$\begin{array}{rcl} \begin{array}{l} 4272 \\ \cancel{1320} \end{array} \times 0 & = & 0 \\ \underline{6081} \times 12.4 & = & \underline{75400} = EM_y \\ \begin{array}{l} \cancel{12480} \\ 10353 \end{array} e_x = \underline{7.3'} & & \underline{75400} \end{array}$$

Bearing pressures: ("Foundation Design")

$$A \quad \frac{e_x}{35} = 0.208 \quad \frac{e_y}{28} = 0.207 \quad K = 4.5$$

$$(1) F_{max} = \frac{K EV}{A} = \frac{4.5 \times 10^{353}}{980} = \underline{47.55} \text{ KSF}$$

(2) Resultant is outside, "KERN"

$$(3) \text{Sliding factor (along x-axis)} = \frac{3650}{1041353} = \underline{0.35}$$

$$(4) \text{Sliding factor of safety} = \frac{0.625}{0.353} = \underline{1.77}$$

Conclusion: Referring to results on page 41, bearing pressure decreased by 36%, but it's still too high.
∴ Stabilizing by interconnection of 3 monoliths is recommended.


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
DOWNSTREAM GATE MONO #18
COMPUTED M.T. CHECKED _____

PROJECT LED #1
FILE NO. 800A
DATE 1.75 PAGE 83 OF _____ PAGES

STABILIZATION OF INTERM. WALL GATE MONO #18

12 ANCHORS WITH 300 KIPS CAPACITY EACH



$$M_{xx} = 37,606 \text{ k} \cdot \text{ft} \quad y = 6.1'$$

$$M_{yy} = 181,105 \text{ k} \cdot \text{ft} \quad x = 29.9'$$

$$\Sigma V = 6081 \times 3600 = 9681 \text{ k}$$

$$x' = \frac{6081 \times 12.4}{9681} = 7.8'$$

$$y' = \frac{6081 \times 7.9}{9681} = 4.96'$$


$$\frac{e_x}{d} = \frac{7.8}{35.0} = .22$$

$$\frac{e_y}{b} = \frac{4.96}{28.0} = .18$$

$$C = 4.2 \quad f_{\text{sole}} = 4.2 \frac{9681}{980} = 41.5 \text{ k} \cdot \text{F}$$

$$F_{\text{SOT}} = \frac{9681 \times 17.5}{102,600} = 1.65$$

$$F_{\text{SS}} = \frac{9681 \times 6.25}{3650} = 1.66$$

HARZA
ENGINEERING
COMPANY
CHICAGOSUBJECT INTERMEDIATE WALL
GATE MONOLITH #18
COMPUTED M.J. CHECKED R.N.M.PROJECT LED #1
FILE NO 800A
DATE 12.74 PAGE 84 OF PAGESINTERMEDIATE WALL GATE MONOLITH #18MONO'S #17, 18, 19 INTERCONNECTEDMONOLITH #19

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	INTERMEDIATE WALL GATE MONOLITH #18		PROJECT	LED #1	
	COMPUTED	M.J.		FILE NO.	800A	
	CHECKED	R.N.M.		DATE	12.74 PAGE 85 OF 85	

INTERMEDIATE WALL GATE MONOLITH #18 (CONT'D)

MONOLITHS #18 & #19 INTERCONNECTED (CONT'D)

MONOLITH #19

	LOADS KIPS	V ↓	V ↑	ARM	M _{xx}	M _{yy}	M _{xy}	M _{yx}
①	35×23×57×.15	6883						
②	5.5×3×23×.087	33		14.75			487	
③	2×80×23×.15		552					
④	2×6×8×23×.063	139						
⑤	4.5×3.08×.50		693	8.5		5890		
⑥	4×8×53.5×.15		257	10.5	2638			
⑦	4×9×12.3×.063	25		10.5		263		
⑧	$(14^2 - \frac{2.5^2}{2}) \times 53 \times .15$		1533	6.5				9964
⑨	$(14^2 - \frac{2.5^2}{2}) \times 7 \times .063$	95		6.5			553	
Wt.	11.5×.063×2×.35		583					
		Σ 7166	3618		2698	6153	1040	9964
		Σ V: 3548 ↓			Σ 34552		Σ 89242	

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u>	PROJECT <u>LED #1</u>
	<u>GATE MONO. #18 & MONO. #19</u>	FILE NO. <u>B00A</u>
	COMPUTED <u>M.J.</u>	CHECKED <u>R.N.M.</u>
	DATE <u>12.74</u> PAGE <u>86</u> OF <u> </u> PAGES	

INTERMEDIATE WALL GATE MONO #18 & MONO #19 -
- INTERCONNECTED
(BY SHEAR KEYS)

MONOLITH #18

$$M_{yy} = 6081 \times 12.4 = 75500 \text{ k}$$

$$M_{xx} = 6081 \times 7.90 = 48100 \text{ k}$$

$$V = 6081 \text{ k} \quad \text{AREA } 35 \times 28 = 980 \text{ ft}^2$$

MONOLITH #19

$$M_{yy} = 3548 \times 2.51 = 8920 \text{ k}$$

$$M_{xx} = 3548 \times 0.97 = 3450 \text{ k}$$

$$V = 3548 \text{ k} \quad \text{AREA } 23 \times 35 = 805 \text{ ft}^2$$

6081

$$3548 \times \frac{10.57}{(12.47 + 6.1)} = 66,000$$

9629

$$y_1 = \frac{66000}{9629} = 6.85'$$

$$6081 \times 12.4 = 75400$$

$$3548 \times 2.51 = 8910$$

$$84310 \text{ k}$$

$$x_1 = \frac{84310}{9629} = 8.75'$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
GATE MONOLITH #18
COMPUTED M. J. CHECKED R. N. M.

PROJECT LED #1
FILE NO. 800 A
DATE 12.74 PAGE 87 OF PAGES

INTERMEDIATE WALL GATE MONOLITH #18, INTERCONNECTED
WITH MONOLITH #19 (CONT'D)

MONOLITH #19 $\Sigma V = 3548 k$

$\Sigma M_{xx} = 3455' k$

$\Sigma M_{yy} = 8924' k$

$e_y = \frac{3455}{3548} = 0.97'$

$e_x = \frac{8924}{3548} = 2.51'$


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
GATE MONO #18 & MONO #19
COMPUTED M.J. CHECKED R.N.M.

PROJECT LS P#1
FILE NO. 8004
DATE 12.74 PAGE 88 OF 88 PAGES

INTERMEDIATE WALL GATE MONO #18 & MONO #19 -

INTERCONNECTED (UNITED)
(BY SHEAR KEYS)



$$H_x = 3650k \rightarrow$$

$$H_y = 2210k \downarrow$$

$$\text{RESULTANT } H = 4280k$$

$$M_x = 9629 \times 3.25 = 31400'k$$

$$M_{yy} = 9629 \times 8.75 = 84200'k$$

1). LEAN T-N-T @ MIDDLE 2'

$$2). \frac{H}{V} = \frac{4280}{9629} = .445$$

$$3). FSS = \frac{9629 \times 6.25}{4280} = 1.41 \text{ (MAY BE RESISTED BY FLOOR)}$$

$$4). f_{soil} = 3.25 \times \frac{6081}{28 \times 35} = 2910 \text{ KSF} \quad C = 3.25$$

$$\frac{e_x}{b_1} = \frac{8.75}{35.0} = 0.25 \quad \frac{e_y}{b_1} = \frac{3.25}{51.0} = 0.064$$

$$5). F_{SOT} = \frac{134170}{102400} = 1.31$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
GATE MONO #18 & MONO #19
COMPUTED M.J. CHECKED P.N.M.

PROJECT LED #1
FILE NO 800A
DATE 12.74 PAGE 89 OF PAGES

INTERMEDIATE WALL GATE MONO #18 & MONO #19 INTERCON-
-NECTED (JOINTED)
(BY SHEAR KEYS)
OVERTURNING STABILITY

MONOLITH WT. 6634^k $M_{yy} = 116,900'k$ $a = 17.5' @ \frac{1}{2}$

$M^2 = 1380 \times 20.0 + 583 \times 17.5 + 112,600'k = 102,400'k$

$M^2 = \underbrace{(6634 + 470)}_{124,000} \times 17.5 + \underbrace{440 \times 17.5}_{7700} + \underbrace{2470}_{197,540} = 134,170'k$

WATER IN CULVERTS AND GATE SLOTS

$8 \times 10 \times 28 \times .063 = 141'k$ $141 + 85 = 226'k$

$8 \times 6 \times 28 \times .063 = 85'k$ $141 - 85 = 56'k$

GATE SLOTS $13.5 \times 4.0 + (2 \times 4 - 2) = 54.0 + 6 = 60.0'k$ $440'k$

$60 \times 8.5 \times .063 = 37'k$ $176 - 37 = 213'k$

$60 \times 46.5 \times .063 = 176'k$ $176 - 37 = 139'k$

$M_{yy} = 56 \times 5.5 + 139 \times 15.5 = 308 + 2160 = 2470'k$


$FSOT = \frac{\frac{197,540}{134,170} \times 1.15}{\frac{112,600}{102,400}} = 1.31$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
GATE MONOLITH #18
COMPUTED RNM CHECKED _____

PROJECT LOCK & DAM #1
FILE NO 8COA
DATE _____ PAGE 90 OF _____ PAGES

MONOLITH # 17



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>INTERMEDIATE WALL</u>	PROJECT <u>LOCK & DAM #1</u>
	GATE MONOLITH #18	FILE NO. <u>800A</u>
	COMPUTED <u>R.V.A.</u> CHECKED <u>M.J.</u>	DATE <u>12/74</u> PAGE <u>91</u> OF <u> </u> PAGES

FORCES IN MONOLITH #17

	$V \downarrow$	x	y	M_{Y-Y}	M_{X-X}
① $35 \times 57.1 \times 28 \times 0.15$	+8394 ↓	0	0	0	0
② $9 \times 3 \times 2 \times 28 \times 0.15$	+227 ↓	0	0	0	0
- ③ $80 \times 2 \times 28 \times 0.08$ $- 80 \times 2 \times 18 \times 0.15 = -672$ $2.8 \times 8 \times 18 \times 0.08 / 70 = -500$	-358 ↑	0	0	0	0
- ④ $54.6 \times 4 \times 2 \times 19.5 \times 0.15$	-1278 ↑	0	4.25	0	-5432
⑤ $47.1 \times 4 \times 19.5 \times 0.063$	+231 ↓	15.5	4.25	-3581	+982
⑥ $12.1 \times 4 \times 19.5 \times 0.063$	+59 ↓	15.5	4.25	+915	+251
⑦ $4.7 \times 4 \times 2 \times 28 \times 0.15$	-153 ↑	0	0	0	0
SUB TOTAL	= +7117.600			= -2666	-4199
				2930	7870
UPLIFT	= -1380	2.5	0	+3450	0

$$H = \left(\frac{2.37 \times 3}{2} + 2.37 \times 11.1 \right) = 71.6$$

$$H = 71.6 \times 28 = \underline{2000}^K \quad \quad \quad 41,000$$

$$\Sigma H = 2,000^K \rightarrow$$

$$\Sigma V = 5530^K \downarrow$$

$$\Sigma M_{Y-Y} = +41,784.2$$

$$\Sigma M_{X-X} = -4199.3$$

$$e_x = \frac{41784}{5537} = 7.28' > \frac{L}{6}$$


$$e_y = \frac{4199}{5537} = 0.73'$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
GATE MONOLITH #18
COMPUTED M.J. CHECKED M.J.

PROJECT LED #1
FILE NO. 800A
DATE 12.74 PAGE 92 OF 92 PAGES

INTERMEDIATE WALL GATE MONOLITH #18-IMPROVED CONDITIONS
OF STABILITY BY INTERCONNECTING MONO'S #17, 18 & 19



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	INTERMEDIATE WALL	PROJECT	LED #1
		GATE MONOLITH #18 & MONO'S	FILE NO.	800A
	COMPUTED	M. J.	CHECKED	17519 R. R. M.
			DATE	12-74 PAGE 99 OF PAGE 99

INTERMEDIATE WALL GATE MONO #18 & MONO'S #17 & 19

INTERCONNECTED BY SHEAR KEYS,

OVERTURNING STABILITY

$$M^p = 102,400 + 1260 \times 27.27 + 960 \times 7.3 + 1380 \times 2.5 = 147,380 \quad 181,720'k$$

$$H = (2.37 \times 38.0/2 + 2.37 \times 14.5) \times 28 = 1260 + 960 = 2220k$$

$$F_{sot} = \frac{6960 \times 17.5 + 134170}{147380} = \frac{319340}{147380} = 1.74$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
GATE MONOLITH #18 & MONO'S
COMPUTED M.J. 17519
CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 12.74 PAGE 94 OF PAGES

INTERMEDIATE WALL GATE MONO #18 & MONO'S #17 & 19

INTRCONNECTION BY SHEAR KEYS (CONT'D)

$$M_{yy} = 5580 \times 7.4 + 6081 \times 12.4 + 3548 \times 2.5 = 125,590 \text{ k}$$

$$e_x = \frac{125,590}{15210} = 8.3'$$

$$\Sigma V = 5580 + 6081 + 3548 = 15210 \text{ k}$$

1). RESULTANT ^{OUTSIDE} INSIDE MIDDLE ^{2.4} BY ³ OR 1'

$$2). \frac{\Sigma H}{\Sigma V} = \frac{5650}{15210} = .37$$

$$3). FSS = \frac{15210 \times .625}{5650} = 1.68$$

$$4). f_{soil} = 2.60 \times \frac{6081}{35 \times 28} = 16.1 \text{ ksf OR } \frac{2}{3} \times \frac{6081}{9.2 \times 28} = 15.7 \text{ ksf}$$

$$\frac{e}{b} = \frac{8.30}{35.0} = .238 \quad C = 2.60 \quad a = 17.5 - 8.3 = 9.2$$

$$5). FSOT = \frac{256170}{147380} = 1.74$$

$$\begin{array}{r} 5580 \times 7.4 = 41292 \\ 6081 \times 12.4 = 75404 \\ 3548 \times 2.5 = 8870 \\ \hline 15209 \end{array}$$

$$\bar{y} = \frac{19665}{15209} = -1.29$$

$$f_{soil} = 2.5 \times \frac{15209}{35 \times 19} = 13.9 \text{ ksf}$$

$$\frac{e_x}{e_b} = \frac{8.3}{35} = .239$$

$$\frac{e_1}{I} = \frac{1.29}{74.0} = .016$$

} K = 2.5


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVING CONDITIONS
OF STABILITY OF RIVER WALL
COMPUTED M.J. CHECKED P.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 10.74 PAGE 95 OF 95 PAGES

RIVER WALL MONOLITH #19

BACKFILLING RIVERSIDE UP TO EL 710.0'



	<u>SHEAR</u>	<u>ARM</u>	<u>MOMENT C "A"</u>
$HW2 = .73 \times \frac{11.6}{2} \times 28 = 1180^k$		3.88	460.0 ^{ik}
$HE1 = .96 \times 11.4 \times 28 = 307.0^k$		19.20	5900.0
$HE2 = .96 \times 11.6 \times 28 = 312.0^k$		5.80	1810.0
$HE3 = .15 \times 11.6 \times 28 = 48.8^k$		3.88	189.0
$\Sigma H = 785.8^k$			$\Sigma M = 8359.0^k$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>IMPROVING CONDITIONS</u>	PROJECT <u>LED #</u>
	<u>OF STABILITY @ RIVER WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>10.74</u> PAGE <u>96</u> OF <u>96</u> PAGES

RIVER WALL MONOLITH #19 (CONT'D)

BACKFILLING RIVERSIDE UP TO EL 710.0' (CONT'D)

$$\Sigma H = 2150 - 786 = 1364 \text{ k}$$

$$\Sigma M_A = 110280 - 39600 + 8360 - 21840 = 57200 \text{ k}$$

$$\Sigma V = 5059 \text{ k}$$

LOAD ON TIMBER PILES FROM AVERAGE HYDROSTATIC

LOCKSIDE LOAD

$$P = 51.10 \pm \frac{23800}{725} = 51.1 \pm 32.8$$

$$a = \frac{57.200}{5059} = 11.3' \quad c = 4.7'$$

$$M_d = 23800 \text{ k} \quad H = 1364 \text{ k}$$

$$P_{MAX} = 83.9 \text{ k}$$

$$P_{MIN} = 18.3 \text{ k} \quad H_p = \frac{1364}{99} = 13.8 \text{ k/ft}$$

SEE LOAD ON
TIMBER PILES
ON PAGE 96 &
WHERE STEEL
SHEET PILING
IS NEGLECTED

AREA LOADING FOR THE SAME CONDITION

$$1). \text{ RESULTANT INSIDE MIDDLE } \frac{10.61}{0.68} \text{ BY } \frac{0.14}{0.63}$$

$$2). f_{SOIL} = 12.20 \text{ KSF (MAX)} ; 0.20 \text{ KSF MIN}$$

$$3). \frac{\Sigma H}{\Sigma V} = \frac{1364}{5059} = .270 \quad (-.367)$$

$$4). FSS = \frac{5059 \times 55}{1364} = 2.04$$

$$5). FSOT = 118640 / 61440 = 1.93$$

$$\frac{32}{6} = 5.33$$

$$\frac{4.70}{.63}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVING CONDITIONS
OF STABILITY OF RIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800A
DATE 10.76 PAGE 97 OF 97 PAGES

RIVERWALL MONOLITH #19 (CONT'D)

BACKFILLING RIVERSIDE UP TO EL 71.00' (CONT'D)

LOAD ON TIMBER PILES FROM MAX. HYDROST. LOCKSIDE LOAD 11'

$$\Sigma H = 2150 - 786 = 1364^k$$

$$\Sigma V = 4530^k$$

$$M_A = 110,280 - 39,600 + 8360 - 33,150 = 45,900^k$$

$$e = \frac{45,900}{4530} = 10.13 \quad e = 5.87'$$

$$M_e = 26,600^k$$

PILE LOAD

$$P = 45.6 \pm \frac{26,600}{725} = 45.6 \pm 36.7$$

$$P_{MAX} = 82.3^k \quad P_{MIN} = 8.9^k$$

AREA LOADING

SEE PAGE 96 G
FOR TIMBER PILE
LOADS WHERE STEEL
SHEET PILING IS
NEGLECTED

$$1). \text{ RESULTANT OUTSIDE MIDDLE } \frac{1}{3} \text{ BY } 1.04'$$

$$2). f_{SOIL} = \frac{2}{3} \times \frac{4531}{10.13 \times 28.0} = \frac{10.70}{18.50^k/ft}$$

$$3). \frac{\Sigma H}{\Sigma V} = \frac{1364}{4531} = .302 (.367)$$

$$4). FSS = \frac{4531 \times .55}{1364} = 1.83$$

$$5). FSOT = 118,640 / 72,750 = 1.63$$

RIVER WALL MONOLITH NO 19
IMPROVE, NORMAL LOADING CONDITIONS FOR PILE LOADING
BACK FILL RIVERSIDE UP TO EL 710'

For 3' wall

$$\Sigma V = 5059 \times \frac{3}{28} = 542^k \downarrow \quad \begin{array}{l} I = 540 \text{ ft}^4 \\ S = 45 \text{ ft}^3 \end{array}$$

$$\Sigma M_c = 23,800 \times \frac{3}{20} = 2550^k \cdot l$$

$$E_H = 1364 \times \frac{3}{28} \quad 146^k \rightarrow P_H = 16^k$$

$$P_{\text{max}} = \frac{542}{9} + \frac{2550}{45} = 60 + 57 = \underline{\underline{117}} \text{ K}$$

$$P_{MIN.} = \dots \dots \dots 60 - 57 = \underline{3^k}$$

3' strip
of wall:

$$\epsilon_V = 4530 \times \frac{3}{28} = 486^{\text{K}}$$

$$\Sigma M_{\ell} = 26,600 \times \frac{3}{28} = 2850'K$$

$$\Sigma H = 1364 \frac{K}{20} \cdot \frac{3}{4} = 146^K \quad P_H = 16^K$$

$$P_{\text{May}} = \frac{486}{9} + \frac{2850}{45} = 54 + 63 = \underline{117^k}$$

$$P_{\text{MIU}} = \dots 54 - 63 = 9^k$$


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVING CONDITIONS
OF STABILITY OF RIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800 A
DATE 10.74 PAGE 99 OF PAGES

RIVER WALL GATE MONOLITH #20

ASSUME MONOLITHS #20 & #21 INTERCONNECTED



WEIGHT OF MONOLITH #21

$$\textcircled{1} \quad 24.0 \times 57.0 \times 23.0 \times .15 = 4750$$

$$\textcircled{2} \quad 4.0 \times 57.0 \times 23.0 \times .15 = 788$$

$$\textcircled{3} \quad 9.0 \times 4.0 \times 23.0 \times .087 = 72$$

$$\textcircled{4} \quad - 80.0 \times 23.0 \times .15 = -276$$

$$\hline 5334^k$$

ASSUMED PILING $9 \times 8 = 72 + 2 \times 8 = 88$ ^{ASS'D FOR SWT. PILING}

PILE LOADINGS MONOLITH #21 - EXISTING CONDITION

$$\text{UPLIFT LOAD } 32 \times 23.0 \times .73 = 538^k$$

$$\text{(5334 - 538) / 88} = 54.5^k/\text{PILE}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVING CONDITIONS
OF STABILITY OF RIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800 A
DATE 10.74 PAGE 100 OF 100 PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)
ASSUME MONOLITHS #20 & #21 INTERCONNECTED

$$\begin{array}{rcl}
 I_{xx} & = & 22 \times 3.0^2 = 198 \\
 & & 22 \times 6.0^2 = 792 \\
 & & 22 \times 9.0^2 = 1780 \\
 & & 22 \times 12.0^2 = 3190 \\
 & & 22 \times 15.0^2 = 4960 \\
 & & 22 \times 18.0^2 = 7130 \\
 & & 22 \times 21.0^2 = 9700 \\
 & & 22 \times 24.0^2 = 12700 \\
 & & \hline
 & & 40,440 \text{ FT}^4
 \end{array}$$

$$S_{xx} = \frac{40,440}{24} = 1680 \text{ FT}^3$$

$$\begin{array}{rcl}
 I_{yy} & = & 2 \times 17 \times 3.0^2 = 306 \\
 & & 2 \times 17 \times 6.0^2 = 1220 \\
 & & 2 \times 17 \times 9.0^2 = 2750 \\
 & & 2 \times 17 \times 12.0^2 = 4900 \\
 & & 2 \times 17 \times 14.5^2 = 7150 \\
 & & \hline
 & & 16,326
 \end{array}$$


$$S'_{yy} = \frac{16,326}{14.5} = 1133 \text{ C SHEET PILES}$$

$$S_{yy} = \frac{16,326}{12} = 1360 \text{ C TIMBER PILES}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>IMPROVING CONDITIONS</u>	PROJECT <u>LED #1</u>
	<u>DESTABILITY RIVER WALL</u>	FILE NO. <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>10.74</u> PAGE <u>102</u> OF <u>102</u> PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

ASSUME MONOLITHS #20 & 21 INTERCONNECTED (CONT'D)



CENTER GRAVITY OF LOADS

$$5645 \times 0 = 0$$

$$\frac{4796 \times 18.25}{10441} = \frac{88.700}{88.700}$$

$$y = \frac{88.700}{10441} = 8.39'$$

$$M_{xx} = 10.441 \times 4.13 = 43300 \text{ 'k}$$


$$P = \frac{10441}{137} \pm \frac{43300}{1680} \pm \frac{48550}{1360} = 55.83 \pm 25.80 \pm 11.94$$

MAX PILE LOAD $P = 117.3 \text{ k/PILE}$

MIN PILE LOAD $P = -57 \text{ k/PILE}$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY ANALYSIS</u>	PROJECT <u>LED #1</u>
	<u>C RIVER WALL</u>	FILE NO <u>800A</u>
	COMPUTED <u>M.T.</u> CHECKED <u>R.N.M.</u>	DATE <u>11.74</u> PAGE <u>102</u> OF <u>102</u> PAGES

RIVER WALL GATE MONOLITH #20 (ROUTED)
BACKFILLING RIVERSIDE UP TO EL 710.0'



H_{W2}	118.0^k	$+ 3.98 = 460.5^k$	$\left. \begin{array}{l} 19.20 = 5900.0' \\ 5.80 = 1810.0' \\ 3.88 = 131.0' \end{array} \right\} 8359.0^k$
H_{E1}	307.0^k		
H_{E2}	312.0^k		
H_{E3}	48.8^k		
$\left. \begin{array}{l} 667.8^k \\ \sim 668 \end{array} \right\}$			

$$E1 \quad 4.6 \times 30.4 / 2 \times 22.8 \times 11.6 = 228 \times 14.47 = 3300.1^k$$

$$\Sigma M_{y2} = 8359.0 - 3300 = 5060^k$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY ANALYSTS</u>	PROJECT <u>LEO #1</u>
	<u>C RIVER WALL</u>	FILE NO <u>800A</u>
	COMPUTED <u>M.J.</u> CHECKED <u>R.N.M.</u>	DATE <u>11.74</u> PAGE <u>108</u> OF <u>108</u> PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

BACKFILLING RIVERSIDE UP TO FL 710.0' (LOCKSIDE AVERAGE)

$$\Sigma M_{yy} = 5060 - 73 \times 5.8 \times 28 \times 3.87 - 117 \times 1.4 \times 28 \times 12.5 - 117 \times 11.6 \times 28 \times 5.8$$

$$\Sigma M_{yy} = 48550 - 4130 = 44420 \text{ k} \quad - 151 \times 11.6 \times 28 \times 3.9 = 5060 - 930 = 4130 \text{ k}$$

$$\Sigma M_{xx} = 40.820 \text{ k}$$

$$\Sigma V = 5645 + 228 = 5873 \text{ k}$$

$$\Sigma H_x = 2684 \text{ k}$$

$$\Sigma H = \sqrt{2684^2 + 2050^2} = 3380 \text{ k}$$

PILE LOADING

$$P = 5873/99 \pm \frac{40820}{495} + \frac{44420}{600} = 59.4 + 82.4 = 73.8$$

$$\text{MAX } P = 215.6 \text{ k}$$

$$\text{MIN } P = -96.8 \text{ k}$$

FOR PILE LOADS
WITHOUT SHEET
PILING, Pp 1034; 105

AREA LOADING FOR THE SAME CONDITION

$$q_y = \frac{40820}{5873} = 6.95 \quad q_x = \frac{44420}{5873} = 7.55$$

$$\frac{6.95}{28.0} = .25 \quad \frac{7.55}{29.0} = .26 \quad A = 29 \times 28 = 812 \text{ ft}^2$$

$$L = 6.30$$

$$f_{\text{soil}} = 6.30 \times \frac{5873}{812} = 45.50 \text{ ksf}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RIVER WALL - TAKING</u>	PROJECT <u>LED #1</u>
	<u>W. E. LOAN</u>	FILE NO. <u>800A</u>
	COMPUTED <u>JL</u> CHECKED <u>R.N.M.</u>	DATE <u>3/75</u> PAGE <u>103a</u> OF <u> </u> PAGES

RIVER WALL GATE MONUMENT #20

RAVERSIDE BACKFILLED UP TO E1.710

"LOCKSIDE AVERAGE" (REF. p. 103)

$$\Sigma V = 5873^k$$

$$\Sigma M_{xx} = 40820^k \quad \Sigma M_{yy} = 44420^k$$

$$\Sigma H_x = 2684^k \quad \Sigma H_y = 2050^k \quad \Sigma I_k = 3320^k$$

$$P_V = \frac{5873}{81} \pm \frac{40820 \cdot 10}{4860} \pm \frac{44420 \cdot 12}{4860} =$$

$$= 72 \pm 101 \pm 110 = \begin{cases} 283^k & \text{max} \\ -134^k & \text{min} \end{cases}$$

$$P_H = \frac{2684}{81} \pm \frac{22^k}{18} = P_{Hx} = 33 \pm 1.2$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVED CONDITION
OF STABILITY OF RIVER WALL
COMPUTED M.T. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800A
DATE 11.74 PAGE 104 OF 104 PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)

BACKFILLING RIVERSIDE UP TO EL 710.0'

SUMMARY OF RESULTS FOR AREA LOADING

1). $f = 45.50 \text{ KSF}$

2). $R = 6500 \text{ K}$

3). $\frac{\Sigma H_x}{\Sigma V} = \frac{2684}{5873} = 0.44$

4). $FSS_x = \frac{5873 \times .55}{2684} = 1.20$ $FSS_R = \frac{5873 \times .55}{3380} = 0.96$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RIVER WALL STABILITY</u>	PROJECT <u>LRD #1</u>
	<u>PILE LOAD</u>	FILE NO. <u>802A</u>
	COMPUTED <u>JL</u>	CHECKED <u>R.N.M.</u>
		DATE <u>3/75</u> PAGE <u>105</u> OF <u> </u> PAGES

RIVER WALL GATE MONOLITH #20
RIVERSIDE BACK FILLED UP TO EL. 710.3'

"LOCKSIDE MAXIMUM" (REF. P. 106)

$$\Sigma V = 5610^k$$

$$\Sigma M_x = 42690^k \quad \Sigma M_y = 45840^k$$

$$\Sigma H_x = 2684^k \quad \Sigma H_y = 2050^k \quad \Sigma H_R = 3380^k$$

$$P_V = \frac{5610}{81} \pm \frac{42690 \times 12.2}{1860} \pm \frac{45840 \times 12.2}{1860} =$$

$$= 69 \pm 105 \pm 113 = \begin{cases} 287^k & \text{max} \\ -149^k & \text{min} \end{cases}$$

$$P_{H_x} = \frac{2684}{81} = 22^k \text{ L.F.} \quad P_{H_R} = \frac{3380}{81} = 42^k \text{ R.F.}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVED CONDITIONS
OF STABILITY CRIB WALL
COMPUTED M.T. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800 A
DATE 1.75 PAGE 106 OF PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)
BACKFILLING RIVERSIDE UP TO EL 710.0 / (CRIB SIDE MAXIMUM)

$$\Sigma V = 5380 + 228 = 5610^k$$

$$\Sigma H_x = 2684^k \quad \Sigma H_y = 2050^k \quad \Sigma H = 3380^k$$

$$\Sigma M_{xx} = 42,690^k$$

$$\Sigma M_{yy} = 49,970 - 4130 = 45,840^k$$

$$FSS_x = \frac{5610 \times .55}{2684} = 1.15 \quad FSS_y = \frac{5610 \times .55}{3380} = 0.92$$

$$e_y = \frac{42690}{5610} = 7.6'$$

$$e_x = \frac{45840}{5610} = 8.18'$$

$$e_y/b = 7.6/28.0 = .272$$

$$e_x/d = 8.18/29.0 = .282$$

$$K = 7.6$$

$$f_{soil} = 7.6 \frac{5610}{912} = 52.4 \text{ ksf}$$

INTERCONNECTION OF RIVERWALL MONOLITHS 20, 19 & 21

NO BACKFILL BEHIND
WALLS


REFERENCES

Pg 55 MON #19.

63 MON # 20

-107 MON # 21

$$I_A = \frac{32(79)^3}{12} = 1,315,000$$



V	ARM _x	M _y	ARM _y	M _x
5059	x 5.84	29500	- 25.5	- 129,000
5645	x 8.62	48700	+ 9.75	+ 55,000
4796	x 0	0	+ 28.0	+ 134,300
<u>R = 15500</u>	<u>5.04'</u>	<u>78200</u>	<u>3.89'</u>	<u>60300</u>
e_x	ΣM_y		e_y	ΣM_x

COMPUTE FOUNDATION PRESSURE AT POINTS 1, 2, 3, 4, 5 AND 6, ASSUMING NO TRANSFER OF VERTICAL LOAD BETWEEN MONOLITHS:

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RIVER WALL STABILITY</u>	PROJECT <u>LE D #1</u>
	FOUNDATION PRESSURES & SLIDING	FILE NO <u>800 A</u>
	COMPUTED <u>E. N. M.</u>	DATE <u>4/75</u> PAGE <u>1066</u> OF <u> </u> PAGES
	CHECKED <u>✓</u>	

INTERCONNECTION OF 20, 19 & 21 (CONT'D) — NO BACKFILLING.

"LOCK SIDE AVERAGE" UPLIFT

$$f_{①} = \frac{5059}{896} + \frac{60,300(-39.5)}{1,315,000} + \frac{78,200(-16.0)}{215,700}$$

$$f_{①} = 5.65 - 1.81 - 5.82$$

$$f_{①} = \underline{-1.98 \text{ KSF}}$$

$$f_{②} = \frac{5059}{896} + \frac{60,300(-11.5)}{1,315,000} + 5.82$$

$$f_{②} = 5.65 - 0.53 + 5.82$$

$$f_{②} = \underline{10.94 \text{ KSF}}$$

$$f_{③} = \frac{5645}{896} + \frac{60,300(16.5)}{1,315,000} + 5.82$$

$$f_{③} = \underline{12.88 \text{ KSF}}$$

$$f_{④} = \frac{4796}{736} + 1.81 + 5.82 = \underline{14.15 \text{ KSF}}$$

$$f_{⑤} = 6.52 + 0.76 - 5.82 = \underline{1.46 \text{ KSF}}$$

$$f_{⑥} = 6.30 - 0.53 - 5.82 = \underline{-0.05^* \text{ KSF}}$$

$$\frac{25.5}{14.0}$$

$$39.5 = -Y_1$$

$$\frac{28.0}{11.5} = -Y_2 = -Y_6$$

$$\frac{28.0}{16.5} = Y_3 = Y_5$$

$$\frac{23}{39.5} = Y_4$$

$$X_2 = X_3 = X_4 = 16'$$

$$X_1 = X_5 = X_6 = -16'$$

* THE TENSION PRESSURES ARE NOT CRITICAL & THEREFORE FURTHER REFINEMENT IS NOT REQUIRED

	FOUNDATION PRESSURE, KSF	
	f_{max}	f_{min}
MON. # 19	10.94	-1.98*
MON # 20	12.88	-0.05*
MON # 21	14.15 ←	1.46

RESULTANT IS OUTSIDE OF KERN

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RIVER WALL STABILITY
FOUNDATION PRESSURE
COMPUTED R.N.M. CHECKED JL

PROJECT L&D #1
FILE NO. 800 A
DATE 4/75 PAGE 106C OF PAGES

INTER CONNECTION OF RIVER WALL MONOLITHS 210, 18 & 21

' LOCKSIDE MAXIMUM " UPLIFT

NO BACKFILLING

$$I_x = 1,315,000$$

$$I_y = 215,700$$

$$4531 \times 7.14 = 32351$$

$$5380 \times 9.29 = 49980$$

$$4796 \times 0 = 0$$

$$14707 \times 5.60 = 82331 \text{ (K)}$$

$$EN = \frac{e^x}{EM^3}$$

$$4531 \times -25.5 = -115540$$

$$5380 \times 10.45 = +56221$$

$$4796 \times 28.0 = +134288$$

$$14707 \times 5.10 = +74969$$

$$EN = \frac{e^x}{EM^3}$$

$$\frac{M_x}{I_x} = \frac{74969}{1315000} = 0.0570; \frac{M_y}{I_y} = \frac{82331}{215700} = 0.3816$$

$$\frac{4531}{896} = 5.06 \quad \frac{5380}{896} = 6.00$$

$$\frac{4796}{736} = 6.52$$

$$f_1 = 5.06 + 0.0570(-39.5) + 0.3816(-16) = -3.30 \text{ KSF}$$


$$f_2 = 5.06 + 0.0570(-11.5) + 0.3816(16) = +10.51 \text{ KSF}$$

$$f_3 = 6.00 + 0.0570(16.5) + 0.3816(16) = 13.05 \text{ KSF}$$

$$f_4 = 6.00 + 0.0570(11.5) + 0.3816(-16) = -0.77 \text{ KSF}$$

$$f_5 = 6.52 + 0.0570(39.5) + 0.3816(16) = 14.88 \text{ KSF}$$

$$f_6 = 6.52 + 0.0570(16.5) + 0.3816(-16) = 1.35 \text{ KSF}$$



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RIVER WALL STABILITY</u>	PROJECT <u>L & D # 1</u>
	<u>FOUNDATION PRESSURES & SLIDING</u>	FILE NO <u>800A</u>
	COMPUTED <u>E.N.M.</u> CHECKED <u>✓</u>	DATE <u>4/75</u> PAGE <u>1060</u> OF <u> </u> PAGES

INTERCONNECTION OF 20, 19 & 21 -- NO BACKFILL (CONT'D)"LOCKSIDE MAX." UPLIFT

	FOUNDATION PRESSURES, KSF	
	f MAX	f MIN
MONOLITH #19	10.51	-3.30 ← +
MONOLITH #20	13.05	-0.77 +
MONOLITH #21	14.88 ←	1.85

SLIDING FOR MONOLITHS 20 & 21"LOCKSIDE AVERAGE" UPLIFT

$$\Sigma V_{20+21} = 5645 + 4796 = \underline{10441}^K$$

$$\Sigma H_x = 1000 + 2470 = 3470^K$$

$$\Sigma H_y = \quad \quad \quad = 2050^K$$

$$\Sigma H_R = \underline{4030}^K \quad \checkmark \quad (\text{HORIZONTAL RESULTANT})$$

$$\text{SLIDING FACTOR} = \frac{4030}{10441} = .386 \quad \text{F.S.S.} = \underline{1.42} < 1.5$$

"LOCKSIDE MAX." UPLIFT

$$\Sigma V_{20+21} = 5380 + 4796 = 10176^K$$

$$\Sigma H_R = \quad \quad \quad = 4030^K \quad \checkmark$$

$$\text{SLIDING FACTOR} = \frac{4030}{10176} = .396 \quad \text{F.S.S.} = \underline{1.39} < 1.5$$

* THE TENSION PRESSURES ARE NOT CRITICAL
 ∴ FURTHER REFINEMENT IS NOT REQUIRED.

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RIVERWALL STABILITY
HORIZONTAL PILE LOAD
COMPUTED P.N.M. CHECKED JJ

PROJECT L & D #1
FILE NO 800 A
DATED 4/75 PAGE 106 OF 106 PAGES

INTERCONNECTION OF RIVERWALL MONOLITHS 20, 19 & 21

"LOCKSIDE MAX." & "LOCKSIDE AVE" UPLIFTS

$$\begin{array}{r} 2032 \times 24.5 = 49784 \quad + \\ 1000 \times 3.5 = 3500 \quad + \\ \hline 53284'k? \end{array}$$

$$\begin{array}{r} 2470 \times (-3.5) = -8645 \quad - \\ 2050 \times (-16) = -32800 \quad - \\ \hline 41445'k \end{array}$$

$$\begin{array}{l} \Sigma M_H = 11839'k \quad \curvearrowright \\ \Sigma H_X = 5502'k \quad H_X = \frac{5502}{245} = 22.45 \\ \Sigma H_Y = 2050'k \quad H_Y = \frac{2050}{225} = 9.11 \end{array}$$

$$J = I_X + I_Y = 118,800$$

$$r = 37.95'ft$$

$$H_P = \frac{\Sigma M_H (r)}{J} = \frac{11839 (37.95)}{118,800} = 3.78$$


$$H_P (X \text{ COMPONENT}) = 3.78 \times \frac{36}{37.9} = 3.59$$

$$H_P (Y \text{ COMPONENT}) = 3.78 \times \frac{12}{37.9} = 1.20$$

$$\begin{array}{r} 3.59 + 22.45 = 26.04 \approx 26 \\ 1.20 + 9.11 = 10.31 \approx 10 \end{array} \quad \left\{ \begin{array}{l} P_H = 30'k \\ H_{(MAX)} \end{array} \right.$$

$$\frac{49.5}{2} \times 0.0625 \times 28 = 2150'F \rightarrow$$

$$\frac{11.6}{2} \times 0.0625 \times 28 = \frac{118}{2032'k} \leftarrow \frac{1}{2} = 1016 \approx 1000'k \leftarrow$$



HARZA
ENGINEERING
COMPANY
CHICAGOSUBJECT RIVER WALL STABILITY
PILE LOADS
COMPUTED R. H. M. CHECKED JJPROJECT L & D #1
FILE NO. 800 A
DATE 4/175 PAGE 106 OF 106 PAGESINTERCONNECTION OF MONOLITHS 19, 20 & 21 — NO BACKFILL"LOCKSIDE AVERAGE" UPLIFT

ASSUME NO TRANSFER OF VERTICAL LOAD BETWEEN MONOLITHS

$$\Sigma M_Y = \underline{78,200'K} \quad (\text{Fr. Foundation pressure})$$

$$\begin{array}{rcl}
 5059 & \times & 24.5 = 123945 \\
 5645 & \times & -10.75 = -60684 \\
 4796 & \times & -24.0 = -139084 \\
 \hline
 15500 & & \bar{Y} = 4.89 \quad \Sigma M_Y = 75823
 \end{array}$$

$$\bar{X} = \frac{78200}{15500} = 5.05'$$

$$I_X = 105,300 \quad I_Y = 13,500$$

$$\frac{M_X}{I_X} = 0.72$$

$$\frac{M_Y}{I_Y} = 5.79$$

$$\begin{array}{rcl}
 \frac{5059}{81} = 62^K & \frac{5645}{81} = 70^K & \frac{4796}{63} = 76^K
 \end{array}$$

$$\begin{aligned}
 P_1 &= 62 + .78(-36) + 5.79(-12) \\
 &= 62 - 27 - 69 \\
 &= -34^K
 \end{aligned}$$

$$P_2 = 62 + .78(-12) + 69 = 122^K$$

$$P_3 = 70 + .78(-9) - 69 = -6^K$$


$$P_4 = 70 + .78(15) + 69 = 150^K$$

$$P_5 = 76 + .78(+18) - 69 = 20^K$$

$$P_6 = 76 + .78(36) + 69 = 172^K$$

P MAX M MIN

MONOLITH #	T9	122 ^K	-34 ^K
20		150 ^K	-6 ^K
21		172	20 ^K



HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RIVERWALL STABILITY</u>	PROJECT <u>L & D #1</u>
	<u>PILE LOADS</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>J1</u>	DATE <u>4/75</u> PAGE <u>106</u> PAGES

INTERCONNECTION OF MONOLITHS 19, 20 & 21 - NO BACKFILL

" LOCKSIDE MAXIMUM" UPLIFT

NO TRANSFER OF VERTICAL LOAD BETWEEN MONOLITHS

$$4531 \times 24.5 = 111,000 \quad \bar{x} = \frac{M_y}{15500} = 5.31'$$

$$5380 \times 11.45 = 61,601$$

$$4796 \times 2.9 = 13,908.4$$

$$15500 \times 5.79 = 89,685$$

$$\frac{M_x}{I_y} = 0.85$$

$$\frac{M_y}{I_x} = 6.10$$

24'

$$\frac{4531}{81} = 56^k$$

$$\frac{5380}{81} = 66^k$$

$$\frac{4796}{63} = 76^k$$

MONOLITH # 19

$$P_{MIN} = P_1 = 56 + (.85)(-36) + 6.10(12) = 56 - 30 - 73 = -47^k$$

$$P_{MAX} = P_2 = 56 + (.85)(12) + 73 = 119^k$$

MONOLITH # 20


$$P_{MIN} = P_3 = 66 + (.85)(-9) - 73 = -14^k$$

$$P_{MAX} = P_4 = 66 + .85(15) + 73 = 151^k$$

MONOLITH # 21

$$P_{MIN} = P_5 = 76 + (.85)(18) - 73 = 18^k$$

$$P_{MAX} = P_6 = 76 + 30 + 73 = 179^k$$




HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVED CONDITIONS
DESTABILITY C RIVER WALL
COMPUTED M.J. CHECKED _____

PROJECT LED #1
FILE NO. 800A
DATE 1.7.5 PAGE 107 OF _____ PAGES

RIVER WALL GATE MONOLITH #20 (CONT'D)
INTERCONNECTION OF MONOLITHS #19, 20 & 21 & BACKFILLING



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT IMPROVED CONDITIONS
OF STABILITY OF RIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO 800A
DATE 1.75 PAGE 108 OF PAGES

RIVER WALL GATE MONOLITH #20 (LOADED)
INTERCONNECTION OF MONO'S #19, 20, 21 & BACK FILLING

LOCKSIDE AVERAGE

$$5059 \quad 23,800$$

$$5873 \quad 44,420$$

$$X = \frac{68220}{15.725} = 4.33 \quad \text{e}_x$$

$$\frac{4796}{15.728 \text{ k}} \quad \frac{0.0}{68,220}$$

$$\frac{5059}{812} \pm \frac{5059 \times 4.33}{3940} = 6.3 \pm 5.6$$

$$FSS = \frac{(5873 + 4796) \times 55}{8380} = 1.74$$

$$S = \frac{28 \times 21^2}{6} = 3940 \text{ ft}^3$$

$$\int_{SOIL} = \frac{5873}{912} \pm \frac{5873 \times 4.33}{3940} = 7.2 \pm 6.5 \quad \begin{cases} \text{MAX } 13.7 \text{ ksf} \\ \text{MIN } 0.7 \text{ ksf} \end{cases}$$

LOCKSIDE MAXIMUM

$$4530 \quad 26,600 \text{ lb}$$

$$5610 \quad 45,840 \text{ lb}$$

$$X = \frac{72,440}{14936} = 4.84 \quad \text{e}_x$$

$$\frac{4796}{14936} \quad \frac{0.0}{72,440 \text{ lb}}$$

$$FSS = \frac{5610 + 4796}{3380} \times 55 = 1.70$$

$$\frac{4530}{812} \pm \frac{4530 \times 4.84}{3940} = 5.58 \pm 5.56$$

$$\int_{SOIL} = \frac{5610}{812} \pm \frac{5610 \times 4.84}{3940} = 6.9 \pm 6.9 \quad \begin{cases} \text{MAX } 13.8 \text{ ksf} \\ \text{MIN } 0.0 \text{ ksf} \end{cases}$$


(NEXT Pp 103a TO 108 e)

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT PIER WALL STABILITY
PILE LOAD
COMPUTED JL CHECKED R.M.M.

PROJECT LED #1
FILE NO. 800A
DATE 3/75 PAGE 108a OF 108a PAGES

PIER WALL METHOD: #19, #20 & #21 INTERCONNECTED
RIVER SIDE BACKFILLED UP TO EL. 710.0'



$$I_x = 2 \cdot 9 \cdot 26.5^2$$

$$+ 2 \cdot 9 \cdot 22.5^2$$

$$+ 2 \cdot 9 \cdot 20.5^2$$

$$+ 2 \cdot 9 \cdot 21.5^2$$

$$+ 2 \cdot 9 \cdot 24.5^2$$

$$+ 2 \cdot 9 \cdot 21.5^2$$

$$+ 18 \cdot 15^2$$

$$+ 18 \cdot 12^2$$

$$+ 9 \cdot 9^2$$

$$+ 9 \cdot 6^2$$

$$+ 9 \cdot 3^2$$

$$= 105300 \text{ pile}^2$$

$$I_y = 2 \cdot 9 \cdot 12.5^2$$

$$+ 2 \cdot 9 \cdot 10.5^2$$

$$+ 2 \cdot 9 \cdot 8.5^2$$

$$+ 2 \cdot 9 \cdot 6.5^2$$

$$+ 2 \cdot 9 \cdot 4.5^2$$

$$+ 2 \cdot 9 \cdot 2.5^2$$

$$+ 18 \cdot 1.5^2$$

$$+ 18 \cdot 0.5^2$$

$$+ 9 \cdot 0.5^2$$

$$= 12500 \text{ pile}^2$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>PIER WALL STABILITY</u>	PROJECT <u>LAD #1</u>
	<u>PILE LOAD</u>	FILE NO. <u>500A</u>
	COMPUTED <u>JL</u>	CHECKED <u>R.N.M.</u>
	DATE <u>3/75</u> PAGE <u>108b</u> OF <u> </u> PAGES	

PIER WALL MONOLITHS #19, #20 & #21 INTERCONNECTED
RIVERSIDE BACKFILLED UP TO EL. 710.0

"LOCKSIDE APPROX." (REF. P. 96, 103 & 107)

w/d per: p.m.s.

RESULTS

VERTICAL:

$$\begin{aligned}
 5059 \times 4.70 &= 23777 \\
 5873 \times 7.5 &= 44047.5 \\
 5024 \times (-9.2) &= -46220.8 \\
 \hline
 15956 &= 62196
 \end{aligned}$$

$$\bar{X} = \frac{62196}{15956} = 3.90'$$

$$\begin{aligned}
 5059 \times 24.5 &= 124045.5 \\
 5873 \times (-16.0) &= -93968 \\
 5024 \times (-24.0) &= -120576 \\
 \hline
 15956 &= -82100
 \end{aligned}$$


$$\bar{Y} = \frac{-82100}{15956} = -5.14'$$

HORIZONTAL:

$$\begin{aligned}
 +1364 \times 24.5 &= +33418 \\
 +1000 \times 3.5 &= +3500 \\
 (2470 - 2050) \times (-16.0) &= -6800 \\
 -549 \times (-24.0) &= +13176 \\
 \hline
 3617 &= 32194
 \end{aligned}$$

$$2050 \times (-16.0) = -32800$$

$$\Sigma M_H = +13732 \text{ (cc)}$$



$$668 \times \frac{23.0}{28.0} = 549k$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RIVER WALL STABILITY
PILE LOAD
COMPUTED JL CHECKED RNM

PROJECT RD #1
FILE NO 800A
DATE 3/75 PAGE 108 OF 108 PAGES

RIVER WALL MONOLITHS #19, #20 & #21 INTERCONNECTED
RIVERSIDE BACK FILLED UP TO EL. 710.0

"LOCKSIDE AVERAGE" (CONT'D)

$$\Sigma V = 15956^k$$


$$\Sigma M_x = 83124^k \quad \Sigma M_y = 63496^k$$

$$\Sigma H_x = 3380^k \quad \Sigma H_y = 2050^k \quad \Sigma M_H = 13732^k (\circ)$$

$$A P_V = \frac{5024}{9 \times 7} + \frac{83124 \times 36.0}{105300} + \frac{63496 \times 12.0}{13500} = 80 + 28 + 56 = 164^k$$

$$B P_V = \frac{5059}{9 \times 9} - \frac{83124 \times 36.0}{105300} - \frac{63496 \times 12.0}{13500} = 62 - 28 - 56 = -22^k$$

ASSUMING THAT ALL HORIZONTAL
LOADS ARE TAKEN BY PILES
(NO PASSIVE SOIL PRESSURE)



$$r = \sqrt{12.0^2 + 26.0^2} = 27.95'$$

$$I_p = I_x + I_y = 165450 + 135000 = 118850$$

$$P_{Hx} = \frac{3617}{27.95} = 16.07^k \quad P_{Hy} = \frac{2050}{27.95} = 73.3^k$$

$$P_r = \frac{13732}{27.95} = 4.38^k$$

$$P_{rx} = 4.38 \frac{12.0}{27.95} = 1.38^k$$

$$P_{ry} = 4.38 \frac{26.0}{27.95} = 4.15^k$$

$$\max P_H = \sqrt{(P_{Hx} + P_{rx})^2 + (P_{Hy} + P_{ry})^2} = \sqrt{(16.07 + 1.38)^2 + (73.3 + 4.15)^2} = 78.5^k$$

$$\min P_H = 14.21^k$$

$$\text{AVE. } P_H = 18.50^k$$

$$= 22.78^k$$


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RIVER WALL STABILITY
PILE LOAD
COMPUTED JJ CHECKED R.N.M.

PROJECT L&D #1
FILE NO. 800A
DATE 3/75 PAGE 108d OF PAGES

RIVER WALL MONOLITHS #19, #20 & #21 INTERCONNECTED.
RIVERSIDE BACKFILLED UP TO EL. 710.0'

"LOCAL SIDE MAXIMUM" (DIFF. P. 97, 106 & 107)



RESULTANTS

VERTICAL:

$$\begin{aligned} 4530 \times 5.87 &= 26571 \\ 5610 \times 8.18 &= 45896 \\ 5024 \times (-.92) &= -4622 \\ \hline 15164 &= 67854 \end{aligned}$$

$$\bar{X} = \frac{67854}{15164} = 4.42'$$

$$\begin{aligned} 15164 \times 24.5 &= 371538 \\ 5610 \times (-11.10) &= -62271 \\ 5024 \times (-26.5) &= -133136 \\ \hline 15164 &= -96982 \end{aligned}$$

$$\bar{Y} = \frac{-96982}{15164} = -6.40'$$

11.04 (20.11) 1962

SAINT ANGELO, TEXAS

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT EXISTING CONDITION
OF STABILITY OF RIVER WALL
COMPUTED M.J. CHECKED R.N.M.

PROJECT LED #1
FILE NO. 800 A
DATE 1.75 PAGE 109 OF PAGES

PILE BEARING CAPACITY

ULTIMATE BEARING CAPACITY (EM 1110-2-2906)

$$Q_u' = A_t \sqrt{2} D_2 N_q + 2 A_f K D_2^2 \sqrt{2} \tan \delta$$

$$A_t = .785 \times .83^2 = .558 \text{ ft}^2$$

$$\sqrt{2} = .034 \text{ ton/lin ft} \quad \text{PILE LENGTH ASS'D 13'}$$

$$D_2 = 13'; \quad N_q = 20$$

$$A_f = \pi \times .83 = 2.6 \text{ ft}^2$$

$$K = 1.50$$

$$\tan \delta = \tan 33^\circ = .65$$

$$Q_u' = .558 \times .034 \times 13 \times 20 + 1.3 \times 1.50 \times 169 \times .034 \times .65$$

$$Q_u' = 4.9 + 7.3 = \underline{12.2 \text{ ton/pile}}$$

ASSUMING FS = 3

$$Q = 12.2 / 3 = 4.0 \text{ ton/pile}$$

PILE BEARING CAPACITY Q = 4.0 ton/pile

HARZA
ENGINEERING
COMPANY
CHICAGOSUBJECT STABILITY ANALYSIS
OF DAM - LOADING CONDITIONS
COMPUTED R.N.M. CHECKED JJPROJECT LOCK & DAM #1
FILE NO. 800 A
DATE JAN '75 PAGE 110 OF PAGESLOADING CONDITIONS - THE FOLLOWING ARE ASSUMPTIONS

AND OTHER GIVEN DATA USED IN THE ANALYSES OF VARIOUS LOADING CONDITIONS. IN ALL CASES, THE HORIZONTAL PILE LOAD OF 4 K PER PILE AND FRICTIONAL RESISTANCE OF 40 K APRON DUE TO ITS SUBMERGED WEIGHT ARE ASSUMED TO RESIST HORIZONTAL FORCES.

I NORMAL OPERATING CONDITION

1. UPSTREAM WATER SURFACE EL. 723.2
2. EXISTING SAND FILL IN DAM
3. UPSTREAM SEDIMENT EL 710 ±
4. TAILWATER ELEVATION 690.6'
5. ICE PRESSURE 10 KIPS PER FOOT OF CREST HORIZONTAL AT ELEVATION 723.2'
6. TENDENCY OF MONOUM TO SLIDE TAKEN ALONG CRITICAL PLANE FROM BOTTOM OF CUT-OFF WALL, EL 684.6 TO EL. 690.6 AT THE TOE. (FOR ALL LOADING CONDITIONS)

II FLOOD DISCHARGE CONDITIONA. 1965 FLOOD EXISTING CONDITION

1. MAX. UPSTREAM W.S. EL 734.7
TAIL WATER AND LOWER POOL EL 719.
2. SPACE INSIDE OF DAM FILLED WITH WATER
3. UPLIFT DETERMINED BY FLOW NET METHOD.

B. 1951 FLOOD EXISTING CONDITION

1. MAX. UPSTREAM W.S. EL. 731
TAILWATER EL. 695.5 (BEFORE HYDRAULIC JUMP)
LOWER POOL EL. 709.0
2. UPLIFT DETERMINED BY FLOW NET METHOD.
3. WATER INSIDE DAM SAME LEVEL AS RELIEF HOLE OUTLETS (EL 697.4 ±)

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY ANALYSIS</u>	PROJECT <u>LOCKE DAM #1</u>
	<u>OF DAM - LOADING CONDITION</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>dl</u>	DATE <u>JAN '75</u> PAGE <u>III</u> OF <u> </u> PAGES

LOADING CONDITIONS (CONT'D)

III EARTHQUAKE CONDITION

1. EARTHQUAKE INERTIA FORCES AND HYDRO-DYNAMIC FORCES ADDED TO AND ICE PRESSURE REMOVED FROM NORMAL OPERATING CONDITION.
- 2 EARTHQUAKE ACCELERATION ASSUMED TOWARD UPSTREAM DIRECTION I.E., FORCES ARE OPPOSITE (TOWARD DOWNSTREAM DIRECTION).

$$\frac{a}{g} = 0.1$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY ANALYSIS</u>	PROJECT <u>LOCK & DAM #1</u>
	OF <u>DAM - IMPROVED CONDITION</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>B.N.M.</u> CHECKED <u>JL</u>	DATE <u>JAN '75</u> PAGE <u>112</u> OF <u> </u> PAGES

LOADING CONDITION

1951 FLOOD IMPROVED CONDITION


1. MAXIMUM UPSTREAM W.S. EL 731
TAILWATER EL. 695.5
LOWER POOL EL 709.
2. UPLIFT DETERMINED BY FLOW NET METHOD
3. WATER IN CAVITY OF DAM SAME LEVEL
AS RELIEF HOLE OUTLETS (EL. 697.4 ±)
4. FOR STABILIZATION BY INCREASING THE HEIGHT
OF EXISTING SAND FILL, A SLIDING SAFETY
FACTOR OF 1.5 WAS SET FOR THE FORCE
OF FRICTION TO EQUALIZE THE COMBINED
TANGENTIAL COMPONENTS OF $S.V.$ & $S.H.$ FORCES
ON AN INCLINED SLIDING PLANE, AND THE
REQUIRED HEIGHT OF ADDITIONAL SAND FILL DETERMINED.

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RESULTS OF BUTTRESS
DAM STABILITY ANALYSIS
COMPUTED R.N.M. CHECKED JL

PROJECT LOCK & DAM #1
FILE NO. 800 A
DATE JAN '75 PAGE 113 OF PAGES

I NORMAL OPERATING CONDITION (EXISTING)



1. BEARING PRESSURES $f_A = \frac{2.53}{2.24} \text{ KSF}$
 $f_B = 1.08^2 \text{ KSF}$

2. RESULTANT WITHIN MIDDLE $\frac{1}{3}$, $e = \frac{4.32}{4.68}$


3. SLIDING FACTOR, $\frac{R_T}{R_H} = 0.279$

4. "SLIDING SAFETY FACTOR", $\underline{\underline{SSF}} = 2.33$
(f = 0.649)

II FLOOD DISCHARGE CONDITION

A. 1965 FLOOD EXISTING CONDITION

734.7




1. BEARING PRESSURES: $f_A = \frac{1.36 \text{ KSF}}{1.15} = 1.18 \text{ KSF}$
 $f_G = \frac{1.13}{1.12} \text{ KSF}$
2. RESULTANT WITHIN MIDDLE $\frac{1}{3}$; $e = \frac{0.96}{0.32}$
3. SLIDING FACTOR, $\frac{R_T}{R_N} = 0.217$
4. SLIDING SAFETY FACTOR, SSF 2.98
 $(f = 0.649)$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>RESULTS OF BUTTRESS</u>	PROJECT <u>LOCK & DAM No. 1</u>
	<u>DAM STABILITY ANALYSIS</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>J1</u>	DATE <u>JAN '75</u> PAGE <u>115</u> OF <u> </u> PAGES

II FLOOD DISCHARGE CONDITION

B. 195' FLOOD EXISTING CONDITION

731.-



1. BEARING PRESSURES:
- | | |
|---------|-------------------------|
| $f_A =$ | $\frac{1.47}{1.27}$ KSF |
| $f_B =$ | $\frac{1.47}{1.27}$ KSF |

2. RESULTANT WITHIN MIDDLE $\frac{1}{3}$ $e = \frac{0.72}{1.27}$

3. SLIDING FACTOR $\frac{R_T}{R_N} = 0.439$

4. SLIDING SAFETY FACTOR, SSF = 1.48
($f = 0.649$)


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RESULTS OF BUTTRESS
DAM STABILITY ANALYSIS
COMPUTED R.N.M. CHECKED JL

PROJECT LOCKE DAM #1
FILE NO. 800 A
DATE JAN. '75 PAGE 111 OF 111 PAGES

III EARTHQUAKE CONDITION

(EXISTING)



1. BEARING PRESSURES $f_A = \frac{2.27}{2.08} \text{ KSF}$
 $f_B = 1.28 \text{ KSF}$
2. RESULTANT WITHIN MIDDLE $\frac{1}{3}$, $e = \frac{2.81'}{2.44'}$
3. SLIDING FACTOR, $\frac{R_T}{R_N} = .03/9$
4. SLIDING SAFETY FACTOR, $\underline{\underline{SSF = 2.03}}$
($f = 0.649$)


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT RESULTS OF BUTTRESS
DAM STABILITY ANALYSIS
COMPUTED E. N. M. CHECKED J

PROJECT LOCK & DAM #1
FILE NO. 800A
DATE 4/75 PAGE 117 OF PAGES

FLOOD DISCHARGE

1951 FLOOD - IMPROVED CONDITION



$$(87 + EV \cos 60.5^\circ) \cdot \frac{649}{1.5} = 821 - EV \sin 60.5^\circ$$

$$EV = 1463^k \text{ IMPROVED}$$

$$EV' = -1446 \text{ WITHOUT IMPROVEMENT}$$

$$\Delta V = \underline{17^k} \text{ REQUIRED WEIGHT OF ADDITIONAL SAND FILL FOR SSF OF 1.5}$$

1. BEARING PRESSURES:

2. RESULTANT IN MIDDLE THIRD

3. SLIDING FACTOR = 0.6

4. SSF = 1.5

$$\begin{aligned} \sigma_1 &= 1.48 \text{ ksf} \\ \sigma_2 &= 1.30 \text{ ksf} \end{aligned}$$

R.N.

NORMAL
OPERATING CONDITION

ASSUMPTIONS:

B. A = 16'

1. UPSTREAM WATER SURFACE
ELEV. 723.2

- 56.6

2. EXISTING SAND FILL 7' HIGH

3. UPSTREAM SEDIMENT HEIGHT 15'

4. TAILWATER ELEV. 690.6'

5. 8" TO 12" CONCRETE RESURFACING @
DOWNSTREAM FACE.

7. 2' OF ICE = 10^K PER FOOT OF CREST →

(PAGE 5 OF EM 1110-2-2200)

- ① 2.75 x 8.75 x 1
- ② 2.5 x 12.53 x 1
- ③ 2.17 x 13.3 x 1
- ④ 3.5 x 6.2 x 1/2 x
- ⑤ 2/3 x 12.5 x 11.02 x
- ⑥ 1.5 x 16.2 x 16
- ⑦ 5.9 x 4 x 1/2 x 16
- ⑧ 5.9 x 3.8 x 16
- ⑨ 46.8 x 3.0 x 16
- ⑩ 10.0 x 4.0 x 16
- ⑪ 1.0 x 1.5 x (16-2)
- ⑫ 6.0 x 1.0 x 0.5
- ⑬ 5.0 x 1.0 x 0.5
- ⑭ 8.5 x 4 x 2.4
- ⑮ 1.7 x 3.5 x 4
- ⑯ 2.75 x 3.9 x 4
- ⑰ 1.0 x 1.5 (16-2)
- ⑱ 1.0 x 1.5 (16-2)
- ⑲ 0.5 x 48.4 x 2
- ⑳ 6.25 x 4.7 x 1/2
- ㉑ 2.7 x 4.7 x 1/2
- ㉒ 33.7 x 4.7 x 2
- ㉓ 1.0 x 1.5 x (16-2)
- ㉔ 1.0 x 6.0 x 1.3
- ㉕ 1.0 x 1.5 x 16

R.N.M.

2/14

J1

3/24/75

118

183

690.6 (M.S.L.)

(KIP)

(FT-KIP)


(FEET)

1	2.75 x 8.15 x 16 x 0.15	57.95	49.8	2886
2	2.5 x 12.53 x 16 x 0.15	75.48	41.2	3110
3	2.17 x 13.33 x 16 x 0.15	69.42	31.4	2180
4	3.5 x 6.2 x 1/2 x 16 x 0.15	9.24	25.5	236
5	2/3 x 12.5 x 11.02 x 16 x 0.15	220.57	20.0	4411
6	1.5 x 16.0 x 16 x 0.15	58.32	9.5	554
7	5.9 x 4 x 1/2 x 16 x 0.15	28.32	4.1	116
8	5.9 x 3.8 x 16 x 0.15	53.31	2.9	156
9	46.8 x 3.0 x 16 x 0.15	337.00	29.2	9839
10	10.0 x 4.0 x 16 x 0.15	96.00	54.6	5242
11	1.0 x 1.5 x (16-2) x 0.15	5.15	19.7	59
12	6.0 x 1.0 x 0.33 x 0.15		0.30 18.4	6
13	5.0 x 1.0 x 0.33 x 0.15		0.25 32.0	10
14	8.0 x 4.0 x 42.4 x 0.15	56.22	28.6	1608
15	1.7 x 3.5 x 4.0 x 0.15	3.57	6.5	23
16	2.75 x 3.9 x 4.0 x 0.15	6.44	51.0	328
17	1.0 x 1.5 (16-22) x 0.15	3.11	26.7	83
18	1.0 x 1.5 (16-22) x 0.15	3.11	34.3	106
19	0.5 x 42.4 x 2.2 x 0.15	7.06	25.5	200
20	6.25 x 4.7 x 1/2 x 3.2 x 0.15	4.65	45.7	222
21	2.7 x 4.7 x 1/2 x 3.2 x 0.15	2.09	9.1	19
22	33.7 x 4.7 x 2.2 x 0.15	52.27	26.6	1401
23	1.0 x 1.5 x (16-2) x 0.15	3.15	29.2	92
24	1.0 x 6.0 x 1.5 x 0.15		0.30 28.3	8
25	1.0 x 1.5 (16-1.5) x 0.15	3.20	23.0	74
Sub-total		1154.27	0.85	24 32945

LOCK & DAM #1
STABILITY OF DAM

2

NORMAL CONDITION (CONT'D)



2.0' for 34
1.75' for 35
1.67' for 36
1.10' for 37


Areas:

$$\begin{aligned} 4 \times 2 &= 8.00 \\ \frac{4 + 2.2}{2} &= 3.10 \\ A_{34} &= 11.10 \end{aligned}$$

$$\begin{aligned} 4 \times 1.75 &= 7.0 \\ \frac{4 + 1.75}{2} &= 2.875 \\ A_{35} &= 7.9 \end{aligned}$$

$$\begin{aligned} 4 \times 1.67 &= 6.68 \\ \frac{4 + 1.67}{2} &= 2.835 \\ A_{36} &= 9.4 \end{aligned}$$

$$\begin{aligned} 4 \times 1.10 &= 4.4 \\ \frac{4 + 1.10}{2} &= 2.55 \\ A_{37} &= 7.15 \end{aligned}$$



$$4 \times 1.5 = 6$$

$$\frac{2.2 + 4}{2} \times \frac{1.5}{12} = 2.84$$

$$A_{14} = 8.84 \text{ ft}^2$$

- 5a 4.0 x 3.0 x 16 x
- 5b 0.5 x 7.0 x 16 x
- 5c 4.0 x 6.0 x 16 x
- 10a 1.5 x 1.5 x 16 x
- 26 1.0 x 1.5 x 16 x
- 27 10.5 x 8.5 x 16 x
- 28 4.4 x 3 x 16 x
- 29 19.3 x 3 x 16 x
- 30 9.7 x 7.3 x 16 x
- 31 3.8 x 7.3 x 16 x
- 32 6.0 x 7.3 x 16 x
- 33 3.0 x 6.0 x 16 x
- 34 11.1 x 5.5 x 16 x
- 35 3.9 x 12.5 x 16 x
- 36 9.4 x 13.3 x 16 x
- 37 7.15 x 4.0 x 16 x
- 38 5.75 x 8.0 x 16 x
- 39 8.75 x 0.4 x 16 x
- 40 } 7.0 x 14.6 x 16 x

W N A

0.174

11

3/24/75

119


184

230.6 CM.S...

4.0 x 5.0 x 16 x 0.15	76.80	12.1	1743	} Reduction in Parabolic Area - Stem Reduction - Beam
4.5 x 7.0 x 16 x 0.15	4.30	19.5	819	
4.0 x 5.0 x 16 x 0.15	4.1	17.0	490	
4.5 x 5.0 x 16 x 0.15	3.60	53.2	192	
4.0 x 1.5 x 16 x 0.15	3.4	19.4	62	} - Beam
4.5 x 3.0 x 16 x 0.15	4.30	39.4	431	
4.4 x 5.0 x 16 x 0.15	4.45	13.3	64	
4.0 x 2.0 x 16 x 0.15	4.38	24.3	1030	
4.7 x 2.5 x 16 x 0.15	4.51	21.8	237	} Wall opening
4.5 x 2.0 x 16 x 0.15	4.67	22.8	152	
4.0 x 1.5 x 16 x 0.15	10.53	18.6	196	
4.0 x 4.0 x 16 x 0.15	4.05	21.0	25	
4.1 x 5.0 x 16 x 0.15	4.15	18.0	679	} Wall opening
4.9 x 1.5 x 16 x 0.15	12.68	40.6	747	
4.0 x 1.5 x 16 x 0.15	4.20	29.1	558	
4.1 x 1.5 x 16 x 0.15	4.2	22.6	37	
4.0 x 1.5 x 16 x 0.15	15.15	18.2	191	} Wall opening
4.0 x 1.5 x 16 x 0.15	4.40	14.1	66	
4.0 x 1.5 x 16 x 0.15	4.42	10.2	202	
4.0 x 1.5 x 16 x 0.15	176.38	155.28	3324	
4.0 x 1.5 x 16 x 0.15	115.51	0.83	14	} Wall opening
4.0 x 1.5 x 16 x 0.15	135.05	150.10	3324	
sub total	1176.55	29.10	3324	
	1177		3324	

LOCKE DAM NO 1
STABILITY OF DAM

NORMAL CONDITION (CONT'D)



42	15.8
43	5.5
44	9.0
45	6.0
F	45 x 7
	5011

	Water
H	062.5
W ₁	22.23
W ₂	22.23
U ₁	32.5
U ₂	32.5

	Earth
	for
HS ₁₅	020.5
WS ₁₅	9.0

BEARING PRESSURES:

$$\bar{x}_{A'} = \frac{37885}{1726} + 4.13 = 26.08' \quad e = 30.4 - \bar{x}_{A'} = 4.32'$$

$$f_{A'} = \frac{1726}{972.8} \left(1 + \frac{6 \times 4.32}{60.8} \right) = 2.53$$

$$f_B = 1.677 \left(1 - 0.42 \right) = 1.02$$

$$\begin{aligned} 40 \times 6.0 \times 16 \times .088 &= 34 \times 546 = 1045 \\ 20 \times 10 \times 16 \times .088 &= 28 \times .87 = 25 \\ 3.3 \times 4.13 \times 16 \times .15 &= \frac{33}{95} \times 2 = +67 \\ \text{Wt. of core below} &= 95 \times 1803 = 1703 \text{ k} \end{aligned}$$

Ice
10 x
CONC.

R.N.M.

8/74

11

3/24/75

120

185

690.6 C.M.S.L

42	15.8 x 1.0 x 16 x 0.15	37.92	7.8	296	} Resurfacing
43	5.5 x 1.0 x 16 x 0.15	13.20	2.2	29	
44	9.0 x 0.83 x 16 x 0.15	17.93	14.6	262	
45	6.0 x 0.67 x 16 x 0.15	9.65	19.8	191	
		<u>78.70</u>		<u>778</u>	
F	45 x 7 x 14 x 0.12 cement-sand fill	526.4	29.0	15266	} 7 1/2 high fill

Water:

H	0.625 x 32.5 ² x 16 x 1/2	+ 528.13	10.83	5720	} Hydrostatic Weight of Water
W ₁	22.23 x 29.33 x 16 x 0.0625	326.00	44.53	14517	
W ₂	22.23 x 2.34 x 16 x 0.0625	52.02	55.48	2886	
U ₁	32.5 x 0.0625 x 4 x 16		130.0	54.65	
U ₂	32.5 x 0.0625 x 52.65 x 16 x 1/2		427.78	35.10	15015

Earth and sediment forces:

HS ₁₅	0.20 x 5 x 15 x 16 x 1/2	+ 37	5.0	185	} See Flood Condition
WS ₁₅	9.0 x 6.0 x 1/2 x 0.0625 x 16	29.0	53.65	1556	

Ice pressure:

10 x 16		160	32.5	5200	
sub-total 4 =	725.1	933.4	557.78	33225	33444 34225
conc. below el 690.6		95		1803	
	725.1	2439.8	713.9	36576	74463
		1726		37885	

32
1045
-25
+67
1803 'k'

(A) = 2.53
= ~~2.34~~ KSF
(B) = ~~1.00~~ KSF
= 1.02


LOCK & DAM #1
STABILITY OF DAM

2

NORMAL OPERATING CONDITION
(CONT'D)

SLIDING SAFETY FACTOR (SSF)

ASSUME APRON SLAB & PILE
RESISTANCE AS IN Pgs 1254



Above e
Below

$H_a = 2.03 \times 6$

$E_a = 0.31 \times 6$

$E_b = \frac{0.12 \times 6}{2}$

$S_a = 52.6 \times 6$

$C_a = 6 \times 4$

PILE RESI

APRON SUB
FRICTION
WITH 1.5
 $C_f = .1$

$$R = \sqrt{728^2 + 1837^2} = 1976$$

$$\theta = \tan^{-1} \frac{728}{1837} = 21.62^\circ$$

$$R_T = R \sin \frac{15.57^\circ}{6.05^\circ} = \frac{530^k}{1903^k} = .279$$

$$SSF = \frac{.649}{530/1903} = 2.33$$

R.N.M.

8/14

J1

3/24/75 121 186
690.6 - 684.6

Above elev. 690.6 → + 725 1631
Below 690.6:

$$H_a 2.03 \times 6 \times 16$$

$$E_a 0.31 \times 6 \times 16$$

$$F_b \frac{0.12 \times 6 \times 16}{2}$$

$$S_a \frac{52.6 \times 6 \times 16 \times 0.068}{2}$$

$$C_a 6 \times 4 \times 16 \times 0.088$$

$$\Delta H = 231 \left\{ \begin{array}{l} 195 \\ + 30 \\ + 6 \end{array} \right.$$

$$\Delta V = 206 \left\{ \begin{array}{l} 172 \\ 34 \end{array} \right.$$

PILE RESISTANCE - 160

APRON SUBMERGED WT. - 68

FRICTION RESISTANCE

WITH 1.5 SAFETY FACTOR

(f = 499)

P₈ 1254

P₉ 135

728^k


1837

LOCK AND DAM #1
STABILITY OF DAM

2

FLOOD DISCHARGE CONDITION

APRIL 1951 FLOOD } FORCES
APRIL 1965 FLOOD }



W_1 22.23 x
 W_2 22.23 x
 W_3 (1965) 11.5
 W_3 (1951) 7.8
 H_1 0.0625 x
 H_2 (1951) = 7.8
 H_2 (1965) = 11.5 x
 H_3 (1951) = 0.06
 H_3 (1965) = 0.06
 U_1 55.6 x 33
 U_2 4.5 x 55
 U_3 1.0 x 44
 U_1 30.6 x 15
 U_2 30.6 x 6.5
 U_3 25 x 22
 U_4 25 x 3.6
 U_5 1.0 x 40.0
 $HS15$ 0.0205 x
 $WS15$ 9 x 6 x 1/2 x
 F_1 (1951) 44 x 3
 F_1 (1965) 44 x 3
 F_2 47 x 3.7 x

R.N.M.

1/75

J1

3/24/75

122

187

→ (4)

$$W_1 \quad 22.23 \times 29.33 \times 1.0/2$$

326

44.5

14507

$$W_2 \quad 22.23 \times 2.34 \times 1.0$$

52

55.5

2886

$$W_3(1965) \quad 11.5 \times 31.7 \times 1.0$$

365

40.7

14056

$$W_3(1951) \quad 7.8 \times 31.7 \times 1.0$$

247

40.7

10053

$$H_1 \quad 0.0625 \times 32.5^2 \times 16 \times \frac{1}{2} + 528$$

10.8

5720

$$H_2(1951) = 7.8 \times 0.0625 \times 32.5 \times 16 + 254$$

16.3

4140

1951 Flood

$$H_2(1965) = 11.5 \times 0.0625 \times 31.7 \times 16 + 374$$

16.3

6096

1965 Flood

$$H_3(1951) = 0.0625 \times 48^2 \times 16/2 - 12$$

1.6

19

$$H_3(1965) = 0.0625 \times 28.4^2 \times 16/2 - 403$$

9.5

3820

$$U_1 \quad 55.6 \times 33.5 \times 1.0$$

1863

27.8

51791

$$U_2 \quad 4.5 \times 55.6 \times 1.0/2 \quad (1965)$$

125

37.0

4625

$$U_3 \quad 1.0 \times 44.0 \times 1.0$$

44

56.1

2468

$$U_1 \quad 30.6 \times 15.5 \times 16 \times 0.0625$$

474

15.3

7252

$$U_2 \quad 30.6 \times 6.5 \times \frac{1}{2} \times 1.0$$

99

20.4

2020

$$U_3 \quad 25 \times 22 \times 1.0$$

550

43.1

23705

$$U_4 \quad 25 \times 3.6 \times \frac{1}{2} \times 1.0$$

45

47.3

2129

$$U_5 \quad 1.0 \times 40.0 \times 1.0$$

40

56.1

2244

$$HS15 \quad 0.0205 \times 152 \times 16 \times \frac{1}{2} + 37$$

5.0

185

$$WS15 \quad 9 \times 6 \times \frac{1}{2} \times 0.0675 \times 16$$

29

53.7

$$F_1(1951) \quad 44 \times 3.3 \times 14 \times 0.12$$

244

29.0

$$F_1(1965) \quad 44 \times 3.3 \times 14 \times 0.13$$

264

29

$$F_2 \quad 47 \times 3.7 \times 13 \times 0.13$$

294

29

Uplift,
1965 Flood

Uplift,
1951 Flood,
see uplift
diagram

Sediment

1556 } $W=130, K=0.3$

7076 } Existing

7656 } Sand fill

8526 }

LOCK AND DAM NO. 1
STABILITY OF DAM

2

1965 5-1000

Determination of water
using weighted creep theory for
comparison with flow net method
13-page design of small dams.

And

h

28

11

..

2

2

2

11, 37 x 4

11. 3142.6

11, 34, 52.

114 1.1 x 41

184

44.

14

R.N.M.

1/75

11

2/25/75

123

35

$$H = 734.7 - 719 = 15.7'$$

$$L = 92 \quad p = \frac{L}{H} = 5.85$$

Point	Creep length, x	Uplift, $(L-x) \frac{1}{p} + 29.4$
a	0	44.1
b	21.	40.5
c	42	36.9
d	58.9	34.0
e	60.9	33.7
f	64.2	33.2
g	66.2	32.8
h	79.0	30.6
i	86.0	29.4
j	92.0	28.4

U ₁	37 x 4	148
U ₂	3 x 52.6 / 2	79
U ₃	34 x 52.6	1788
U ₄	7.1 x 4 1/2	14

$\Sigma U = 2029$ kips Creep theory

$\Sigma U = 2032$ kips Flow net method

\therefore USE FLOW NET

LOCK AND DAM NO. 1
STABILITY OF DAM

2

R.A

FLOOD DISCHARGE CONDITION

1965 FLOOD

Concrete
Resurfacing

Assumptions:

1. Max. flood el. 734.7 } April 1965
T.W. el. 719.0 }
2. Water inside Dam as high as T.W.
3. Uplift by Flow Net Method.

F₁
F₂

W₁
W₂

W₃

W₄

W₅

W₆

W₇

24 x 16 x 1/2 x
22 x 17.3 x 1/2
8.3 x 17.3 x
10.7 x 17.3 x

BEARING PRESSURES @ PTS. (A') & (B)

U₁

U₂

U₃


H₁

H₂

H₃

HS15

WS15



$$\bar{x}_{A'} = \frac{30757}{1215} + 4.13 = 29.44 \quad e = 30.4 - 29.44 = 0.96$$

$$f_{A'} = \frac{1215}{972.8} \left(1 + \frac{6 \times 0.96}{60.8} \right) = 1.36$$

$$f_{B'} = \frac{1215}{972.8} (1 - 0.96) = 1.13$$

Additional 2
below

A'

(A')

(B')

R. N. M.

1-13-75

J1

3/25/75

124

189

690.6

Concrete D.L.
Resurfacing

(Kips)



(Kips)

(feet)

34304 } From Norma
778 } Condition7656 } Sand Fill
8526 }14507 } Water, up-
2886 } stream
14856 }

1018 } Water, downstream

5828 } Water
2889 } inside
1215 }51791 }
4625 } Uplift
2468 }5720 } Lateral
6096 } hydrostatic
3820 }185 } Sediment
1556 }

1803

Additional submerged Concrete
below el. 690.6

95

536

3247

2032

120 1215

70885 99839
~~29040~~
30757

30+ 29.44 ft

+ 0.96

A'

1.36
 (A) = ~~1.19~~ KSF
 (B) = ~~1.12~~ KSF
 1.13


LOCK AND DAM NO. 1
STABILITY OF DAM

2

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY OF</u>	PROJECT <u>L & D #1</u>
	<u>BUTTRESS DAM</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>E.H.M.</u> CHECKED <u>JJ</u>	DATE <u>4/75</u> PAGE <u>125</u> OF <u> </u> PAGES

FLOOD DISCHARGE1965 FLOOD - EXISTING CONDITION

"SLIDING SAFETY FACTOR" AT PLANE AC
 UPLIFT BY FLOW NET METHOD
 ADDITIONAL FORCES BELOW EL. 690.6:



$$\Sigma H = 536 + 131 - 228 = 439^k \quad \Sigma V = 1120 + 206 = 1326^k$$

$$\alpha = 6.05^\circ$$

$$\begin{aligned} \Sigma H_N &= 439 \sin \alpha = 46^k \\ \Sigma V_N &= 1326 \cos \alpha = 1319^k \\ \Sigma H_N + \Sigma V_N &= 1365^k \end{aligned}$$

$$\begin{aligned} \Sigma H_T &= 439 \cos \alpha = 437^k \\ \Sigma V_T &= 1326 \sin \alpha = 140^k \\ \Sigma H_T - \Sigma V_T &= 297^k \end{aligned}$$

$$SSF = \frac{(\Sigma H_N + \Sigma V_N) (0.649)}{(\Sigma H_T - \Sigma V_T)} = \frac{1365 \times 0.649}{297} = 2.98$$

$$CHECK: R = \sqrt{439^2 + 1326^2} = 1398$$

$$\theta = \tan^{-1} \frac{43}{1326} = 18.32^\circ$$

$$\angle W = 12.27^\circ$$

$$R_T = R \sin W = \frac{297}{1398} = 0.217$$

$$R_N = R \cos W = \frac{1366}{1398}$$


$$SSF = \frac{0.55}{29/136} = 2.98$$

(NEXT SHEET IS P. 125a)

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILITY ANALYSIS</u>	PROJECT <u>L & D #1</u>
	<u>OF BUTTRESS DAM</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.H.M.</u> CHECKED <u>JI</u>	DATE <u>4/75</u> PAGE <u>125 a</u> OF <u> </u> PAGES

A. FRICTIONAL RESISTANCE OF SUBMERGED CONCRETE
DOWNSTREAM, 44.13 ft. from pt. "A".

(1)
B. CRITICAL SHEAR SECTION OF APRON, CHECKED FOR AL-
LOWABLE FORCE REACTION ASSUMING THAT THE CUT-
OFF-WALL, APRON (2) & PILES ACT AS A SOLID SUPPORT.



A. Submerged concrete wt downstream of point "A" :

$$\textcircled{a} \quad 2 \times 10 \times 16 \times .088 = 28$$

$$\textcircled{b} \quad 3 \times 4.13 \times 16 \times .088 = 17$$

$$\textcircled{c} \quad 40 \times 3 \times 16 \times .088 = 141$$

$$\begin{aligned} \textcircled{d} \quad & 3 \times 4 \times 16 = 192 \\ & - 2 \times 2 \times 3 \times 12 = -24 \\ & 3.5 \times 4 \times 2 = 28 \end{aligned} \quad \left. \begin{array}{l} \\ \\ \end{array} \right\} \times .088 = 17$$

$$F = 203 \times .499 = 101 \text{ K} \quad \leftarrow \quad 203 \text{ K} \downarrow$$

$$* F = \frac{203 \times .499}{1.5}$$

$$= 68 \text{ K}$$

(With 1.5
safety factor)

B. Shearing capacity of slab at section a-a :

$$t = .2'$$

$$L = 16'$$

$$t \times L = A = 2 \times 16 \times 144 = 4608 \text{ in}^2$$

$$v = \frac{V}{A} = 60 \text{ psi (Very conservative, } f'_c = 3.11 \text{ ksi)}$$

$$V = 60 \times 4608 = 276 \text{ K}$$

276 K shall be governed by pile resistance.


Assume 4' spacing e.w., 40 piles per 16' monolith

40 @ 4 K per pile = 160 kips. \therefore Use Q = 160 K


(PREVIOUS SHEET IS P. 125)

LOWER POOL
EL. 709

EL 734.0



17.61
b



LOCK AND DAM NO. 1
UPLIFT UNDERNEATH THE DAM

FLOOD DISCHARGE CONDITION


R. N.

1951 FLOOD

Purpose: Determination of Uplift
using weighted creep theory for
comparison with flow net
method."

Ref.: DESIGN OF SMALL DAMS
56.6'

$$L = (6 + 1)$$



(For other information,
see page 9)

U ₁	5.8 x 9.0 x 16
U ₂	5.8 x 1.3 x 1/2
U ₃	46.8 x 11.2 x 1/2
U ₄	46.8 x 7.1 x 1/2
U ₅	3.0 x 21.3 x 1/2
U ₆	40 x 1.0 x 1/2

R.N. M.

12/10/74

127 193

$$L = (6 + 17.5 + 2) \times 2 + \frac{80.75}{3} = 77.9' \quad H = 731 - 695.5 = 35.5'$$

$$r = \frac{L}{H} = 2.1943$$

$$U = \frac{L - r}{r} + 4.8$$

Point	Hor. Dist D (FE)	$\frac{D}{3}$	Vert. Dist. Creep. (ft)	α	LIFT (H. & H.D)
a					40.4
b	1.0	0.3	23.5	23.8	29.5
c	-	-	17.5	41.3	21.5
d	3.0	1.0		42.3	21.0
e	-	-	6.0	48.3	18.3
f	46.75	15.6		63.9	11.2
g	-	-	2.0	65.9	10.3
h	10.0	3.3		69.2	8.8
i	-	-	2.0	71.2	7.9
j	20.0	6.7		4.8	4.8

$$5.8 \times 9.0 \times 16 \times 0.0625$$

52

$$5.8 \times 1.3 \times \frac{1}{2} \times 1.0$$

4

$$46.8 \times 11.2 \times 1.0$$

524

$$46.8 \times 7.1 \times \frac{1}{2} \times 1.0$$

166

$$3.0 \times 21.3 \times 1.0$$

64

$$40 \times 1.0 \times 1.0$$

40

$$\Sigma U = 950$$

Creep theory

$$1208$$

Flow net Method

\therefore USE FLOW NET

LOCK AND DAM NO. 1
STABILITY OF DAM


2

FLOOD DISCHARGE

1951 FLOOD - EXISTING CONDITION

Assumptions:

1. Max. flood el. 731.
T.W. el. 695.5 (Lower pool el. 709)
2. Water inside Dam same level as relief hole outlets (697.4 ±)
3. Uplift by flow net method.



$$\bar{X}_{A'} = \frac{34113}{1335} + 4.13 = 29.68 \text{ ft} \quad e = 30.4 - \bar{X} = 0.72'$$

$$f_{(A')} = \frac{1335}{972.8} \left(1 + \frac{6 \times 0.72}{60.8} \right) = 1.47 \text{ KSF}$$

$$f_{(B)} = 1.374 (1 - 0.071) = 1.27 \text{ KSF}$$

Concr
Resur

F₁
F₂

W₁
W₂
W₃

U₁
U₂
U₃
U₄
U₅

H₁
H₂
H₃

HS15
WS15

Subm

A'

R.N.M.

12-10-74

J1

3/26/75

128

194

690.6

Concrete D.L.
Resurfacing1177
7934304 } From nori
778 } conditionF₁

244

7076 } Existing

F₂

294

8526 } sand fill

W₁

326

14507 } Water up

W₂

52

2886 } stream.

W₃

247

10053 }

U₁

474

7252

U₂

99

2020

U₃

550

23705

U₄

45

2129

U₅

40

2244

} Uplift,

H₁

+528

5720

H₂

+254

4140

H₃

-12

19

} Lateral
hydrostatic

HS15

+37

185

WS15

29

1556

} Sediment

Submerged conc. below
elev. 690.6

95

1803

807

2543 1208
1335 ↓47395 81508
34113

A'

29.68 ft

0.72'

A' = 1.47 ksf

B = 1.07 ksf

LOCK AND DAM NO. 1
STABILITY OF DAM

2


HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILITY OF
BUTTRESS DAM
COMPUTED R.N.M. CHECKED J

PROJECT L & D # 1
FILE NO. 800A
DATE 4/1/75 PAGE 129 OF PAGES

1951 FLOOD - EXISTING CONDITION

SLIDING SAFETY FACTOR AT PLANE AC ADDITIONAL FORCES BELOW EL. 690.6:



$$\Sigma H' = 807$$

$$H_a = (2.52 - 0.3)(16 \times 6) = +211$$

$$E_a = 0.31 \times 6 \times 16 = +30$$

$$E_b = 0.12 \times 6 \times 16 \times \frac{1}{2} = +6$$

$$\Sigma H = 1054$$

$$\Sigma V' = 1240^k$$

$$S_a = \text{---} \text{---} \text{---} \text{---} \text{---} 172$$

$$C_a = \text{---} \text{---} \text{---} \text{---} \text{---} 34$$

$$\Sigma V = 1446^k$$

(NEXT SHEET IS P. 129 a)

SEE CONTINUATION
ON PAGE 129 a

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILITY OF
BUTTRESS DAM
COMPUTED R.N.M. CHECKED ✓

PROJECT LOCK & DAM NO 1
FILE NO. 800 A
DATE 4/75 PAGE 129 OF 129 PAGES

BUTTRESS DAM
1951 FLOOD — EXISTING CONDITION

DETERMINATION OF FACTOR OF SAFETY AGAINST SLIDING,
(S.S.F.)

$$\boxed{(\sum H_N + \sum V_N) \cdot \frac{.649}{\text{S.S.F.}} = \sum H_T - \sum V_T}$$

$$\sum H^1 = 1054 \quad \sum H = 1054 - 228 = 826^k \quad \sum V = 1446^k$$

$$\left. \begin{array}{l} \sum H_N = 826 \sin 6.05^\circ = 87 \\ \sum V_N = 1446 \cos 6.05^\circ = 1438 \end{array} \right\} 1525$$

$$\left. \begin{array}{l} \sum H_T = 826 \cos 6.05^\circ = 821 \\ - \sum V_T = 1446 \sin 6.05^\circ = -152 \end{array} \right\} 669$$

$$\text{S.S.F.} = \frac{1524 \times .649}{66} = \underline{1.48}, < 1.5$$

CHECK:

$$R = \sqrt{826^2 + 1446^2} = 1665$$

$$\begin{aligned} \theta &= \tan^{-1} \frac{826}{1446} = 29.74^\circ \\ \alpha &= -6.05^\circ \\ \omega &= 23.69^\circ \end{aligned}$$

$$\frac{R_T}{R_N} = \frac{R \sin \omega}{R \cos \omega} = \frac{669^k}{1525^k} = .439$$

$$\text{S.S.F.} = 1.48$$

PREVIOUS SHEET IS P. 129

EARTHQUAKE CONDITION

(NORMAL CONDITION WITH EARTHQUAKE)

ASSUMPTIONS:


EARTHQUAKE INERTIA AND HYDRODYNAMIC

FORCES ADDED TO AND ICE PRESSURE

REMOVED FROM NORMAL OPERATING

CONDITION.

ACCELERATION IN UPSTREAM DIRECTION.



Normal c

Less Ice pr

P_{e2} Hydrod

Inertia

1	59 x
2	75 x
3	67 x
4	9 x
5	221 x
6	58 x
7	28 x
8	54 x
9	337 x
10	96 x
11	3 x
12	0.3
13	0.29
14	56
15	4
16	6 x
17	3 x

R. N. M.

8/74

Jl

3/26/75

130

197

690.6

Normal condition - - +725. 1631

36082

Less ice pressure - -160.

5200.
41282Pe₂ Hydrodynamic 3.6x16 + 57.6

13.0 749

Inertia forces:

1	59 x 0.1	+5.8	11.5	68
2	75 x 0.1	+7.5	18.3	137
3	67 x 0.1	+6.9	26.0	179
4	9 x 0.1	+0.9	31.0	28
5	221 x 0.1	+22.1	25.0	553
6	58 x 0.1	+5.8	14.2	82
7	28 x 0.1	+2.8	6.0	17
8	54 x 0.1	+5.4	2.0	108
9	337 x 0.1	+33.7	1.5	51
10	76 x 0.1	+9.6	5.0	48
11	3 x 0.1	+0.3	10.0	3
12	0.3 x 0.1	—	—	—
13	0.25 x 0.1	—	—	—
14	56 x 0.1	+5.6	4.0	22
15	4 x 0.1	0.4	4.5	2
16	6 x 0.1	0.6	5.0	3
17	3 x 0.1	0.3	10.0	3

167.1
13.0

2.53

LOCK & DAM #1
STABILITY OF DAM

2

EARTHQUAKE CONDITION (CONT'D)

Corps of Engineers' Formula

(Pg 5, "SMALL DAM DESIGN")

$$P_{e2} = \frac{2}{3} C_e \times y \sqrt{h y}$$

$$C_e = \frac{51}{\sqrt{1 - 0.72 \left(\frac{h}{1000 t_e} \right)^2}} = 51$$

t_e = Earthquake vibration pd. = 1 sec.

h = total height of dam = 32.5'

y = depth of water = y

$$P_{e2} = \frac{2}{3} \times 51 \times 0.1 \times 32.5 \sqrt{32.5} = \underline{3.6 \text{ K/ft.}}$$

18	3
19	7
20	5
21	2
22	52
23	3
-24	0
25	3
-5a	7
-5b	4
-5c	2
-10a	4
26	3
27	1
28	3
29	4
30	9
31	7
32	1
33	4
34	1
35	
36	
37	4
38	1
39	4

R.N.M.

8/74

J1

3/26/75

131

15

690.6


18	3 x 0.1	+ 0.3	10.0	3	
19	7 x 0.1	+ 0.7	5.7	4	
20	5 x 0.1	+ 0.5	7.5	4	
21	2 x 0.1	+ 0.2	7.5	2	
22	52 x 0.1	+ 5.2	8.5	44	
23	3 x 0.1	+ 0.3	18.0	5	
-24	0.3 x 0.1	-	-		
25	3 x 0.1	+ 0.3	18.0	5	
-5a	77 x 0.1	- 7.7	25.0		193
-5b	42 x 0.1	- 4.2	23.5		99
-5c	29 x 0.1	- 2.9	22.0		64
-10a	4 x 0.1	- 0.4	9.4		4
26	3 x 0.1	+ 0.3	18.0	5	
27	12 x 0.1	+ 1.2	13.5	16	
28	5 x 0.1	+ 0.5	13.5	7	
29	42 x 0.1	+ 4.2	15.0	63	
30	9 x 0.1	+ 0.9	21.3	19	
31	7 x 0.1	+ 0.7	22.7	16	
32	11 x 0.1	+ 1.1	21.0	23	
33	4 x 0.1	- 0.4	22.0		9
34	14 x 0.1	+ 1.4	9.2	13	369
35	19 x 0.1	+ 1.9	16.2	31	
36	19 x 0.1	+ 1.9	24.0	46	
37	4 x 0.1	+ 0.4	28.0	11	
38	11 x 0.1	+ 1.1	25.0	28	
39	4 x 0.1	+ 0.4	20.4	8	

LOCK & DAM #1
STABILITY OF DA

2

NORMAL OPERATING CONDITION

WITH EARTH QUAKE (CONTD)



BEARING PRESSURES:

$$\Sigma V = 1726 \text{ k} \quad \Sigma M_A = 40496 \text{ k}$$

$$\bar{X}_{A'} = \frac{40496}{1726} + 4.13 = 27.59'$$

$$f_{(A)} = \frac{1726}{972.8} \left(1 + \frac{6 \times 2.81}{60.8} \right) = 2.27$$

$$f_{(B)} = 1.77 \left(1 - \frac{6 \times 2.81}{60.8} \right) = 1.28$$

40 } 20
41 }

42 } 3
43 } 1
44 } 1
45 } 1

F 53

WSR 28

Sub

(A)

R N M

8/74

J/

3/26/75

132

199

690.6

40 } 41 }	20 x 0.1	+ 2.0	14.0	28
42	38 x 0.1	+ 3.8	14.7	56
43	13 x 0.1	+ 1.3	6.0	8
44	18 x 0.1	+ 1.8	25.6	46
45	10 x 0.1	+ 1.0 1.9	31.2	31 169
F	535 x 0.1	+ 53.5	6.5	345
WS ₁₅	29 x .1	+ 2.6	12.4	35

Submerged concrete
below el. 690.6

95

1803

804

1726

2958. 43454
40496

(A)

$$+ 4.13 = 27.59'$$

$$e' = 2.81'$$

$$(A') = 2.27 \text{ ksf}$$

$$(D) = 1.28 \text{ ksf}$$

LOCK & DAM #1
STABILITY OF DAM

2

EARTHQUAKE CONDITION

Sliding Safety Factor @ Plane AC

$$R = \sqrt{807^2 + 1837^2} = 2006^k$$

$$\tan^{-1} \theta = \tan^{-1} \frac{807}{1837} = 23.72^\circ$$
$$\delta = \frac{6.05^\circ}{.1767} = 34.25^\circ$$

$$R_f = R \sin \omega = 609^k$$

$$R_N = R \cos \omega = 1911^k$$

$$\text{Sliding factor} = \frac{609}{1911} = .319$$

$$SSF = \frac{.649}{.319} = 2.03$$

Below C

H_a
E_k
E_b
S_a
C_a

40 piles @ 4'

$$\frac{203^k \times .55}{1.5}$$

RNM

1/74

J1

3/26/75

153

200

690.6 - 684.6

804 1631

Below el. 690.6 :

H_a
E_a
E_b
S_a
C_a

} 1231

} 206

} From normal
condition

40 piles @ 4^k per pile - 160^k

$\frac{203^k \times .55}{1.5}$

- 68

Friction from
Weight of Apron

807 12

1837

LOCK AND DAM No. 1
STABILITY OF DAM

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	STABILITY OF	PROJECT	L ⁴ D ^B 1
		BUTRESS DAM	FILE NO.	800 A
	COMPUTED	DRD	CHECKED	RM
			DATE	4/76 PAGE 134 OF _____ PAGES

FLOOD DISCHARGE1951 FLOOD - IMPROVED CONDITION

MAX. FLOOD EL. 731. -

$$\Sigma M_A' = 34113 \text{ (Pg. 128)}$$

LOWER POOL EL 709. -

TAILWATER ELEVATION @ APRON 695.5'

$$\Sigma V = 1335^k \text{ (PAGE 128)}$$

$$M_{\text{FILL}} = \frac{17}{128} \times 476^k$$

$$\Sigma V = \frac{17}{128}^k \text{ (ADDITIONAL FILL - PAGE 135)}$$

$$\Sigma V = 1352^k \text{ (ABOVE ELEVATION 690.6)}$$

$$\Sigma H = 807^k \text{ (PAGE 128)}$$

$$\Sigma M_A = 34113 + 476 = 34589^k$$

FOR BEARING PRESSURES, $L' = 60.8'$ (from A' to B)


$$\bar{X}_{A'} = \bar{X}_A + 4.13', \text{ AREA} = 972.8$$

$$\bar{X}_{A'} = \frac{34589^k}{1352^k} + 4.13 = 29.71'$$

$$e_{A'} = 30.4 - 29.71 = 0.69 \text{ ft.}$$

$$f_{A'} = \frac{1352}{972.8} \left(1 + \frac{(6 \pm 0.69)}{60.8} \right) = 1.48 \text{ KSF}$$

$$f_B = \frac{1352}{972.8} \left(1 - \frac{(6 \pm 0.69)}{60.8} \right) = 1.30 \text{ KSF}$$



BUTTRESS DAM
1951 FLOOD - IMPROVED CONDITION

OF 1.5 (For other assumptions see page 70)

$\Sigma H' = 1054^k$ $\Sigma V = 1446^k$

$- \frac{228}{\Sigma H = 826^k}$

$\Sigma V = 1443^k$

ΣH_N ΣH_T ΣV_N ΣV_T

PROPOSED FILL
TOP OF EXIST-
ING FILL

40 PILES

203 K
(Submerged weight)

$\frac{160}{68} = \frac{228}{K}$

$\frac{X}{4} = \frac{K}{160}$

$\angle \alpha = 6.05^\circ$

SLIDING PLANE

$\frac{2.03 \times .499}{1.5}$

$$(\Sigma H_N + \Sigma V_N) \left(\frac{0.649}{1.5} \right) = \Sigma H_T - \Sigma V_T$$

$$(326 \pm 6.05 \pm \sqrt{(6.05)^2}) \left(\frac{0.64}{1.5} \right) = 826 \pm 6.05 \pm 24.01 \pm 6.05$$

$$(57 + 0.7944 \pm \sqrt{0.4326}) = 821 - 0.1053 \pm \sqrt{}$$


$$37.6 + 0.4302 = V = 321 - 0.1053 = V$$


$$0.035 \leq V = 783.4$$

$$\therefore \Sigma V = 1463 \text{ K}$$

EV FOR EXISTING CONDITION = 1446 K

REQUIRED WEIGHT OF ADDITIONAL FILL = 17^K
REQUIRED HEIGHT OF ADDITIONAL FILL = $0.25' +$





HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT COFFERDAMS

COMPUTED R.N.M.

CHECKED JL

PROJECT LOCK & DAM No. 1

FILE NO. 800 A

DATE 4/19/75 PAGE OF PAGES

UPSTREAM & DOWNSTREAM COFFERDAMS

UPSTREAM $H = 733 - 708 = 25$ FT

DOWNSTREAM $H = 705 - 674 = 31$ FT

STABILITY OF DOWNSTREAM COFFERDAM

1. OVERTURNING

$W = 130$ PCF

$$\sum M_c = 0, \text{ wh } B(B) = M$$

$$B = \frac{1}{\sqrt{6M}} \text{ wh } M = 28 \times .0625 \times 4.3 = 230$$

$$B_{\text{req'd}} = \frac{1}{\sqrt{6 \times 230}} = 18.5'$$

$$B_{\text{ave}} (\text{USED}) = \frac{A_1 + A_2}{Y}$$

$$= \frac{646.9 + 211.4}{33.87} = 25.31' > 18.5'$$

O.K.

2. VERTICAL SHEAR @ Φ

$$Q = \text{VERTICAL SHEAR PER FT STRIP}$$

$$= \frac{3}{2} \frac{M}{B} = \frac{1.5 \times 230}{25.31} = 13.63$$


$\Phi = 33^\circ$

$R = \text{SHEARING RESISTANCE}$

$$= \frac{Kwh^2}{2} (\tan \phi + .30 \times .9)$$

$$= \frac{.295 \times 1.3 \times 31^2}{2} (.92) = 16.95$$

$$F.S. = \frac{R}{Q} = \frac{16.95}{13.63} = \underline{1.24}$$



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT COFFERDAMS

COMPUTED P.N.M.

CHECKED J1

PROJECT L & D #1

FILE NO 800A

DATE 4/14/75 PAGE OF PAGES

DOWNSTREAM COFFERDAM (CONT'D)

3. INTERLOCK TENSION


UNIT PRESSURE @ BOTTOM

$$Kwh = .295 \times 0.13 \times 31 = 1.19 \text{ KSF}$$

$$P = Kwh(D) = 1.19 \times 28 = 33.32 \text{ K/ft}$$

$$T = \frac{P}{2} = 16.66 \text{ K/LIN. FT.}$$

$$= 1.4 \text{ K/LIN. INCH} < 8 \text{ K}$$



RECOMMENDED DESIGN STRESS IN INTERLOCKS OF
SECTION MP-101 = 8 K/LIN. INCH

UPSTREAM COFFERDAM WILL BE THE SAME AS

DOWNSTREAM COFFERDAM

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>CONSTRUCTION ENCLOSURE</u>	PROJECT <u>LED #1</u>
	COMPUTED <u>M.J.</u>	FILE NO. <u>800A</u>
	CHECKED <u>RNM</u>	DATE <u>12.74</u> PAGE <u>1</u> OF <u>5</u> PAGES

CONSTRUCTION ENCLOSURE STRUCTURE

DL & LL 30PSF

ASSUME SPACING OF SUPPORTS 10'-0" ON CTRS

LOAD ON TRUSS $10 \times 30 = 300 \text{ #/FT}$

$.30 \times 64 + .03 \times 64 = 19.20 + 1.92 = 21.12 \text{ k}$

USE #4 L12, ALLOWABLE LOAD 23.10 k

SPACING OF BMS 7'-4"

LOAD ON BMS $7.33 \times .03 = .22 \text{ k/}$

TOTAL LOAD /BM $.22 \times 10.0 = 2.2 \text{ k/BM}$

USE M6x4.4, ALLOWABLE LOAD 3.8 k/BM

USE 2x6 TIMBER C 2'-0" CTRS FOR ROOF CURF

BFAM C I-WALL

LOAD $\sim .35 \text{ k/FT}$

TOTAL LOAD ON BM $.35 \times 29 = 10.2 \text{ k}$

USE W16x26

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT	<u>CONSTRUCTION SHELTER</u>		PROJECT	<u>LED #1</u>	
				FILE NO.	<u>800A</u>	
	COMPUTED	<u>M.J.</u>	CHECKED	<u>RNM</u>	DATE	<u>12.5.74</u>
				PAGE	<u>2</u>	OF <u>2</u> PAGES

ESTIMATE OF MATERIALS FOR CONSTRUCTION SHELTER

ROOF TRUSSES (LT JOISTS)

$$64.0 \times 30 = 1.92^k / \text{TRUSS}$$

$$2 \times 54 \times 1.92 = 208^k$$

$$\text{SECONDARY TRUSSES \& BRIDGING} = 116^k \quad \text{SEE NEXT SH7.}$$

$$\text{TRUSS STEEL TOTAL} = 324.0^k$$

BEAMS 19 LINES \times 532' LG CABOT 7" CTRS

$$M6 \times 4.4 \quad 19 \times 532 \times .0044 = 45.0^k$$

$$WB \times 17 \quad 4 \times 532 \times .0170 = 36.2$$

$$W16 \times 26 \quad 29 \times .026 \times 54 = 40.8$$

$$\text{TOTAL} = 122.0^k$$

COLUMNS

$$12 \times 4 \times .017 \times 54 = 44.0^k$$

$$\text{BASES} \quad 4 \times 54 \times .025 = 6.0$$

$$\underline{\hspace{1cm}} \\ 50.0^k$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT CONSTRUCTION SHELTER
COMPUTED M.J. CHECKED RNM

PROJECT LED #1
FILE NO. 800A
DATE 1274 PAGE 3 OF PAGES

ESTIMATE OF MATERIALS FOR CONSTRUCTION SHELTER

ROOF TRUSSES (CONTD)

BRIDGING FOR TRUSSES

BLINDS OF BRIDGING 532' LG

$$8 \times 532 \times 2 \times 1.06 \times .005 = 45.2k$$

TRUSSES C BOTTOM OF JOISTS, ~ 100' SPACING, GREQ'D

$$6 \times 2 \times 64.0 \times .09 \text{ WT/FT} = 70.0k$$

BRIDGING AND SECONDARY TRUSSES TOTAL 116.0k

BRACING FOR COL'S

$$2 \times 18.8 \times .010 \times 54 = 21.0k \quad \text{CENTER BAY}$$

$$4 \times 17 \times 25.5 \times .005 = 9.0 \quad \text{AT 4 ROWS OF COL'S}$$

$$\text{BRACING TOTAL} = 30.0k$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>CONSTRUCTION SHELTER</u>	PROJECT <u>LSO #1</u>
	COMPUTED <u>M.J.</u>	FILE NO. <u>800A</u>
	CHECKED <u>BNM</u>	DATE <u>12.74</u> PAGE <u>4</u> OF <u> </u> PAGES

ESTIMATE OF STEEL FOR CONSTRUCTION SHELTER

ROOF TRUSSES	324k	SAY	164 TON
BEAMS	172k		86 "
BRACING L3	100k		50 "

TOTAL STEEL REQ'D 300 TON

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT QTO - SHELTER

PROJECT L & D #1

FILE NO 800 A

COMPUTED R.N.M. CHECKED JJ

DATE 4/14/75 PAGE 5 OF 5 PAGES

REHABILITATION OF BOTH LOCKS

LUMBER: 1x6 160x535 = 86,000 BOARDS FT

2x8 160x266x11.33 = 57,000 " "

TOTAL = 143,000 " "

TAR PAPER: (86,000)1.1 = 95,000 FT²



CANVASS:

12' HIGH ALL AROUND

(157 + 532) 2 x 12 — — — = 17,000

LOCK OPENINGS 56(28 + 57) 2 = 10,000

TOTAL 27,000 FT²



HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT QTO - SHELTER
REHABILITATION OF LAND LOCK
COMPUTED R.V.M. CHECKED JL

PROJECT L & DAM #1
FILE NO. 800A
DATE 4/10/75 PAGE 7 OF 9 PAGES

STEEL

① ROOF TRUSS (LJ BAR JOISTS)

$$1.92 \text{ K/TRUSS}, 1 \times 54 \times 1.92 = 104 \text{ K}$$

② BRIDGING

$$\begin{array}{l} \times 4 \text{ SETS/BAY,} \\ \times 53 \text{ BAYS} \\ \times 22' \text{ LONG/SET} \\ \times 5 \# / \text{FT} \end{array} \left. \vphantom{\begin{array}{l} \times 4 \text{ SETS/BAY,} \\ \times 53 \text{ BAYS} \\ \times 22' \text{ LONG/SET} \\ \times 5 \# / \text{FT} \end{array}} \right\} \text{-----} 23 \text{ K}$$

③ SECONDARY TRUSSES @ BOTTOM OF JOISTS SPACED 100' (6 REQ'D/LINE)

$$6 \times 64 \times .09 \text{ -----} 35 \text{ K}$$

④ MGX4.4 BEAMS (SPACED 7'-4")

$$\left(\frac{64}{7.33} + 1 \right) \times 530 \times 4.4 \text{ -----} 23 \text{ K}$$

⑤ W8X17 COLUMNS

$$12 \times 3 \times .017 \times 54 \text{ -----} 33 \text{ K}$$

$$⑥ \text{ W16X26 } 29 \times .026 \times 54 \text{ -----} 41 \text{ K}$$

$$⑦ \text{ W8X17 } 3 \times 10 \times 54 \times 17 \text{ -----} 28 \text{ K}$$

$$⑧ \text{ BASE PL } 3 \times 54 \times .025 \text{ -----} 41 \text{ K}$$

$$⑨ \text{ COL. BRACE, CENTER BAY } 2 \times 18.5 \times .010 \times 54 = 21 \text{ K}$$

$$⑩ \text{ 3 ROWS COL. } 3 \times 17 \times 25.5 \times .005 = 7$$

$$\text{TOTAL FOR STEEL} = \frac{319 (1.14) \times 180 \text{ TONS}}{2}$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>OTO - SHELTER</u>	PROJECT <u>LG D #1</u>
	<u>REHABILITATION OF LAND LOCK</u>	FILE NO <u>800A</u>
	COMPUTED <u>T.N.M.</u> CHECKED <u>J</u>	DATE <u>4/10/75</u> PAGE <u>8</u> OF <u>9</u> PAGES

LUMBER

$$1" \times 6" \quad 94 \times 535 \quad = \quad 51,000$$

$$2" \times 8" \quad 94 \times 266 \times 1.33 \quad = \quad \underline{34,000}$$

$$TOTAL = \underline{\underline{85,000}} \text{ BOARD FEET}$$

TAR PAPER

$$51,000 + (10\%) 51,000 = \underline{\underline{56,000}} \text{ FT}^2$$

CANVAS

12' HIGH ENCLOSURE

$$(93 + 532) 2 \times 12 \quad = \quad 15,000$$

LOCK OPENING

$$56 \times (28 + 57) \quad = \quad \underline{4,760}$$

$$TOTAL FOR CANVAS = \underline{\underline{20,000}} \text{ FT}^2$$

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>QTN - SHELTON</u>	PROJECT <u>LOCK & DAM #1</u>
	<u>PLAN 2 & PLAN 4</u>	FILE NO. <u>800 A</u>
	COMPUTED <u>R.N.M.</u> CHECKED <u>✓</u>	DATE <u>4/18/75</u> PAGE <u>9</u> OF <u>9</u> PAGES

SUMMARY

MATERIAL	REHABILITATION OF BOTH LOCKS	REHABILITATION OF LAND LOCK ONLY
STRUCTURAL STEEL, TONS	300	180
LUMBER, BF/1000	143	85
TAR PAPER SQ. FT.	95,000	56,000
CANVAS SQ. FT.	27,000	20,000

HARRIS ENGINEERING COMPANY CHICAGO	SUBJECT <u>UPPER GUIDE WALL</u>	PROJECT <u>LOCK AND DAM No. 1</u>
	<u>REMEDIAL PRESSURE GROUTING</u>	FILE NO. <u>800A</u>
	COMPUTER <u>VT</u> DRAWING <u>II</u>	DATE <u>APR 9 1975</u> PAGE <u>1</u> OF <u>1</u>

ASSUME THAT CRIBS IN MONTHS 8-13
NEED REMEDIAL GROUTING

LENGTH OF CRIBS $\Sigma L = 190$ FT
WIDTH OF CRIBS $= 18$ FT
HEIGHT OF ROCK FILL $= 11$ FT

ASSUME THAT HOLES WILL BE DRILLED
AT 6 FT SPACING IN 3 ROWS

$$n = \frac{190}{6} \times 3 = 95 \text{ holes}$$

$$\text{DEPTH OF DRILL HOLE} = 732.7 - 706.7 = 26 \text{ FT}$$

TOTAL LENGTH OF DRILLING

$$\Sigma L = 95 \times 26 = 2470 \text{ LIN FT}$$

DEPTH OF GROUTING - 11 FT EACH HOLE

ASSUME THAT GROUT TAKE IS 2 CU FT/LIN FT

TOTAL VOLUME OF GROUT

$$11 \times 2 \times 95 = 2090 \text{ CU FT}$$

COST

SET-UPS	96	$\times \$50$	=	4,800
DRILLING	2470	$\times \$10$	=	24,700
GROUTING	80	$\times \$160$	=	12,800

TOTAL \$42,300

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT REMOVAL OF BACKFILL
BEHIND LAND WALL
COMPUTED VT CHECKED JH

PROJECT LOCK AND DAM No. 1
FILE NO. 800A
DATE APR. 7 1938 PAGE OF PAGES

LENGTH FT	WIDTH FT	AREA FT ²
--------------	-------------	-------------------------

90	30	2,700
325	50	16,250
100	40	4,000

22,950

DEPTH = 10 FT

VOLUME $22,950 \times \frac{10}{27} = 8,500$

SAY 9,000 CY

UNIT COST \$ 3.00

COST $9,000 \times 3 = \$27,000$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILIZING OF LAND WALL
USING INCLINED ROCK ANCHORS
COMPUTED VT CHECKED JL

PROJECT LOCK AND DAM No. 1
FILE NO. 900A
DATE APR. 7 1975 PAGE L OF 1 PAGES

ALT. 1 1 3/8" SINGLE ANCHORS

Use 1 3/8" single anchors - 3 per monolith

Total number of anchors = 48

Length of anchor = 90 ft

Diameter of bore hole = 3 in

SET-UP

48 holes @ \$ 400.00 = \$ 19,200

DRILLING

Total length = 48 x 90 = 4,320 lin ft

Unit cost of 3" bore = \$ 10.00 per lin ft

Cost of drilling 4320 x 10.00 = \$ 43,200

PLACE, GROUT AND TENSION ANCHOR BARS

Anchor Bars

1 3/8" bars: $W = 5.05 \text{ lb/ft}$

Total length = 48 x 90 = 4,320 lin ft

Total weight = 4320 x 5.05 = 21,800 lbs

GROUT

$D = 3" = 0.25 \text{ ft}$

Volume of one hole $V = \frac{\pi}{4} \times 0.25^2 \times 90 = 4.41 \text{ cu-ft}$

Total volume $\Sigma V_{\text{holes}} = 48 \times 4.41 = 211 \text{ cu-ft}$

<u>Cost</u>	4320 x \$ 11.00	47,520
	<u>TOTAL</u>	<u>109,920</u>

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT STABILIZING OF LAND WALL
USING INCLINED ROCK ANCHORS
COMPUTED VT CHECKED JI

PROJECT LOCK AND DAM No. 1
FILE NO. 800 A
DATE Apr. 7 1952 PAGE 2 OF 2 PAGES

ALT. 2 1 1/4" DOUBLE ANCHORS

Use 1 1/4" double anchors - 2 per monolith

Total number of anchors = 32

Length of anchor = 95 feet

Diameter of bore hole = 4 in

SET-UP

32 holes @ \$ 400.00 = \$ 12,800

DRILLING

Total length = $32 \times 95 = 3,040$ lin ft

Unit cost of 4" bore = \$ 12.00 per lin ft

Cost of drilling $3040 \times 12.00 = \$ 36,480$

PLACE, GROUT AND TENSION ANCHOR BARS

Anchor Bars

1 1/4" bars: $w = 4.172$ lbs/ft

Total length = $32 \times 2 \times 95 = 6080$ lin ft

Total weight = $6080 \times 4.172 = 25,400$ lbs

Grout

$D = 4" = 0.33$ ft, $L = 95$ ft

Volume of one hole $V = \frac{\pi}{4} \times 0.33^2 \times 95 = 8.3$ cu ft

Total volume $\Sigma V_{net} = 32 \times 8.3 = 265$ cu ft

Cost $3040 \times \$ 15.00$ \$ 45,600
\$ 94,880

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>STABILIZING OF LAND WALL</u>	PROJECT <u>LOCK AND DAM No. 1</u>
	<u>USING INCLINED ROCK ANCHORS</u>	FILE NO. <u>800 A</u>
COMPUTED <u>VT</u>	CHECKED <u>JL</u>	DATE <u>Apr. 7, 1975</u> 3 OF <u>3</u> PAGES

ALT. 3 1 1/4" TRIPLE ANCHORS

Use 1 1/4" triple anchors - 2 per monolith
 Total number of anchors = 32
 Length of anchor = 100 feet
 Diameter of bore hole = 5 in

SET-UP

32 holes @ \$ 400.00 = \$ 12,800

DRILLING

Total length = $32 \times 100 = 3,200$ lin ft
 Unit cost of 5" bore = \$ 16.00 per lin ft
 Cost of drilling $3200 \times 16.00 = \$ 51,200$

PLACE, GROUT AND TENSION ANCHOR BARSAnchor Bars

1 1/4" bars, $n = 4,172$ lb./ft
 Total length = $32 \times 100 = 9,600$ lin ft
 Total weight = $9600 \times 4,172 = 40,050$ lbs

Grout

$D = 5" = 0.417$ ft; $L = 100$ ft
 Volume of one hole $V = \frac{\pi}{4} \times 0.417^2 \times 100 = 13.66$ cu-ft
 Total volume $\Sigma V_{\text{hole}} = 32 \times 13.66 = 437$ cu-ft

Cost 3200×20.00 \$ 64,000
\$ 128,000

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT INTERMEDIATE WALL
SHEAR KEYS, LOWER GATE MONO'S.
COMPUTED JL CHECKED VT

PROJECT LOCK AND DAM No 1
FILE NO. B00A
DATE 4/75 PAGE OF PAGES

VERTICAL KEYS (2.0' ϕ)

$$\text{SET-UP} \quad 4 \times \$250.- = 1,000$$

$$\text{DRILLING} \quad L = 4 \times 10.0' = 160.0'$$

$$160.0' \times \$140.- = 22,400$$

$$\text{CONCRETE} \quad V = \frac{3.14 \times 2.0^2}{4} \times 160.0' \times \frac{1}{27} = 19 \text{ c.y.}$$

$$19.0 \text{ c.y.} \times \$120.- = 2,280$$

$$25,680$$

HORIZONTAL KEYS (2.0' ϕ) $n = 8$

SET-UP AND DRILLING

$$8 \times \$1,200.- = 9,600$$

$$\text{CONCRETE} \quad V = \frac{3.14 \times 2.0^2}{4} \times 6.0' \times 8 \times \frac{1}{27} = 6 \text{ c.y.}$$

$$6 \text{ c.y.} \times \$120.- = 720$$

$$10,320$$

$$\text{TOTAL} \quad 25,680 + 10,320 = \$36,000$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT BACKFILL TO STABILIZE
DOWNSTREAM MOUNDINGS OF RIVER WALL
COMPUTED VT CHECKED JL

PROJECT LOCK AND DAM NO. 1
FILE NO. 800 A
DATE APR. 9, 1975 PAGE 1 OF 1 PAGES

FOR COMPUTATION PURPOSES ASSUME 3 DIFFERENT
GROUND ELEVATIONS

ELEVATION	DISTANCE FT
700	80
690	40
680	30

EXCAVATION

ASSUME A DEPTH OF 3 FEET
AREA 80×160

$$V = 80 \times 160 \times 3 \times \frac{1}{27} = 1420 \text{ CY MAX } 1500 \text{ CY}$$

IMPERVIOUS BLANKET

MIN. THICKNESS = 2 FEET


VOLUME = 1500 CY (EXCAVATION)

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT BATFILL TO STABILIZE
DOWNSTREAM MONOLITHS OF RIVER WALL
COMPUTED VT CHECKED JL

PROJECT LOCK AND DAM No. 1
FILE NO. 800 A
DATE APR. 8, 1975 PAGE 2 OF 2 PAGES

CROSS-SECTION: GROUND ELEV. 680



SCALE 0 10 20 FEET

Excavation	$105 \times 3 =$	315 ft ²
Impervious blanket	$85 \times 3 =$	255 ft ²
Random fill	$50 \times 24 =$	1200 ft ²
Gravel filter	$108 \times 15 =$	162 ft ²
Random rock fill	$110 \times 2 =$	220 ft ²
Selected large rocks	$115 \times 2.5 =$	287 ft ²

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT BACKFILL TO STABILIZE
DOWNSTREAM MONOLITHS OF RIVER WALL
COMPUTED VT CHECKED JL

PROJECT LOCK AND DAM NO. 1
FILE NO. 800 A
DATE APR. 8 1975 PAGE 3 OF 3

GROUND ELEV. 690

Excavation	$80 \times 3 =$	240 ft ²
Impervious blanket	$60 \times 3 =$	180 ft ²
Random fill	$38 \times 14 =$	532 ft ²
Gravel filter	$78 \times 1.5 =$	117 ft ²
Random rock fill	$83 \times 2 =$	166 ft ²
Selected large rocks	$90 \times 2.5 =$	225 ft ²

GROUND ELEV. 700

Excavation	$60 \times 3 =$	180
Impervious blanket	$40 \times 3 =$	120
Random fill	$26 \times 4 =$	104
Gravel filter	$52 \times 1.5 =$	78
Random rock fill	$57 \times 2 =$	114
Selected large rocks	$62 \times 2.5 =$	155

HARZA ENGINEERING COMPANY CHICAGO	SUBJECT <u>BACKFILL TO STABILIZE DOWN- STREAM MONOLITHS OF RIVER WALL</u>	PROJECT <u>LOCK AND DAM NO. 1</u>
	COMPUTED <u>VT</u> CHECKED <u> </u>	FILE NO. <u>800A</u> DATE <u>APR. 8, 1975</u> PAGE <u>4</u> OF <u>4</u> PAGES

EXCAVATION

$$\begin{aligned}
 315 \times 30 &= 9450 \text{ ft}^3 \\
 240 \times 40 &= 9600 \\
 180 \times 80 &= 14400
 \end{aligned}$$

$$33450 \text{ ft}^3 = 1238 \text{ cy}$$

$$\text{USE } 1.15 \times 1238 = 1424 \text{ cy} \rightarrow 1500 \text{ cy}$$

GRAVEL FILTER

$$\begin{aligned}
 255 \times 30 &= 7650 \text{ ft}^3 \\
 180 \times 40 &= 7200 \\
 120 \times 80 &= 9600
 \end{aligned}$$

$$24,450 \text{ ft}^3$$

$$\text{USE } 24,450 \times 1.15 \times \frac{1}{27} = 1041 \text{ cy} \rightarrow 1100 \text{ cy}$$

RANDOM FILL

$$\begin{aligned}
 1200 \times 30 &= 36,000 \text{ ft}^3 \\
 532 \times 40 &= 21,280 \\
 104 \times 90 &= 9,320
 \end{aligned}$$

$$65,600 \text{ ft}^3$$

$$\text{USE } 65,600 \times 1.15 \times \frac{1}{27} = 2794 \text{ cy} \rightarrow 3000 \text{ cy}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT BACKFILL TO STABILIZE DOWN-
STREAM MONOLITHS OF RIVER WALL
COMPUTED VT CHECKED JH

PROJECT LOCK AND DAM NO. 1
FILE NO. 800 A
DATE APR. 8 1935 PAGE 5 PAGES

GRAVEL FILTER

$$162 \times 30 = 4860 \text{ ft}^2$$

$$117 \times 40 = 4680$$

$$78 \times 80 = 6240$$

$$15780 \text{ ft}^2$$

$$\text{USE } 15780 \times 1.15 \times \frac{1}{27} = 875 \text{ cu} \rightarrow 700 \text{ cu}$$

RANDOM ROCK FILL

$$220 \times 30 = 6600 \text{ ft}^2$$

$$166 \times 40 = 6640$$

$$114 \times 80 = 9120$$

$$22360 \text{ ft}^2$$

$$\text{USE } 22360 \times 1.15 \times \frac{1}{27} = 952 \text{ cu} \rightarrow 1000 \text{ cu}$$

SELECTED LARGE CORN

$$285 \times 30 = 8550 \text{ ft}^2$$

$$225 \times 40 = 9000$$

$$175 \times 80 = 12400$$

$$29950$$

$$\text{USE } 29950 \times 1.15 \times \frac{1}{27} = 1275 \text{ cu} \rightarrow 1200 \text{ cu}$$

HARZA
ENGINEERING
COMPANY
CHICAGO

SUBJECT BACKFILL TO STABILIZE DOWN
STREAM MONUMENTS OF RIVER WALL
COMPUTED VT CHECKED JL

PROJECT LOCK AND DAM NO. 1
FILE NO. 800 A
DATE APR. 8 1975 PAGE 6 OF 6 PAGES

COST ESTIMATE

ITEM	QUANTITY	UNIT PRICE	CO.
Excavation	1500 cu	3.00	4,500
Gravel filter	1100	10.50	11,550
Random fill	3000	6.00	18,000
Gravel filter	700	10.50	7,350
Random rock fill	1000	16.00	16,000
Selected large rocks	1300	25.00	32,500
TOTAL			\$ 89,900